This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

+ *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.

+ *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.

+ *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.

+ *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at `http://books.google.com/`

38,960


ARTES
SCIENTIA
VERITAS
LIBRARY OF THE
UNIVERSITY OF MICHIGAN
E PLURIBUS UNUM
SI QUAERIS PENINSULAM AMOENAM
CIRCUMSPICE

Q
15
.F
1

FERGUSON's LECTURES

ON

SELECT SUBJECTS,

IN

MECHANICS,	OPTICS,
HYDROSTATICS	GEOGRAPHY,
HYDRAULICS,	ASTRONOMY, AND
PNEUMATICS,	DIALING.

WITH

NOTES AND AN APPENDIX,

ADAPTED TO THE PRESENT STATE OF THE ARTS AND SCIENCES,

By DAVID BREWSTER, A.M.

The Second Edition.

IN TWO VOLUMES,

WITH A QUARTO VOLUME OF PLATES.

Volume II.

EDINBURGH:

PRINTED FOR BELL & BRADFUTE, J. FAIRBAIRN; MUNDELL, DOIG, & STEVENSON, EDINBURGH; J. & A. DUNCAN, GLASGOW; AND T. OSTELL, AVE-MARIA LANE, LONDON.

1806.



CONTENTS OF THE SECOND VOLUME.

LECTURE X.

On the principles and art of Dialing.... Dialing by the globe.... Dialing lines.... Tables of the sun's place and declination.... Tables of the equation of Time.... Rules for finding the latitude of places. Page 1

LECTURE XI.

Of Dialing..... Dialing by trigonometry..... Babylonian and Italian dials.... On the placing of dials, and the regulation of time-keepers. 42

LECTURE XII.

Shewing how to calculate the mean time of any new or full moon, or eclipse, from the creation of the world, to the year of Christ 5800.... *Table of lunations.... Tables of the moon's mean motion from the sun, &c.* 71

SUPPLEMENT TO THE PRECEDING LECTURES BY THE AUTHOR.

MECHANICS.

Description of a new and safe crane with different powers 89
Description of a new and accurate pyrometer 94
On Barker's water-mill without wheel or trundle 97

HYDROSTATICS.

A machine for demonstrating that, on equal bottoms, the pressure of fluids is in proportion to their perpendicular height, without any regard to their quantities 100
A machine to be substituted in place of the common hydrostatic bellows 104
The cause of reciprocating springs, and of ebbing and flowing wells, explained 106

HYDRAULICS.

Account of Blakey's fire engine 109
Archimedes's screw engine 113
Quadruple pump-mill for raising water 114

DIALING.

Universal dialing cylinder 118
Cylindrical dial 122
To make three sun dials on three different planes 12
An universal dial on a plain cross 1
An universal dial by a terrestrial globe 1

APPENDIX, BY THE EDITOR.

MECHANICS,

On the construction of undershot water wheels for turning machinery. 139
On the construction of the mill course 140
On the water wheel and its float-boards 147
On the spur wheel and trundle. 154
On the formation, size, and velocity, of the millstone. 158
On the performance of undershot mills 163
On the construction of new mill-wright's tables. 167
Explanation and use of the tables. . 176
Method of measuring the velocity of water. 177
On horizontal mills. 179
On double corn mills. 184
On breast mills. 188
Practical remarks on the performance and construction of overshot water wheels. 192
On the method of computing the effective power of overshot wheels in turning machinery. . . . . ib.
On the performance of overshot and undershot mills. 194
On the formation of the buckets, and the proper velocity of overshot wheels 196
Besant's undershot wheel. 203
On Dr. Barker's mill. 205
Rules for its construction. 208

Account of an improvement in flour-mills. . 203
On the formation of the teeth of wheels, and the leaves of pinions. 210
On bevelled wheels, and the method of giving an epicycloidal form to their teeth. 230
On the formation of epicycloids, mechanically, and on the disposition of the teeth on the wheel's circumference. . . . 234
On the formation of cycloids, and epicycloids, by means of points, and the method of drawing lines parallel to them 236
On the formation of the teeth of rack-work, the wipers of stampers, &c. 241
On the nature and construction of windmills 258
Description of a windmill. . . . . . ib.
On the form and position of windmill sails. 266
To find the momentum of friction. . 270
To find the velocity of the wind. . . 271
On the effect of windmill sails. . . . 278
On horizontal windmills. 281
On wheel carriages. 295
On the formation of carriage wheels 296
On the position of the wheels. 312
On the line of traction, and the method by which horses exert their strength. 313
On the position of the centre of gravity, and the manner of disposing the load 317
On the thrashing machine. 321
On thrashing machines driven by water 323
On thrashing machines driven by horses 327
On the power of thrashing machines. 332
On the nature of friction, and the method of diminishing its effects in machinery. 334

On the nature and operation of fly wheels. . 353
On the construction and effect of machines. . 361
Description of a simple and powerful capstane 381
Account of an improvement upon the balance 385
A mechanical method of finding the centre of gravity. 387

HYDRAULICS.

On the steam engine. 389
On the power of steam engines, and the method of computing it. 411
Description of a water-blowing machine. . . 415
Description of Whitehurst's machine for raising water by its momentum, and Montgolfier's Hydraulic ram. 419

OPTICS.

On achromatic telescopes. 423
On achromatic object glasses, with tables of their radii of curvature. . . . . ib.
On achromatic eye pieces. 444
On the construction of optical instruments, with tables of their apertures, &c. and the method of grinding the lenses and mirrors of which they are composed. 452
On the method of grinding and polishing lenses. . . . . . ib.
On the method of grinding and polishing the mirrors of reflecting telescopes. 457
On the single microscope. 462
On the double microscope. 467
On the refracting telescope. 468
On the Gregorian telescope. 472
On the Cassegrainian telescope. 474
On the Newtonian telescope. 476

Description of a new fluid microscope, invented by the editor. 483
Account of an improvement on the camera obscura, and of a new portable one upon a large scale. 486

DIALING.

Description of an analemmatic dial which sets itself. 489
Description of a new dial, invented by Lambert 496

ASTRONOMY.

On the cause of the tides. 498

LECTURES

ON

SELECT SUBJECTS.

LECTURE X.

THE PRINCIPLES AND ART OF DIALING.

LECT. X. Preliminaries.

A DIAL is a plane, upon which lines are described in such a manner, that the shadow of a wire, or of the upper edge of a plate stile, erected perpendicularly on the plane of the dial, may shew the true time of the day.

The edge of the plate by which the time of the day is found, is called the stile of the dial, which must be parallel to the earth's axis; and the line on which the said plate is erected, is called the substile.

The angle included between the substile and stile, is called the elevation, or height, of the stile.

Those dials whose planes are parallel to the plane of the horizon, are called horizontal dials;

LECT. X. and those dials whose planes are perpendicular to the plane of the horizon, are called vertical, or erect, sun-dials.

Those erect dials, whose planes directly front the north or south, are called direct north or south dials; and all other erect dials are called decliners, because their planes are turned away from the north or south.

Those dials, whose planes are neither parallel nor perpendicular to the plane of their horizon, are called inclining, or reclining dials, according as their planes make acute or obtuse angles with the horizon; and if their planes are also turned aside from facing the south or north, they are called declining-inclining, or declining-reclining dials.

The intersection of the plane of the dial, with that of the meridian, passing through the stile, is called the meridian of the dial, or the hour-line of XII.

Those meridians, whose planes pass through the stile, and make angles of 15, 30, 45, 60, 75, and 90 degrees with the meridian of the place (which marks the hour-line of XII) are called hour-circles; and their intersections with the plane of the dial, are called hour-lines.

In all declining dials, the substile makes an angle with the hour-line of XII; and this angle is called the distance of the substile from the meridian.

The declining plane's difference of longitude, is the angle formed at the intersection of the stile and plane of the dial, by two meridians; one of which passes through the hour-line of XII, and the other through the substile.

LECT. X.

This much being premised concerning dials in general, we shall now proceed to explain the different methods of their construction.

PLATE XX. Fig. 2.

The universal principle on which *dialing* depends.

If the whole earth, *a P c p* were transparent, and hollow, like a sphere of glass, and had its equator divided into 24 equal parts by so many meridian semicircles, *a, b, c, d, e, f, g*, &c. one of which is the geographical meridian of any given place, as London, which is supposed to be at the point *a*; and if the hours of XII were marked at the equator, both upon that meridian and the opposite one, and all the rest of the hours in order on the rest of the meridians, those meridians would be the hour-circles of London; then, if the sphere had an opaque axis, as *P E p*, terminating in the poles *P* and *p*, the shadow of the axis would fall upon every particular meridian and hour, when the sun came to the plane of the opposite meridian, and would consequently shew the time at London, and at all other places on the meridian of London.

Horizontal dial.

If this sphere was cut through the middle by a solid plane *ABCD*, in the rational horizon of London, one half of the axis *EP* would be above the plane, and the other half below it; and if straight lines were drawn from the centre of the plane, to those points where the circumference is cut by the hour-circles of the sphere, those lines would be the hour-lines of a horizontal dial for London: for the shadow of the axis would fall upon each particular hour-line of the dial, when it fell upon the like hour-circle of the sphere.

Fig. 3.

If the plane which cuts the sphere be upright, at *AFCG*, touching the given place (London) at *F*, and directly facing the meridian of Lon-

LECT. X.

don, it will then become the plane of an erect direct south dial; and if right lines be drawn from its centre E, to those points of its circumference where the hour-circles of the sphere cut it, these will be the hour-lines of a vertical or direct south dial for London, to which the hours are to be set as in the figure (contrary to those on a horizontal dial), and the lower half $E\,p$ of the axis will cast a shadow on the hour of the day in this dial, at the same time that it would fall upon the like hour-circle of the sphere, if the dial plane was not in the way.

Vertical dial.

Inclining and reclining dials.

If the plane (still facing the meridian) be made to incline, or recline, by any given number of degrees, the hour-circles of the sphere will still cut the edge of the plane in those points to which the hour-lines must be drawn straight from the centre; and the axis of the sphere will cast a shadow on these lines at the respective hours. The like will still hold, if the plane be made to decline by any given number of degrees from the meridian, toward the east or west: provided the declination be less than 90 degrees, or the reclination be less than the co-latitude of the place: and the axis of the sphere will be a gnomon, or stile, for the dial. But it cannot be a gnomon, when the declination is quite 90 degrees, nor when the reclination is equal to the co-latitude; [1] because in these two cases, the axis has no elevation above the plane of the dial.

Declining dials.

And thus it appears, that the plane of every dial represents the plane of some great circle

[1] If the latitude be subtracted from 90 degrees, the remainder is called the co-latitude, or complement of the latitude.

upon the earth; and the gnomon the earth's axis, whether it be a small wire, as in the above figures, or the edge of a thin plate, as in the common horizontal dials. LECT. X.

The whole earth, as to its bulk, is but a point, if compared to its distance from the sun; and therefore, if a small sphere of glass be placed upon any part of the earth's surface, so that its axis be parallel to the axis of the earth, and the sphere have such lines upon it, and such planes within it, as above described, it will shew the hours of the day as truly as if it were placed at the earth's centre, and the shell of the earth were as transparent as glass.

But because it is impossible to have a hollow sphere of glass perfectly true, blown round a solid plane: or if it was, we could not get at the plane within the glass to set it in any given position; we make use of a wire sphere to explain the principles of dialing, by joining 24 semicircles together at the poles, and putting a thin flat plate of brass within it. Fig. 2, 3.

Dialing by the common terrestrial globe.

A common globe, of 12 inches diameter, has generally 24 meridian semicircles drawn upon it. If such a globe be elevated to the latitude of any given place, and turned about until any one of these meridians cuts the horizon in the north point, where the hour of XII is supposed to be marked, the rest of the meridians will cut the horizon at the respective distances of all the other hours from XII. Then, if these points of distance be marked on the horizon, and the globe be taken out of the horizon, and a flat board or plate be put into its place, even with the surface of the horizon, and if straight lines be drawn from the centre of the board to those

LECT. X. points of distance on the horizon which were cut by the 24 meridian semicircles, these lines will be the hour-lines of a horizontal dial for that latitude, the edge of whose gnomon must be in the very same situation that the axis of the globe was, before it was taken out of the horizon; that is, the gnomon must make an angle with the plane of the dial, equal to the latitude of the place for which the dial is made.

If the pole of the globe be elevated to the co-latitude of the given place, and any meridian be brought to the north point of the horizon, the rest of the meridians will cut the horizon in the respective distances of all the hours from XII, for a direct south dial, whose gnomon must make an angle with the plane of the dial, equal to the co-latitude of the place; and the hours must be set the contrary way on this dial, to what they are on the horizontal.

But if your globe have more than twenty-four meridian semicircles upon it, you must take the following method for making *horizontal and south dials by it.*

To construct a Horizontal dial. Elevate the pole to the latitude of your place, and turn the globe until any particular meridian (suppose the first) comes to the north point of the horizon, and the opposite meridian will cut the horizon in the south. Then, set the hour-index to the uppermost XII on its circle; which done, turn the globe westward until fifteen degrees of the equator pass under the brazen meridian, and then the hour-index will be at I (for the sun moves fifteen degrees every hour) and the first meridian will cut the horizon in the number of degrees from the north point, that I is distant from XII. Turn on until other 15 degrees of the equator pass under the brazen

meridian, and the hour-index will then be at II, and the first meridian will cut the horizon in the number of degrees that II is distant from XII: and so, by making 15 degrees of the equator pass under the brazen meridian for every hour, the first meridian of the globe will cut the horizon in the distances of all the hours from XII to VI, which is just 90 degrees; and then you need go no farther, for the distances of XI, X, IX, VIII, VII, and VI, in the forenoon, are the same from XII, as the distances of I, II, III, IV, V, and VI, in the afternoon; and these hour-lines continued through the centre, will give the opposite hour-lines on the other half of the dial: but no more of these lines need be drawn than what answer to the sun's continuance above the horizon of your place on the longest day, which may be easily found by the twenty-sixth problem of the foregoing lecture. LECT. X.

Thus to make a horizontal dial for the latitude of London, which is $51\frac{1}{2}$ degrees north, elevate the north pole of the globe $51\frac{1}{2}$ degrees above the north point of the horizon, and then turn the globe, until the first meridian (which is that of London on the English terrestrial globes) cuts the north point of the horizon, and set the hour-index to XII at noon.

Then, turning the globe westward until the index points successively to I, II, III, IV, V, and VI, in the afternoon; or until 15, 30, 45, 60, 75, and 90 degrees of the equator pass under the brazen meridian, you will find that the first meridian of the globe cuts the horizon in the following number of degrees from the north toward the east, viz. $11\frac{1}{2}$, $24\frac{1}{4}$, $38\frac{1}{12}$, $53\frac{1}{4}$, $71\frac{1}{15}$, and 90; which are the respective distances of

LECT. X. the above hours from XII upon the plane of the horizon.

PLATE XXI. Fig. 1. To transfer these, and the rest of the hours, to a horizontal plane, draw the parallel right lines *a c* and *b d* upon that plane, as far from each other as is equal to the intended thickness of the gnomon or stile of the dial, and the space included between them will be the meridian or twelve o'clock line on the dial. Cross this meridian at right angles with the six o'clock line *g h*, and setting one foot of your compasses in the intersection *a*, as a centre, describe the quadrant *g e* with any convenient radius or opening of the compasses: then, setting one foot in the intersection *b*, as a centre, with the same radius describe the quadrant *f h*, and divide each quadrant into 90 equal parts or degrees, as in the figure.

Because the hour-lines are less distant from each other about noon, than in any other part of the dial, it is best to have the centres of these quadrants at a little distance from the centre of the dial-plane, on the side opposite to XII, in order to enlarge the hour-distances thereabout under the same angles on the plane. Thus, the centre of the plane is at *C*, but the centres of the quadrants at *a* and *b*.

Lay a ruler over the point *b* (and keeping it there for the centre of all the afternoon hours in the quadrant *f h*), draw the hour-line of I, through $11\frac{1}{3}$ degrees in the quadrant; the hour-line of II, through $24\frac{1}{4}$ degrees; of III, through $38\frac{1}{12}$ degrees; IIII, through $53\frac{1}{2}$; and V, through $71\frac{1}{15}$: and because the sun rises about four in the morning, on the longest days at London, continue the hour-lines of IIII and V, in the afternoon, through the centre *b* to the opposite

3

side of the dial.—This done, lay the ruler to the centre *a*, of the quadrant *e g*, and through the like divisions or degrees of that quadrant, viz. $11\frac{1}{3}$, $24\frac{1}{4}$, $38\frac{1}{12}$, $53\frac{1}{2}$, and $71\frac{1}{15}$, draw the forenoon hour-lines of XI, X, IX, VIII, and VII; and because the sun does not set before eight in the evening on the longest days, continue the hour-lines of VII and VIII in the forenoon, through the centre *a*, to VII and VIII in the afternoon; and all the hour-lines will be finished on this dial, to which the hours may be set, as in the figure. LECT. X.

Lastly, through $51\frac{1}{2}$ degrees of either quadrant, and from its centre, draw the right line *a g* for the hypothenuse or axis of the gnomon *a g i*; and from *g*, let fall the perpendicular *g i*, upon the meridian line *a i*, and there will be a triangle made, whose sides are *a g*, *g i*, and *i a*. If a plate, similar to this triangle, be made as thick as the distance between the lines *a c* and *b d*, and set upright between them, touching at *a* and *b*, its hypothenuse *a g* will be parallel to the axis of the world, when the dial is truly set; and will cast a shadow on the hour of the day.

N. B. The trouble of dividing the two quadrants may be saved, if you have a scale with a line of chords upon it, such as that on the right hand of the plate; for if you extend the compasses from 0 to 60 degrees of the line of chords, and with that extent, as a radius, describe the two quadrants upon their respective centres, the above distances may be taken with the compasses upon the line, and set off upon the quadrants.

To make an erect direct south dial. Elevate the pole to the co-latitude of your place, and proceed in all respects as above taught for the *To construct an erect direct south dial.*

LECT. X.

horizontal dial, from VI in the morning to VI in the afternoon, only the hours must be reversed, as in the figure; and the hypothenuse *a g*, of the gnomon *a g f*, must make an angle with the dial-plane, equal to the co-latitude of the place. As the sun can shine no longer on this dial than from six in the morning till six in the evening, there is no occasion for having any more than twelve hours upon it. [a]

Fig. 2.

To construct an *erect declining dial.*

To make an erect dial, declining from the south toward the east or west. Elevate the pole to the latitude of your place, and screw the quadrant of altitude to the zenith. Then, if your dial declines toward the east (which we shall suppose it to do at present) count on the horizon the degrees of declination, from the east point toward the north, and bring the lower end of the quadrant to that degree of declination at which the reckoning ends. This done, bring any particular meridian of your globe (as suppose the first meridian) directly under the graduated edge of the upper part of the brazen meridian, and set the hour-index to XII at noon. Then, keeping the quadrant of altitude at the degree of declination in the horizon, turn the globe eastward on its axis, and observe the degrees cut by the first meridian in the quadrant of altitude (counted from the zenith) as the hour-index comes to XI, X, IX, &c. in the forenoon, or as 15, 30, 45, &c. degrees of the equator pass under the brazen meridian at these hours respectively; and the degrees then cut in the

[a] A new and very simple geometrical method of constructing sun-dials may be seen in our author's Mechanical Exercises, p. 94.—Ed.

quadrant by the first meridian, are the respective distances of the forenoon hours from XII on the plane of the dial —Then, for the afternoon hours, turn the quadrant of altitude round the zenith until it comes to the degree in the horizon opposite to that where it was placed before; namely, as far from the west point of the horizon toward the south, as it was set at first from the east point toward the north; and turn the globe westward on its axis, until the first meridian comes to the brazen meridian again, and the hour-index to XII: then, continue to turn the globe westward, and as the index points to the afternoon hours I, II, III, &c. or as 15, 30, 45, &c. degrees of the equator pass under the brazen meridian, the first meridian will cut the quadrant of altitude in the respective number of degrees from the zenith, that each of these hours is from XII on the dial.—And note, that when the first meridian goes off the quadrant at the horizon, in the forenoon, the hour-index shews the time when the sun will come upon this dial: and when it goes off the quadrant in the afternoon, the index will point to the ime when the sun goes off the dial. LECT. X.

Having thus found all the hour-distances from XII, lay them down upon your dial-plate, either by dividing a semicircle into two quadrants of 90 degrees each (beginning at the hour-line of XII) or by the line of chords, as above directed.

In all declining dials, the line on which the stile or gnomon stands (commonly called the *substile line)* makes an angle with the twelve o'clock line, and falls among the forenoon hour-lines, if the dial declines toward the east; and among the afternoon hour-lines, when

LECT. X. the dial declines toward the west; that is, to the left hand from the twelve o'clock line in the former case, and to the right hand from it in the latter.

To find the distance of the substile from the twelve o'clock line; if your dial declines from the south toward the east, count the degrees of that declination in the horizon from the east point toward the north, and bring the lower end of the quadrant of altitude to that degree of declination where the reckoning ends: then turn the globe until the first meridian cuts the horizon in the like number of degrees, counted from the south point toward the east; and the quadrant and first meridian will then cross one another at right angles, and the number of degrees of the quadrant, which are intercepted between the first meridian and the zenith, is equal to the distance of the substile line from the twelve o'clock line; and the number of degrees of the first meridian, which are intercepted between the quadrant and the north pole, is equal to the elevation of the stile above the plane of the dial.

If the dial declines westward from the south, count that declination from the east point of the horizon toward the south, and bring the quadrant of altitude to the degree in the horizon at which the reckoning ends; both for finding the forenoon hours, and the distance of the substile from the meridian: and for the afternoon hours, bring the quadrant to the opposite degree in the horizon, namely, as far from the west toward the north, and then proceed in all respects as above.

Thus, we have finished our declining dial; and in so doing, we made four dials, viz.

LECT. X.

1, A north dial, declining northward by the same number of degrees. 2, A north dial, declining the same number west. 3, A south dial, declining east. And, 4, A south dial, declining west. Only, placing the proper number of hours, and the stile or gnomon respectively, upon each plane. For, (as above mentioned) in the south-west plane, the substile line falls among the afternoon hours; and in the south-east, of the same declination among the forenoon hours, at equal distances from XII. And so, all the morning hours on the west decliner will be like the afternoon hours on the east decliner; the south-east decliner will produce the north-west decliner; and the south-west decliner, the north-east decliner, by only extending the hour-lines, stile and subtile, quite through the centre: the axis of the stile, (or edge that casts the shadow on the hour of the day) being in all dials whatever parallel to the axis of the world, and consequently pointing toward the north pole of the heaven in north latitudes, and toward the south pole, in south latitudes. *See more of this in the following lecture.*

An easy method for constructing of a dial.

But because every one who would like to make a dial, may perhaps not be provided with a globe to assist him, and may probably not understand the method of doing it by logarithmic calculation; we shall shew how to perform it by the plain dialing lines, or scale of latitudes and hours; such as those on the right hand of Fig. 4, in Plate XXI, or at the top of Plate XXII, and which may be had on scales commonly sold by the mathematical instrument makers.

This is the easiest of all mechanical methods, and by much the best, when the lines are truly

LECT. X. divided: not only the half hours and quarters may be laid down by all of them, but every fifth minute by most, and every single minute by those where the line of hours is a foot in length.

Fig. 3. Having drawn your double meridian line *a b*, *c d*, on the plane intended for a horizontal dial, and crossed it at right angles by the six o'clock line *f e* (as in Fig. 1), take the latitude of your place with the compasses, in the scale of latitudes, and set that extent from *c* to *e*, and from *a* to *f*, on the six o'clock line: then, taking the whole six hours between the points of the compasses in the scale of hours, with that extent set one foot in the point *e*, and let the other foot fall where it will upon the meridian line *c d*, as at *d*. Do the same from *f* to *b*, and draw the right lines *e d* and *f b*, each of which will be equal in length to the whole scale of hours. This done, setting one foot of the compasses in the beginning of the scale at XII, and extending the other to each hour on the scale, lay off these extents from *d* to *e* for the afternoon hours, and from *b* to *f* for those of the forenoon: this will divide the lines *d e* and *b f* in the same manner as the hour-scale is divided, at 1, 2, 3, 4, 5, and 6, on which the quarters may also be laid down, if required. Then, laying a ruler on the point *c*, draw the first five hours in the afternoon, from that point, through the dots at the numeral figures 1, 2, 3, 4, 5, on the line *d e*; and continue the lines of IIII and V through the centre *c* to the other side of the dial, for the like hours of the morning; which done, lay the ruler on the point *a*, and draw the last five hours in the forenoon through the dots 5, 4, 3, 2, 1, on the line *f b*; continuing the hour-lines of VII

and VIII through the centre *a* to the other side of the dial, for the like hours of the evening; and set the hours to their respective lines as in the figure. Lastly, make the gnomon the same way as taught above for the horizontal dial, and the whole will be finished. LECT. X.

To make an erect south dial, take the co-latitude of your place from the scale of latitudes, and then proceed in all respects for the hour-lines, as in the horizontal dial; only reversing the hours, as in Fig. 2; and making the angle of the stile's height equal to the co-latitude.

I have drawn out a set of dialing lines upon the top of Plate XXII large enough for making a dial of nine inches diameter, or more inches if required; and have drawn them tolerably exact for common practice, to every quarter of an hour. This scale may be cut off from the plate, and pasted upon wood, or upon the inside of one of the boards of this book; and then it will be somewhat more exact than it is on the plate, for being rightly divided upon the copper-plate, and printed off on wet paper, it shrinks as the paper dries; but when it is wetted again, it stretches to the same size as when newly printed; and if pasted on while wet, it will remain of that size afterwards.

But lest the young dialist should have neither globe nor wooden scale, and should tear or otherwise spoil the paper one in pasting, we shall now shew him how he may make a dial without any of these helps. Only, if he has not a line of chords, he must divide a quadrant into 90 equal parts or degrees for taking the proper angle of the stile's elevation, which is easily done.

LECT. X.

Fig. 4.

Horizontal dial.

With any opening of the compasses, as $Z L$, describe the two semicircles $L F k$ and $L Q k$, upon the centres Z and z, where the six o'clock line crosses the double meridian line, and divide each semicircle into 12 equal parts, beginning at L; though, strictly speaking, only the quadrants from L to the six o'clock line need be divided; then connect the divisions which are equidistant from L, by the parallel lines KM, IN, HO, GP, and FQ. Draw VZ for the hypothenuse of the stile, making the angle VZE equal to the latitude of your place; and continue the line VZ to R. Draw the line Rr parallel to the six o'clock line, and set off the distance ak from Z to Y, the distance bI from Z to X, cH, from Z to W, dG from Z to T, and eF from Z to S. Then draw the lines Ss, Tt, Ww, Xx, and Yy each parallel to Rr. Set off the distance yY from a to 11, and from f to 1: the distance xX from b to 10, and from g to 2; wW from c to 9, and from h to 3; tT from d to 8, and from i to 4; sS from e to 7, and from n to 5. Then, laying a ruler to the centre Z, draw the forenoon hour lines through the points 11, 10, 9, 8, 7; and laying it to the centre z, draw the afternoon lines through the points 1, 2, 3, 4, 5; continuing the forenoon lines of VII and VIII through the centre Z, to the opposite side of the dial, for the like afternoon hours; and the afternoon lines IIII and V through the centre z, to the opposite side, for the like morning hours. Set the hours to these lines as in the figure, and then erect the stile or gnomon, and the horizontal dial will be finished.

South dial.

To construct a south dial, draw the lines VZ, making an angle with the meridian ZL equal to the co-latitude of your place, and pro-

ceed in all respects as in the above horizontal dial for the same latitude, reversing the hours as in Fig. 2, and making the elevation of the gnomon equal to the co-latitude. LECT. X.

Perhaps it may not be unacceptable to explain the method of constructing the dialing lines, and some others, which is as follows.

With any opening of the compasses, as *E A*, according to the intended length of the scale, describe the circle *ADCB*, and cross it at right angles by the diameters *CEA* and *DEB*. Divide the quadrant *AB* first into nine equal parts, and then each part into 10; so shall the quadrant be divided into 90 equal parts or degrees. Draw the right line *AFB* for the chord of this quadrant, and setting one foot of the compasses in the point *A*, extend the other to the several divisions of the quadrant, and transfer these divisions to the line *AFB* by the arcs, 10 10, 20 20, &c. and this will be a line of chords divided into 90 unequal parts; which, if transferred from the line back again to the quadrant, will divide it equally. It is plain by the figure, that the distance from *A* to 60 in the line of chords, is just equal to *AE*, the radius of the circle from which that line is made; for if the arc 60 60 be continued, of which *A* is the centre, it goes exactly through the centre *E* of the arc *AB*. PLATE XXII. Fig. 1. *Dialing lines*, how constructed.

And therefore, in laying down any number of degrees on a circle, by the line of chords, you must first open the compasses, so as to take in just 60 degrees upon that line, as from *A* to 60; and then, with that extent, as a radius, describe a circle which will be exactly of the same size with that from which the line was divided:

LECT. X

which done, set one foot of the compasses in the beginning of the chord line, as at *A*, and extend the other to the number of degrees you want upon the line, which extent, applied to the circle, will include the like number of degrees upon it.

Divide the quadrant *C D* into 90 equal parts, and from each point of division draw right lines as *i*, *k*, *l*, &c. to the line *C E*; all perpendicular to that line, and parallel to *D E*, which will divide *E C* into a line of sines; and although these are seldom put among the dialing lines on a scale, yet they assist in drawing the line of latitudes. For, if a ruler be laid upon the point *D*, and over each division in the line of sines, it will divide the quadrant *C B* into 90 unequal parts, as *B a*, *a b*, &c. shewn by the right lines 10 *a*, 20 *b*, 30 *c*, &c. drawn along the edge of the ruler. If the right line *B C* be drawn, subtending this quadrant, and the nearest distances *B a*, *B b*, *C c*, &c. be taken in the compasses from *B*, and set upon this line in the same manner as directed for the line of chords, it will make a line of latitudes *B C*, equal in length to the line of chords *A B*, and of an equal number of divisions, but very unequal as to their lengths.

Draw the right line *D G A*, subtending the quadrant *D A*; and parallel to it, draw the right line *r s*, touching the quadrant *D A* at the numeral figure 3. Divide this quadrant into six equal parts, as 1, 2, 3, &c. and through these points of division draw right lines from the centre *E* to the line *r s*, which will divide it at the points where the six hours are to be placed, as in the figure. If every sixth part of the quadrant be subdivided into four equal parts, right lines drawn from the centre through these

points of division, and continued to the line *r s*, will divide each hour upon it into quarters. LECT. X.

In Fig. 2, we have the representation of a portable dial, which may be easily drawn on a card, and carried in a pocket-book. The lines *a d*, *a b*, and *b c*, of the gnomon must be cut quite through the card; and as the end *a b* of the gnomon is raised occasionally above the plane of the dial, it turns upon the uncut line *c d* as on a hinge. The dotted line *A B* must be slit quite through the card, and the thread must be put through the slit, and have a knot tied behind, to keep it from being easily drawn out. On the other end of this thread is a small plummet *D*, and on the middle of it a small bead for shewing the time of the day. *A dial on a card.* Fig. 2.

To rectify this dial, set the thread in the slit right against the day of the month, and stretch the thread from the day of the month over the angular point where the curve lines meet at XII; then shift the bead to that point on the thread, and the dial will be rectified.

To find the hour of the day, raise the gnomon (no matter how much or how little) and hold the edge of the dial next the gnomon toward the sun, so as the uppermost edge of the shadow of the gnomon may just cover the *shadow line*; and the bead then playing freely on the face of the dial, by the weight of the plummet, will shew the time of the day among the hour-lines, as is forenoon or afternoon.

To find the time of sun rising and setting, move the thread among the hour-lines, until it either covers some one of them, or lies parallel betwixt any two; and then it will cut the time of sun-rising among the forenoon hours, and of sun-setting among the afternoon hours, on that

LECT. X. day of the year for which the thread is set in the scale of months.

To find the sun's declination, stretch the thread from the day of the month over the angular point at XII, and it will cut the sun's declination, as it is north or south, for that day, in the arched scale of north and south declination.

To find on what day the sun enters the signs: when the bead, as above rectified, moves along any of the curve lines which have the signs of the zodiac marked upon them, the sun enters those signs on the days pointed out by the thread in the scale of months.

The construction of this dial is very easy, especially if the reader compares it all along with Fig. 3, as he reads the following explanation of that figure.

Fig. 3. Draw the occult line AB parallel to the top of the card, and cross it at right angles with the six o'clock line ECD; then upon C, as a centre, with the radius CA, describe the semicircle AEL, and divide it into 12 equal parts (beginning at A), as Ar, rs, &c. and from these points of division, draw the hour-lines r, s, t, u, v, E, w, and x, all parallel to the six o'clock line EC. If each part of the semicircle be divided into four equal parts, they will give the half-hour lines and quarters, as in Fig. 2. Draw the right line $ASDo$, making the angle SAB equal to the latitude of your place. Upon the centre A describe the arch RST, and set off upon it the arcs SR and ST, each equal to $23\frac{1}{2}$ degrees, for the sun's greatest declination; and divide them tnto $23\frac{1}{2}$ equal parts, as in Fig. 2. Through the intersection D of the lines ECD and ADo draw the right line FDG at right angles to

A D o. Lay a ruler to the points *A* and *R*, and draw the line *A R F* through $23\frac{1}{2}$ degrees of south declination in the arc *S R;* and then laying the ruler to the points *A* and *T*, draw the line *A T G* through $23\frac{1}{2}$ degrees of north declination in the arc *S T:* so shall the lines *A R F* and *A T G* cut the line *F D G* in the proper length for the scale of months. Upon the centre *D*, with the radius *D F*, describe the semicircle *F o G;* and divide it into six equal parts, *Fm*, *mn*, *no*, &c. and from these points of division draw the right lines *m h*, *n i*, *p k*, and *q l*, each parallel to *o D*. Then setting one foot of the compasses in the point *F*, extend the other to *A*, and describe the arc *A z H* for the tropic of ♑: with the same extent, setting one foot in *G*, describe the arc *A E O* for the tropic of ♋. Next setting one foot in the point *h*, and extending the other to *A*, describe the arc *A C I* for the beginnings of the signs ♒ and ♐; and with the same extent, setting one foot in the point *l*, describe the arc *A N* for the beginnings of the signs ♊ and ♌. Set one foot in the point *i*, and having extended the other to *A*, describe the arc *A K* for the beginnings of the signs ♈ and ♎; and with the same extent, set one foot in *k*, and describe the arc *A M* for the beginnings of the signs ♉ and ♍. Then, setting one foot in the point *D*, and extending the other to *A*, describe the curve *A L* for the beginnings of ♈ and ♑; and the signs will be finished. This done, lay a ruler from the point *A* over the sun's declination in the arch *R S T* (found by the following table) for every fifth day of the year and where the ruler cuts the line *F D G*, make marks; and place the days of the month right against these marks, in the manner shewn by Fig. 2.

LECT. X.

LECT. X. Lastly, draw the shadow line *P Q* parallel to the occult line *A B*; make the gnomon, and set the hours to their respective lines, as in Fig. 2, and the dial will be finished.

Fig. 4. There are several kinds of dials, which are called *universal*, because they serve for all latitudes. Of these, the best one that I know is Mr. Pardie's, which consists of three principal parts: the first whereof is called the *horizontal plane* (*A*) because in the practice it must be parallel to the horizon. In this plane is fixed an upright pin, which enters into the edge of the second part *B D*, called the *meridional plane*; which is made of two pieces, the lowest whereof (*B*) is called the *quadrant*, because it contains a quarter of a circle, divided into 90 degrees; and it is only into this part, near *B*, that the pin enters. The other piece is a *semicircle* (*D*) adjusted to the quadrant, and turning in it by a groove, for raising or depressing the diameter (*E F*) of the semicircle, which diameter is called the *axis* of the instrument. The third piece is a *circle* (*G*) divided on both sides into 24 equal parts, which are the hours. This circle is put upon the meridional plane so, that the axis (*E F*) may be perpendicular to the circle; and the point *C* be the common centre of the circle, semicircle, and quadrant. The straight edge of the semicircle is chamfered on both sides to a sharp edge, which passes through the centre of the circle. On one side of the chamfered part, the first six months of the year are laid down, according to the sun's declination for their respective days, and on the other side the last six months. And against the days on which the sun enters the signs, there are straight lines drawn upon the semicircle, with the

An universal dial.

characters of the signs marked upon them. There is a black line drawn along the middle of the upright edge of the quadrant, over which hangs a thread (*H*) with its plummit (*I*) for levelling the instrument. *N. B.* From the 22^{d} of September to the 20th of March, the upper surface of the circle must touch both the centre *C* of the semicircle, and the line of ♈ and ♎; and from the 20th of March to the 22^{d} of September, the lower surface of the circle must touch that centre and line. LECT. X.

To find the time of the day by this dial. Having set it on a level place in sun-shine, and adjusted it by the levelling screws *k* and *l*, until the plumb line hangs over the back line upon the edge of the quadrant, and parallel to the said edge; move the semicircle in the quadrant until the line of ♈ and ♎ (where the circle touches) comes to the latitude of your place in the quadrant: then, turn the whole meridional plane *B D*, with its circle *G*, upon the horizontal plane *A*, until the edge of the shadow of the circle falls precisely on the day of the month in the semicircle; and then, the meridional plane will be due north and south, the axis *E F* will be parallel to the axis of the world, and will cast a shadow upon the true time of the day, among the hours on the circle.

N. B. As, when the instrument is thus rectified, the quadrant and semicircle are in the plane of the meridian, so the circle is then in the plane of the equinoctial: therefore, as the sun is above the equinoctial in summer (in northern latitudes) and below it in winter; the axis of the semicircle will cast a shadow on the hour of the day, on the upper surface of the circle, from the 20th of March to the 22^{d} of September;

LECT. X.

and from the 22[d] of September to the 20th of March, the hour of the day will be determined by the shadow of the semicircle, upon the lower surface of the circle. In the former case, the shadow of the circle falls upon the day of the month, on the lower part of the diameter of the semicircle; and in the latter case on the upper part.

The method of laying down the months and signs upon the semicircle, is as follows. Draw the right line *A C B*, equal to the diameter of
Fig. 5. the semicircle *A D B*, and cross it in the middle at right angles with the line *E C D*, equal in length to *A D B*; then *E C* will be the radius of the circle *F C G*, which is the same as that of the semicircle. Upon *E* as a centre, describe the circle *F C G*, on which set off the arcs *Ch* and *Ci*, each equal to $23\frac{1}{2}$ degrees, and divide them accordingly into that number for the sun's declination. Then, laying the edge of a ruler over the centre *E*, and also over the sun's declination for every fifth day [3] of each month (as in the card-dial), mark the points on the diameter *A B* of the semicircle from *a* to *g*, which are cut by the ruler; and there place the days of the months accordingly, answering the sun's declination. This done, setting one foot of the compasses in *C*, and extending the other to *a* or *g*, describe the semicircle *a b c d e f g*; which divide into six equal parts, and through the points of division draw right lines, parallel to *C D*, for the beginning of the signs (of which one half are on one side of the semicircle, and

[3] The intermediate days may be drawn in by hand, if the spaces be large enough to contain them.

the other half on the other side), and set the characters of the signs to their proper lines, as in the figure. LECT. X.

The following table shews the sun's place and declination, in degrees and minutes, at the noon of every day of the second year after leap year; which is a mean between those of leap year itself, and the first and third years after it. It is useful for inscribing the months and their days on sun-dials; and also for finding the latitudes of places, according to the methods prescribed after the table. [4] Tables of the sun's place and declination.

---

[4] In this edition, the table of the sun's longitude and declination has been calculated anew, and adapted to the present improved state of the solar tables. The editor has also added an accurate table of the equation of time, which, he trusts, will be of great use to the practical dialist. The signs + and —, *add* and *subtract*, at the head of the column, denote that the equation of time must be added to, or subtracted from, the apparent time, or that which is deduced from the motion of the sun, in order to obtain the equated or true time, as shewn by a well-regulated clock or watch. The table is calculated for the second after leap year, and is as accurate as the difference between the civil and solar year will permit.—Ed.

LECT. X.

A Table shewing the sun's place and declination.

Days.	January. Sun's Pl. D.	M.	Sun's Dec. D.	M.	Days.	February. Sun's Pl. D.	M.	Sun's Dec. D.	M.
1	10♑	27	23 S	3	1	12♒	0	17 S	13
2	11	28	22	58	2	13	1	16	56
3	12	29	22	53	3	14	2	16	38
4	13	31	22	47	4	15	3	16	20
5	14	32	22	40	5	16	4	16	2
6	15	33	22	34	6	17	4	15	44
7	16	34	22	26	7	18	5	15	26
8	17	35	22	19	8	19	6	15	7
9	18	37	22	10	9	20	7	14	48
10	19	38	22	2	10	21	7	14	28
11	20	39	21	53	11	22	8	14	9
12	21	40	21	43	12	23	9	13	49
13	22	41	21	33	13	24	9	13	29
14	23	42	21	23	14	25	10	13	9
15	24	43	21	12	15	26	10	12	49
16	25	44	21	1	16	27	11	12	28
17	26	46	20	50	17	28	11	12	7
18	27	47	20	38	18	29	12	11	46
19	28	48	20	25	19	0♓	12	11	25
20	29	49	20	13	20	1	12	11	3
21	0♒	50	20	0	21	2	13	10	42
22	1	51	19	46	22	3	13	10	20
23	2	52	19	32	23	4	13	9	58
24	3	53	19	18	24	5	14	9	36
25	4	54	19	4	25	6	14	9	14
26	5	55	18	49	26	7	14	8	52
27	6	56	18	34	27	8	14	8	29
28	7	57	18	18	28	9	15	8	7
29	8	58	18	2					
30	9	58	17	46					
31	10	59	17	30					

In these Tables N signifies north, and S south, declination.

LECT. X.

A Table shewing the sun's place and declination.

Days	March. Sun's Pl. D.	M.	Sun's Dec. D.	M.	Days	April. Sun's Pl. D.	M.	Sun's Dec. D.	M.
1	10 ♓	15	7 S	44	1	11 ♈	3	4 N	23
2	11	15	7	21	2	12	2	4	46
3	12	15	6	58	3	13	1	5	9
4	13	15	6	35	4	14	0	5	32
5	14	15	6	12	5	14	59	5	55
6	15	15	5	49	6	15	58	6	17
7	16	15	5	26	7	16	57	6	40
8	17	15	5	2	8	17	56	7	3
9	18	15	4	39	9	18	55	7	25
10	19	15	4	16	10	19	54	7	47
11	20	15	3	52	11	20	53	8	9
12	21	15	3	29	12	21	51	8	31
13	22	14	3	5	13	22	50	8	53
14	23	14	2	41	14	23	49	9	15
15	24	14	2	18	15	24	47	9	37
16	25	13	1	54	16	25	46	9	58
17	26	13	1	30	17	26	44	10	19
18	27	12	1	7	18	27	43	10	40
19	28	12	0	43	19	28	41	11	1
20	29	11	0	19	20	29	40	11	22
21	0 ♈	11	0 N	4	21	0 ♉	38	11	43
22	1	10	0	28	22	1	37	12	3
23	2	10	0	52	23	2	35	12	23
24	3	9	1	15	24	3	33	12	43
25	4	9	1	39	25	4	32	13	3
26	5	8	2	2	26	5	30	13	22
27	6	7	2	26	27	6	28	13	42
28	7	6	2	50	28	7	27	14	1
29	8	6	3	13	29	8	25	14	20
30	9	5	3	36	30	9	23	14	38
31	10	4	3	59					

LECT. X.

A Table shewing the sun's place and declination.

Days.	May. Sun's Pl. D.	M.	Sun's Dec. D.	M.	Days.	June. Sun's Pl. D.	M.	Sun's Dec. D.	M.
1	10 ♉	21	14N	57	1	10 ♊	12	22N	0
2	11	19	15	15	2	11	10	22	8
3	12	18	15	33	3	12	7	22	16
4	13	16	15	50	4	13	4	22	24
5	14	14	16	8	5	14	2	22	31
6	15	12	16	25	6	14	59	22	37
7	16	10	16	42	7	15	57	22	43
8	17	8	16	58	8	16	54	22	49
9	18	6	17	14	9	17	51	22	55
10	19	4	17	30	10	18	49	23	0
11	20	2	17	46	11	19	46	23	4
12	20	59	18	1	12	20	43	23	9
13	21	57	18	17	13	21	40	23	12
14	22	55	18	31	14	22	38	23	16
15	23	53	18	46	15	23	35	23	19
16	24	51	19	0	16	24	32	23	21
17	25	48	19	14	17	25	29	23	23
18	26	46	19	27	18	26	27	23	25
19	27	44	19	41	19	27	24	23	26
20	28	41	19	53	20	28	21	23	27
21	29	39	20	6	21	29	18	23	28
22	0 ♊	37	20	18	22	0 ♋	16	23	28
23	1	34	20	30	23	1	13	23	28
24	2	32	20	41	24	2	10	23	27
25	3	29	20	53	25	3	7	23	26
26	4	27	21	3	26	4	5	23	24
27	5	24	21	14	27	5	2	23	22
28	6	22	21	24	28	5	59	23	20
29	7	20	21	33	29	6	56	23	17
30	8	17	21	43	30	7	53	23	14
31	9	15	21	52					

LECT. X.

A Table shewing the sun's place and declination.

Days.	July. Sun's Pl. D.	M.	Sun's Dec. D.	M.	Days.	August. Sun's Pl. D.	M.	Sun's Dec. D.	M.
1	8♋	51	23N	10	1	8♌	26	18N	10
2	9	48	23	6	2	9	24	17	55
3	10	45	23	2	3	10	21	17	40
4	11	42	22	57	4	11	19	17	24
5	12	40	22	52	5	12	16	17	8
6	13	37	22	46	6	13	14	16	52
7	14	34	22	40	7	14	11	16	35
8	15	31	22	34	8	15	9	16	19
9	16	28	22	27	9	16	6	16	2
10	17	26	22	20	10	17	4	15	44
11	18	23	22	12	11	18	2	15	27
12	19	20	22	4	12	18	59	15	9
13	20	17	21	56	13	19	57	14	51
14	21	14	21	47	14	20	54	14	33
15	22	12	21	38	15	21	52	14	14
16	23	9	21	29	16	22	50	13	55
17	24	6	21	19	17	23	47	13	36
18	25	3	21	9	18	24	45	13	17
19	26	1	20	58	19	25	43	12	58
20	26	58	20	47	20	26	41	12	58
21	27	55	20	36	21	27	39	12	18
22	28	52	20	24	22	28	36	11	58
23	29	50	20	13	23	29	34	11	38
24	0♌	47	20	0	24	0♍	32	11	18
25	1	44	19	48	25	1	30	10	57
26	2	42	19	35	26	2	28	10	36
27	3	39	19	22	27	3	26	10	15
28	4	37	19	8	28	4	24	9	54
29	5	34	18	54	29	5	22	9	33
30	6	31	18	40	30	6	20	9	12
31	7	29	18	25	31	7	18	8	50

LECT. X.

A Table shewing the sun's place and declination.

Days.	September. Sun's Pl. D.	M.	Sun's Dec. D.	M.	Days.	October. Sun's Pl. D.	M.	Sun's Dec. D.	M.
1	8 ♍	17	8 N	29	1	7 ♎	34	3 S	0
2	9	15	8	7	2	8	33	3	24
3	10	13	7	45	3	9	33	3	47
4	11	11	7	23	4	10	32	4	10
5	12	9	7	1	5	11	31	4	34
6	13	8	6	38	6	12	30	4	57
7	14	6	6	16	7	13	29	5	20
8	15	4	5	53	8	14	29	5	43
9	16	2	5	31	9	15	28	6	6
10	17	1	5	8	10	16	27	6	29
11	17	59	4	45	11	17	27	6	51
12	18	58	4	22	12	18	26	7	14
13	19	56	3	59	13	19	26	7	37
14	20	55	3	36	14	20	25	7	59
15	21	53	3	13	15	21	25	8	22
16	22	52	2	50	16	22	24	8	44
17	23	50	2	27	17	23	24	9	6
18	24	49	2	4	18	24	23	9	28
19	25	47	1	40	19	25	23	9	50
20	26	46	1	17	20	26	23	10	11
21	27	45	0	54	21	27	23	10	33
22	28	44	0	30	22	28	22	10	54
23	29	42	0	7	23	29	22	11	16
24	0 ♎	41	0 S	16	24	0 ♏	22	11	37
25	1	40	0	40	25	1	22	11	58
26	2	39	1	3	26	2	22	12	18
27	3	38	1	27	27	3	22	12	39
28	4	37	1	50	28	4	22	12	59
29	5	36	2	14	29	5	22	13	14
30	6	35	2	37	30	6	22	13	39
					31	7	22	13	59

LECT. X.

A Table shewing the sun's place and declination.

November.					December.				
Days.	Sun's Pl.		Sun's Dec.		Days.	Sun's Pl.		Sun's Dec.	
	D.	M.	D.	M.		D.	M.	D.	M.
1	8 ♏	22	14 S	19	1	8 ♐	39	21 S	46
2	9	22	14	38	2	9	39	21	55
3	10	23	14	57	3	10	40	22	4
4	11	23	15	16	4	11	41	22	13
5	12	23	15	34	5	12	42	22	21
6	13	23	15	53	6	13	43	22	28
7	14	24	16	11	7	14	44	22	35
8	15	24	16	28	8	15	45	32	42
9	16	24	16	46	9	16	46	22	48
10	17	24	17	3	10	17	47	22	54
11	18	25	17	20	11	18	48	23	0
12	19	25	17	36	12	19	49	23	5
13	20	26	17	53	13	20	50	23	9
14	21	26	18	9	14	21	51	23	13
15	22	27	18	24	15	22	52	23	16
16	23	27	18	39	16	23	53	23	19
17	24	28	18	54	17	24	55	23	22
18	25	28	19	9	18	25	56	23	24
19	26	29	19	23	19	26	57	23	26
20	27	30	19	37	20	27	58	23	27
21	28	30	19	51	21	28	59	23	28
22	29	31	20	4	22	0 ♑	0	23	28
23	0 ♐	32	20	17	23	1	2	23	28
24	1	33	20	30	24	2	3	23	27
25	2	33	20	42	25	3	4	23	26
26	3	34	20	53	26	4	5	23	24
27	4	35	21	5	27	5	6	23	22
28	5	36	21	16	28	6	8	23	19
29	6	37	21	26	29	7	9	23	16
30	7	38	21	36	30	8	10	23	13
					31	9	11	23	9

LECT. X.

Table of the Equation of Time.

Days.	January.		February.		March.		April.	
	M.	S.	M.	S.	M.	S.	M.	S.
1	3 +	48	13 +	58	12 +	45	4 +	7
2	4	16	14	5	12	33	3	49
3	4	44	14	12	12	21	3	31
4	5	12	14	19	12	8	3	13
5	5	39	14	24	11	54	2	55
6	6	6	14	28	11	40	2	37
7	6	33	14	32	11	26	2	20
8	6	59	14	34	11	14	2	2
9	7	24	14	37	10	56	1	45
10	7	49	14	38	10	41	1	28
11	8	13	14	39	10	25	1	12
12	8	37	14	38	10	9	0	55
13	9	0	14	37	9	52	0	39
14	9	22	14	35	9	35	0	23
15	9	44	14	33	9	18	0	8
16	10	4	14	29	9	1	0 −	7
17	10	25	14	25	8	43	0	22
18	10	44	14	20	8	25	0	36
19	11	3	14	15	8	7	0	50
20	11	21	14	8	7	49	1	4
21	11	38	14	2	7	31	1	17
22	11	55	13	54	7	12	1	30
23	12	11	13	46	6	54	1	42
24	12	26	13	37	6	35	1	54
25	12	40	13	28	6	17	2	5
26	12	53	13	18	5	53	2	16
27	13	6	13	8	5	39	2	26
28	13	18	12	57	5	21	2	36
29	13	29			5	2	2	45
30	13	39			4	44	2	53
31	13	49			4	24		

LECT. X.

Table of the Equation of Time.

Days.	May.		June.		July.		August.	
	M.	S.	M.	S.	M.	S.	M.	S.
1	3 −	2	2 −	42	3 +	13	5 +	57
2	3	10	2	34	3	25	5	54
3	3	17	2	24	3	36	5	50
4	3	23	2	14	3	48	5	46
5	3	29	2	4	3	58	5	40
6	3	35	1	54	4	9	5	35
7	3	40	1	43	4	19	5	28
8	3	44	1	32	4	29	5	21
9	3	48	1	21	4	38	5	14
10	3	51	1	10	4	47	5	5
11	3	54	0	58	4	56	4	57
12	3	56	0	46	5	4	4	47
13	3	57	0	34	5	11	4	37
14	3	58	0	22	5	18	4	27
15	3	59	0	9	5	25	4	16
16	3	59	0 +	3	5	31	4	4
17	3	58	0	16	5	37	3	52
18	3	57	0	28	5	42	3	39
19	3	55	0	41	5	47	3	26
20	3	53	0	54	5	51	3	13
21	3	50	1	7	5	54	2	59
22	3	46	1	20	5	57	2	45
23	3	42	1	33	6	0	2	30
24	3	38	1	46	6	2	2	14
25	3	33	1	59	6	3	1	59
26	3	27	2	11	6	4	1	43
27	3	21	2	24	6	5	1	26
28	3	14	2	37	6	4	1	9
29	3	7	2	49	6	3	0	52
30	3	59	3	1	6	2	0	34
31	2	51			6	0	0	17

LECT. X.

Table of the Equation of Time.

Days.	Septem.		October.		Novem.		Decem.	
	M.	S.	M.	S.	M.	S.	M.	S.
1	0	− 2	10	− 10	16	− 13	10	− 49
2	0	20	10	29	16	14	10	27
3	0	39	10	47	16	14	10	3
4	0	58	11	6	16	14	9	39
5	1	18	11	24	16	13	9	15
6	1	37	11	42	16	11	8	50
7	1	57	11	59	16	8	8	24
8	2	18	12	16	16	4	7	58
9	2	38	12	32	16	0	7	31
10	2	58	12	48	15	54	7	4
11	3	19	13	4	15	48	6	37
12	3	40	13	19	15	41	6	9
13	4	1	13	34	15	33	5	41
14	4	22	13	48	15	25	5	13
15	4	43	14	2	15	15	4	44
16	5	4	14	15	15	5	4	15
17	5	25	14	27	14	53	3	45
18	5	46	14	39	14	41	3	16
19	6	7	14	50	14	28	2	46
20	6	28	15	1	14	14	2	16
21	6	49	15	11	13	59	1	46
22	7	10	15	20	13	44	1	16
23	7	30	15	28	13	27	0	45
24	7	51	15	36	13	10	0	15
25	8	11	15	43	12	52	0	+ 15
26	8	32	15	50	12	33	0	45
27	8	52	15	55	12	14	1	15
28	9	12	16	0	11	54	1	45
29	9	31	16	5	11	33	2	14
30	9	51	16	8	11	12	2	43
31			16	11			3	13

Explanation of the Table of the Equation of Time.

As our author has already given a familiar explanation of the equation of time, it may be sufficient to observe, that the preceding table contains the difference between true and apparent time, for every day of the year at 12 o'clock noon, when the sun is in the meridian; and is adapted to the second year after leap year. If apparent, or solar, time is to be converted into true time, as shewn by a well-regulated clock or watch, the equation of time must be added to the apparent time, if it has the sign +, and subtracted from it if it has the sign —: but if true is to be converted into apparent time, the equation must be applied with contrary signs. If the equation is required for any intermediate hour, take the difference during a day, and say, as 24 hours is to this difference, so is the number of hours which the intermediate hour is from the preceding noon, to a third proportional, which, added to, or subtracted from, the equation of time at noon, according as it is increasing or decreasing, will give the equation of time for the given hour. If the equation of time is wanted, at a time when the signs change from + to —, or from — to +, the difference for 24 hours will be found by *adding* the equations of time for the noon preceding and following the given hour. Thus, if the equation of time is required for the 24th December at 12 o'clock midnight, the equation for the 24th at noon is — 15″, and for the 25th at noon + 15″, the difference of which is + 30″. Then, as 24^{h} : + 30″ = 12^{h} : + 15, which, subtracted from 15 seconds, because the numbers are decreasing, the equation for the 24th noon, leaves 0, so that the hour, as shewn by the sun and clock, is the same on the 24th December at midnight. The equation thus found will be accurate for every second year after leap year, and in other years will vary only a few seconds from the truth. In order, however, to determine the equation of time, with accuracy for any other year,

find the difference between the equation of time for the given day, and that which precedes it: then,

1. *For leap year*, take one half of this difference, and add it to the equation for the given time if it increases, but subtract it if it decreases.

2. *For the first after leap year*, take one fourth of the difference, and add it to the equation for the given time if it increases, but subtract it if it decreases.

3. *For the third after leap year*, take one fourth of the difference, and subtract it from the equation for the given time, if it increases, but add it if it decreases. Thus, to find the equation of time for the 2d May 1805, being the first after leap year, the equation in the table is 3′ 10″, the daily difference is 8″, and the equation increases. Add, therefore, 2″, which is one fourth of the daily difference, to 3′ 10″, and the sum 3′ 12″, will be the true equation of time for the 2d May 1805.—Ed.

TO FIND THE LATITUDE OF ANY PLACE BY OBSERVATION.

LECT. X.

The latitude of any place is equal to the elevation of the pole above the horizon of that place. Therefore it is plain, that if a star was fixed in the pole, there would be nothing required to find the latitude, but to take the altitude of that star with a good instrument. But although there is no star in the pole, yet the latitude may be found by taking the greatest and least altitude of any star that never sets: for if half the difference between these altitudes be added to the least altitude, or subtracted from the greatest, the sum or remainder will be equal to the altitude of the pole at the place of observation.[1]

But because the length of the night must be more than 12 hours, in order to have two such observations; the sun's meridian altitude and declination are generally made use of for finding the latitude, by means of its complement, which is equal to the elevation of the equinoctial above the horizon; and if this complement be subtracted from 90 degrees, the remainder will be the latitude, concerning which, I think, the following rules take in all the various cases.

1. If the sun has north declination, and is on the meridian, and to the south of your place, subtract the declination from the meridian altitude (taken by a good quadrant) and the remain-

[1] If the altitude of the pole star be taken six hours before, or after, it comes to the meridian, or arrives at its point of greatest and least altitude, the latitude of the place will thus be accurately obtained by only one observation.—ED.

LECT. X. der will be the height of the equinoctial or complement of the latitude north.

EXAMPLE.

Suppose { The sun's meridian altitude	42°	20′	south.
{ And his declination, subtract	10	15	north.
Remains the complement of the latitude,	32	5	
Which subtract from —	90	0	

And the remainder is the latitude 57 55 north.[a]

2. If the sun has south declination, and is southward of your place at noon, add the declination to the meridian altitude; the sum, if less than 90 degrees, is the complement of the latitude north: but if the sum exceeds 90 degrees, the latitude is south; and if 90 be taken from that sum, the remainder will be the latitude.

EXAMPLES.

The sun's meridian altitude	65°	10′	south
The sun's declination, add	15	30	south
Complement of the latitude	80	40	
Subtract from —	90	0	
Remains the latitude	9	20	north

The sun's meridian altitude	80°	40′	south
The sun's declination, add	20	10	south
The sum is — —	100	50	
From which subtract	90	0	
Remains the latitude —	10	50	so

[a] The sun's meridian altitude, as taken by a quadrant, or any other instrument, must be corrected by the application of parallax and refraction. As the sun is elevated by refraction and depressed by parallax, his apparent meridian altitude must be diminished by the difference between the refraction and parallax.—Ed.

LECT. X.

3. If the sun has north declination, and is on the meridian north of your place, add the declination to the north meridian altitude; the sum, if less than 90 degrees, is the complement of the latitude south; but if the sum is more than 90 degrees, subtract 90 from it, and the remainder is the latitude north.

EXAMPLES.

Sun's meridian altitude	60°	30′	north
Sun's declination, add	20	10	north
Complement of the latitude	80	40	
Subtract from —	90	0	
Remains the latitude	9	20	south

Sun's meridian altitude	70°	20′	north
Sun's declination, add	23	20	north
The sum is —	93	40	
From which subtract —	90	0	
Remains the latitude —	3	40	north

4. If the sun has south declination, and is north of your place at noon, subtract the declination from the north meridian altitude, and the remainder is the complement of the latitude south.

EXAMPLE.

Sun's meridian altitude	52°	30′	north
Sun's declination, subtract	20	10	south
Complement of the latitude	32	20	
Subtract from —	90	0	
And the remainder is the latitude	57	40	south

LECT. X.

5. If the sun has no declination, and is south of your place at noon, the meridian altitude is the complement of the latitude north: but if the sun be then north of your place, his meridian altitude is the complement of the latitude south.

EXAMPLES.

Sun's meridian altitude		38° 30′	south
Subtract from	—	90 0	
Remains the latitude	—	51 30	north

Sun's meridian altitude		38° 30′	north
Subtract from	—	90 0	
Remains the latitude	—	51 30	south

6. If you observe the sun beneath the pole, subtract his declination from 90 degrees, and add the remainder to his altitude; and the sum is the latitude.

EXAMPLE.

Sun's declination	—	20° 30′	
Subtract from	—	90 0	
Remains	—	69 30	} add
Sun's altitude below the pole		10 20	
The sum is the latitude		79 50	

Which is north or south, according as the sun's declination is north or south: for when the sun has south declination, he is never seen below the north pole; nor is he ever seen below the south pole, when his declination is north.

LECT. X.

7. If the sun be in the zenith at noon, and at the same time has no declination, you are then under the equinoctial, and so have no latitude.

If the sun be in the zenith at noon, and has declination, the declination is equal to the latitude, north or south. These two cases are so plain, that they require no examples.[3]

---

[3] The latitude of a place may be found with equal facility and accuracy, by taking the meridian altitude of the planets and fixed stars, and observing the same directions which are given by our author in the case of the sun. When fixed stars, however, are employed, their altitude must be corrected by refraction only, as their parallax is not sensible.—ED.

LECTURE XI.

OF DIALING.

LECT. XI. HAVING shewn in the preceding Lecture how to make sun-dials by the assistance of a good globe, or of a dialing scale, we shall now proceed to the method of constructing dials arithmetically; which will be more agreeable to those who have learned the elements of trigonometry, because globes and scales can never be so accurate as logarithms, in finding the angular distances of the hours. Yet, as a globe may be found exact enough for some other requisites in dialing, we shall take it in occasionally.

The construction of sun-dials on all planes whatever, may be included in one general rule: intelligible, if that of a horizontal dial for any given latitude be well understood. For there is no plane, however obliquely situated with respect to any given place, but what is parallel to the horizon of some other place; and therefore, if we can find that other place by a problem on the terrestrial globe, or by a trigonometrical calculation, and construct a horizontal dial for it; that dial, applied to the plane where it is to

serve, will be a true dial for that place.—Thus, an erect direct south dial in $51\frac{1}{2}$ degrees north latitude, would be a horizontal dial on the same meridian, 90 degrees southward of $51\frac{1}{2}$ degrees north latitude; which falls in with $38\frac{1}{2}$ degrees of south latitude: but if the upright plane declines from facing the south at the given place, it would still be a horizontal plane 90 degrees from that place, but for a different longitude; which would alter the reckoning of the hours accordingly. LECT. XI.

CASE I.

1. Let us suppose that an upright plane at London declines 36 degrees westward from facing the south; and that it is required to find a place on the globe, to whose horizon the said plane is parallel; and also the difference of longitude between London and that place.

Rectify the globe to the latitude of London, and bring London to the zenith under the brass meridian, then that point of the globe which lies in the horizon at the given degree of declination (counted westward from the south point of the horizon) is the place at which the above-mentioned plane would be horizontal.—Now, to find the latitude and longitude of that place, keep your eye upon the place, and turn the globe eastward until it comes under the graduated edge of the brass meridian; then the degree of the brass meridian that stands directly over the place, is its latitude; and the number of degrees in the equator, which are intercepted between the meridian of London and the brass meridian, is the place's difference of longitude.

Thus, as the latitude of London is $51\frac{1}{2}$ de-

LECT. XI. grees north, and the declination of the place is 36 degrees west; I elevate the north pole $51\frac{1}{4}$ degrees above the horizon, and turn the globe until London comes to the zenith, or under the graduated edge of the meridian; then, I count 36 degrees on the horizon westward from the south point, and make a mark on that place of the globe over which the reckoning ends, and bringing the mark under the graduated edge of the brass meridian, I find it to be under $30\frac{1}{4}$ degrees in south latitude: keeping it there, I count in the equator the number of degrees between the meridian of London and the brasen meridian (which now becomes the meridian of the required place) and find it to be $42\frac{3}{4}$. Therefore an upright plane at London, declining 36 degrees westward from the south, would be a horizontal plane at that place; whose latitude is $30\frac{1}{4}$ degrees south of the equator, and longitude $42\frac{3}{4}$ degrees west of the meridian of London.

Which difference of longitude being converted into time, is 2 hours 51 minutes.

The vertical dial declining westward 36 degrees at London, is therefore to be drawn in all respects as a horizontal dial for south latitude $30\frac{1}{4}$ degrees; save only, that the reckoning of the hours is to anticipate the reckoning on the horizontal dial, by 2 hours 51 minutes: for so much sooner will the sun come to the meridian of London, than to the meridian of any place whose longitude is $42\frac{3}{4}$ degrees west from London.

PLATE XXIII. Fig. 1. 2. But to be more exact than the globe will shew us, we shall use a little trigonometry.

Let *NE SW* be the horizon of London, whose zenith is Z, and *P* the north pole of the sphere; and let *Z h* be the position of a vertical plane at

LECT XI.

Z, declining westward from *S* (the south) by an angle of 36 degrees; on which plane an erect dial for London at *Z* is to be described. Make the semidiameter *Z D* perpendicular to *Z h*, and it will cut the horizon in *D*, 36 degrees west of the south *S*. Then, a plane in the tangent *H D*, touching the sphere in *D*, will be parallel to the plane *Z h*; and the axis of the sphere will be equally inclined to both these planes.

Let *WQE* be the equinoctial, whose elevation above the horizon of *Z* (London) is $38\frac{1}{2}$ degrees; and *PRD* be the meridian of the place *D*, cutting the equinoctial in *R*. Then, it is evident, that the arc *RD* is the latitude of the place *D* (where the plane *Z h* would be horizontal) and the arc *RQ* is the difference of longitude of the planes *Z h* and *DH*.

In the spherical triangle *WDR*, the arc *WD* is given, for it is the complement of the plane's declination from *S* the south; which complement is 54° (viz. 90°—36°): the angle at *R*, in which the meridian of the place *D* cuts the equator, is a right angle; and the angle *RWD* measures the elevation of the equinoctial above the horizon of *Z*, namely $38\frac{1}{2}$ degrees. Say, therefore, as radius is to the co-sine of the plane's declination from the south, so is the co-sine of the latitude of *Z* to the sign of *RD* the latitude of *D*;[1] which is of a different denomination from the latitude of *Z*, because *Z* and *D* are on different sides of the equator.

As radius	— — —	10.00000
To co-sine	36° 0′ = *RQ*	9.90796
So co-sine	51° 30′ = *QZ*	9.79415
To sine	30° 14′ = *DR*	9.70211 =

[1] See Playfair's Elements of Geometry. Spher. Trig. Prop. XIX.—Ed.

LECT. XI. the latitude of D, whose horizon is parallel to the vertical plane $Z\,h$ at Z.

N. B. When radius is made the first term, it may be omitted, and then, by subtracting it, mentally, from the sum of the other two, the operation will be shortened. Thus, in the present case,

To the logarithmic sine of WR = [4]	54°	0′	9.90796
Add the logarithmic sine of RD = [5]	38°	30′	9.79415
Their sum *minus* radius			9.70211

gives the same solution as above. And we shall keep to this method in the following part of the work.

To find the difference of longitude of the places D and Z, say, as radius is to the co-sine of $38\frac{1}{2}$ degrees, the height of the equinoctial at Z, so is the co-tangent of 36 degrees, the plane's declination, to the co-tangent of the difference of longitudes. [6] Thus,

To the logarithmic sine of [7]	51°	30′	9.89364
Add the logarithmic tang. of [8]	54°	0′	10.13874
Their sum *minus* radius			10.03238

is the nearest tangent of 47 8′ = WR; which is the co-tangent of 42° 52′ = RQ, the difference of longitude sought. Which difference being reduced to time, is 2 hours $51\frac{1}{2}$ minutes.

3. And thus having found the exact latitude

---

[4] The co-sine of 36° 0′, or of $R\,Q$.
[5] The co-sine of 51° 30′, or of $Q\,Z$.
[6] Playfair's Geom. Spher. Trig. Prop. XVIII.—Ed.
[7] The co-sine of 38° 30′, or of WDR.
[8] The co-tangent of 36°, or of DW.

and longitude of the place *D*, to whose horizon the vertical plane at *Z* is parallel, we shall proceed to the construction of a horizontal dial for the place *D*, whose latitude is 30° 14′ south; but anticipating the time at *D* by 2 hours 51 minutes (neglecting the $\frac{1}{2}$ minute in practice) because *D* is so far westward in longitude from the meridian of London; and this will be a true vertical dial at London, declining westward 36 degrees. LECT. XI.

Assume any right line *C S L* for the substile of the dial, and make the angle *K C P* equal to the latitude of the place (viz. 30° 14′) to whose horizon the plane of the dial is parallel; then *C R P* will be the axis of the stile, or edge that casts the shadow on the hours of the day, in the dial. This done, draw the contingent line *E Q*, cutting the substilar line at right angles in *K*; and from *K* make *K R* perpendicular to the axis *C R P*. Then *K G* (=*K R*) being made radius, that is equal to the chord of 60° or tangent of 45°, on a good sector take 42° 52′ (the difference of longitude of the places *Z* and *D*) from the tangents, and having set it from *K* to *M*, draw *C M* for the hour-line of XII. Take *K N* equal to the tangent of an angle less by 15 degrees than *K M*; that is, the tangent 27° 52′; and through the point *N* draw *C N* for the hour-line of I. The tangent of 12° 52′ (which is 15° less than 27° 52′) set off the same way, will give a point between *K* and *N*, through which the hour-line of II is to be drawn. The tangent of 2° 8′ (the difference between 45° and 42° 52′) placed on the other side of *C L*, will determine the point through which the hour-line of III is to be drawn: to which 2° 8′ if the tangent of 15° be added, it will make 17° 8′; and this set off from *K* toward *Q* on the line *E Q* will give Fig. 2.

LECT. XI.

the point for the hour-line of IV; and so of the rest. The forenoon hour-lines are drawn the same way, by the continual addition of the tangents 15°, 30°, 45°, &c. to 42°, 52° (= the tangent of *KM*) for the hours of XI, X, IX, &c. as far as necessary; that is, until there be five hours on each side of the substile. The sixth hour, accounted from that hour or part of the hour on which the substile falls, will be always in a line perpendicular to the substile, and drawn through the centre *C*.

4. In all erect dials, *CM*, the hour-line of XII is perpendicular to the horizon of the place for which the dial is to serve: for that line is the intersection of a vertical plane with the plane of the meridian of the place, both which are perpendicular to the plane of the horizon: and any line *HO*, or *ho*, perpendicular to *CM*, will be a horizontal line on the plane of the dial, along which line the hours may be numbered: and *CM* being set perpendicular to the horizon, the dial will have its true position.

5. If the plane of the dial had declined by an equal angle toward the east, its description would have differed only in this, that the hour-line of XII would have fallen on the other side of the substile *CL*, and the line *HO* would have a subcontrary position to what it has in this figure.

6. And these two dials, with the upper points of their stiles turned toward the north pole, will serve for the other two planes parallel to them; the one declining from the north toward the east, and the other from the north toward the west, by the same quantity of angle. The like

holds true of all dials in general, whatever be their declination and obliquity of their planes to the horizon. LECT. XI.

CASE II.

7. If the plane of the dial not only *declines*, but also *reclines*, or *inclines*. Suppose its declination from fronting the south S be equal to the arc SD on the horizon; and its reclination be equal to the arc Dd of the vertical circle DZ; then it is plain, that if the quadrant of altitude ZdD, on the globe, cuts the point D in the horizon, and the reclination is counted upon the quadrant from D to d; the intersection of the hour-circle PRd, with the equinoctial WQE, will determine Rd, the latitude of the place d, whose horizon is parallel to the given plane Zh at Z; and RQ will be the difference in longitude of the planes at d and Z. Fig. 3.

Trigonometrically thus: let a great circle pass through the three points W, d, E; and in the triangle WDd, right-angled at D, the sides WD and Dd are given; and thence the angle DWd is found, and so is the hypothenuse Wd. Again, the difference, or the sum, of DWd and DWR, the elevation of the equinoctial above the horizon of Z, gives the angle dWR; and the hypothenuse of the triangle WRd was just now found; whence the sides Rd and WR are found, the former being the latitude of the place d, and the latter the complement of RQ, the difference of longitude sought.

Thus, if the latitude of the place Z be 52° 10′ north; the declination SD of the plane Zh (which would be horizontal at d) be 36°, and the reclination be 15°, or equal to the arc Dd; the south latitude of the place d, that is, the arc Rd,

LECT. XI. will be 15° 9′; and *R Q* the difference of the longitude, 36° 2′. From these data, therefore, let the dial (Fig. 4) be described, as in the former example.

8. Only it is to be observed, that in the reclining or inclining dials, the horizontal line will not stand at right angles to the hour-line of XII, as in erect dials; but its position may be found as follows.

Fig. 4. To the common substilar line *C K L*, on which the dial for the place *d* was described, draw the dial *C r p m* 12 for the place *D*, whose declination is the same as that of *d*, viz. the arc *S D*; and *H O*, perpendicular to *C m*, the hour-line of XII on this dial, will be a horizontal line on the dial *C P R M* XII. For the declination of both dials being the same, the horizontal line remains parallel to itself, while the erect position of one dial is reclined or inclined with respect to the position of the other.

Or, the position of the dial may be found by applying it to its plane, so as to mark the true hour of the day by the sun, as shewn by another dial; or, by a clock regulated by a true meridian line and equation table.

9. There are several other things requisite in the practice of dialing; the chief of which I shall give in the form of arithmetical rules, simple and easy to those who have learned the elements of trigonometry. For in practical arts of this kind, arithmetic should be used as far as it can go; and scales never trusted to, except in the final construction, where they are absolutely necessary in laying down the calculated hour-distances on the plane of the dial. And although the inimitable artists of this metropolis have no occasion for such instructions, yet they

may be of some use to students, and to private gentlemen, who amuse themselves this way. LECT. XI.

RULE I.

To find the angles which the hour-lines on any dial make with the substile.

To the logarithmic sine of the given latitude, or of the stile's elevation above the plane of the dial, add the logarithmic tangent of the hour distance[1] from the meridian, or from the substile;[2] and the sum *minus* radius will be the logarithmic tangent of the angle sought.

For, in Fig. 2, KC is to KM in the ratio compounded of the ratio of KC to KG ($=KR$) and of KG to KM; which making CK the radius, 10,000,000, or 100,000, or 10 or 1, are the ratio of 10,000,000, or of 100,000, or of 10, or of 1, to $KG \times KM$.

Thus, in a horizontal dial, for latitude 51° 30′, to find the angular distance of XI in the forenoon, or I in the afternoon, from XII.

To the logarithmic sine of 51° 30′	9.89354[3]
Add the logarithmic tang. of 51° 0′	9.42805
The sum *minus* radius is	9.32159=

the logarithmic tangent of 11° 50′, or of the angle which the hour-line of XI or I makes with the hour of XII.

[1] That is, of 15, 30, 45, 60, 75°, for the hours of I, II, III, IV, V, in the afternoon; and XI, X, IX, VIII, VII, in the forenoon.

[2] In all horizontal dials, and erect north or south dials, the substile and meridian are the same; but in all declining dials, the substile line makes an angle with the meridian.

[3] In which case, the radius CK is supposed to be divided into 1,000,000 equal parts.

LECT. XI.

And by computing in this manner, with the sine of the latitude, and the tangents of 30, 45, 60, and 75°, for the hours of II, III, IV, and V, in the afternoon; or of X, IX, VIII, and VII, in the forenoon; you will find their angular distances from XII to be 24° 18′, 38° 3′, 53° 35′, and 71° 6′: which are all that there is occasion to compute for.—And these distances may be set off from XII by a line of chords; or rather, by taking 1,000 from a scale of equal parts, and setting that extent as a radius from *C* to XII: and then, taking 209 of the same parts (which, in the tables, are the natural tangent of 11° 50′), and setting them from XII to XI and to I, on the line *h o*, which is perpendicular to *C* XII: and so for the rest of the hour-lines, which in the table of natural tangents, against the above distances, are 451, 782, 1,355, and 2,920, of such equal parts from XII, as the radius *C* XII contains 1,000. And lastly, set off 1,257 (the natural tangent of 51° 30′) for the angle of the stile's height, which is equal to the latitude of the place.

Fig. 2.

The reason why I prefer the use of the tabular numbers, and of a scale decimally divided, to that of the line of chords is because there is the least chance of mistake and error in this way; and likewise, because in some cases it gives us the advantage of a *nonius* division.[4]

[4] This scale, for sub-dividing the limbs of quadrants, and the divisions of other mathematical instruments, is improperly called *Nonius*, from one Nonius, who is supposed to be its inventor. The honour of the invention is due to Peter Vernier, a French gentleman, from whom it frequently receives its name. The Vernier scale consists of a piece of brass or ivory, which moves along the limb of the quadrant. A space, equal to any number of degrees in the circular arch, 11°, for example, is transferred to this piece of

LECT. XI.

In the universal ring-dial, for instance, the divisions on the axis are the tangents of the angles of the sun's declination placed on either side of the centre. But instead of laying them down from a line of tangents, I would make a scale of equal parts, whereof 1,000 should answer exactly to the length of the semi-axis, from the centre to the inside of the equinoctial ring; and then lay down 434 of these parts toward each end from the centre, which would limit all the divisions on the axis, because 434 is the natural tangent of 23° 29′. And thus by a *nonius* affixed to the sliding piece, and taking the sun's declination from an ephemeris, and the tangent of that declination from the table of natural tangents, the slider might be always set true to within two minutes of a degree.

And this scale of 434 equal parts might be placed right against the $23\frac{1}{2}$ degrees of the sun's declination, on the axis, instead of the sun's

---

of brass, and divided into 10 parts, so that each division of the vernier will exceed each division of the limb by $\frac{1}{10}$ of a degree. Suppose the plumb-line of the quadrant to fall between the 25th and 26th degree, and that the degrees run from right to left. Then, in order to find the number of minutes above 25°, move the vernier till the plumb-line falls on the beginning of its scale, and find what division of the vernier coincides with any division on the limb; and by so many 10ths of a degree will the angle exceed 25°. If the 7th division of the vernier, for instance, coincides with a division on the limb, then, $\frac{7}{10}$ths of a degree, or 42 minutes, must be added to 25 degrees, and the angle will be 25° 42′.—Nonius's method consisted in drawing a number of concentric circles, the outermost of which was divided into 90 parts; the next into 89; the next into 88, &c. so that the plumb-line was sure to coincide with some division in one of these circles, and the angle could be easily deduced, from the number of parts into which that circle was divided.—Ed.

LECT. XI.

place, which is there of very little use. For then, the slider might be set in the usual way, to the day of the month, for common use; but to the natural tangent of the declination, when great accuracy is required.

The like may be done wherever a scale of sines or tangents is required on any instrument.

RULE II.

The latitude of the place, the sun's declination, and his hour distance from the meridian being given, to find (1,) *his altitude;* (2,) *his azimuth.*

Fig. 3.

1. Let d be the sun's place, dR, his declination: and in the triangle PZd, Pd the sum, or the difference, of dR, and the quadrant PR being given by the supposition, as also the complement of the latitude PZ, and the angle dPZ, which measures the horary distance of d from the meridian; we shall (by case 4, of Keill's Oblique spheric trigonometry) find the base Zd, which is the sun's distance from the zenith, or the complement of his altitude.

And (2,) as sine Zd: sine Pd:: sine dPZ: dZP, or of its supplement DZS, the azimuthal distance from the south.

Or, the practical rule may be as follows:

Write A for the sine of the sun's altitude, L and l for the sine and co-sine of the latitude, D and d for the sine and co-sine of the sun's declination, and H for the sine of the horary distance from VI.

Then the relation of H to A will have three varieties.

1. When the declination is toward the elevated pole, and the hour of the day is between XII and VI; it is $A = LD + Hld$, and $H = \frac{A - LD}{ld}$.

LECT. XI.

2. When the hour is after VI, it is $A = L\,D - H\,l\,d$, and $H = \frac{L\,D - A}{l\,d}$

3. When the declination is toward the depressed pole, we have $A = H\,l\,d - L\,D$, and $H = \frac{A + L\,D}{l\,d}$

Which theorems will be found useful, and expeditious enough for solving those problems in geography and dialing, which depend on the relation of the sun's altitude to the hour of the day.

EXAMPLE I.

Suppose the latitude of the place to be $51\frac{1}{2}$ degrees north; the time five hours distant from XII, that is, an hour after VI in the morning, or before VI in the evening; and the sun's declination 20° north. *Required the sun's altitude?*

Then, to log. L = log. sine 51° 38′	1.89354[5]
Add log. D = log. sine 20° 0′	1.53405
Their sum	1.42759

gives $L\,D$ = logarithm of 0.267664, in the natural sines.

And, to log. H = log. sine[6]	15° 0′	1.41300
add log. l. = log. sine[7]	38° 0′	1.79414
log. d. = log. sine[8]	70° 0′	1.97300
Their sum		1.18014

gives $H\,l\,d$ = logarithm of 0.151408, in the natural sines.

---

[5] Here we consider the radius as unity, and not 1,000,000, by which, instead of the index 9, we have—1, as above: which is of no further use, than making the work a little easier.

[6] The distance of one hour from VI.

[7] The co-latitude of the place.

[8] The co-declination of the sun.

LECT. XI.

And these two numbers of (0.267664 and 0.151408) make 0.419072 = *A*; which, in the table, is the nearest natural sine of 24° 47′, the sun's altitude sought.

The same hour-distance being assumed on the other side of VI, then *L D*—*H l d* is 0.116256, the sine of 6° 40′½; which is the sun's altitude at V in the morning, or VII in the evening, when his north declination is 20°.

But when the declination is 20° south, (or toward the depressed pole) the difference *H l d*—*L D* becomes negative, and thereby shews that, an hour before VI in the morning, or past VI in the evening, the sun's centre is 6°′½ 40′ below the horizon.

EXAMPLE II.

In the same latitude and north declination from the given altitude to find the hour.

Let the altitude be 48°; and because, in this case $H=\frac{A-LD,}{ld}$ and *A* (the natural sine of 48°) = .743145, and *L D* = .267664, *A*—*L D* will be 0.475481, whose logarithmic sine is 1.6771381

from which taking the logarithmic sine of *l* + *d* = ... 1.7671354

Remains 1.9099977

the logarithmic sine of the hour-distance sought, viz. of 54° 22′; which, reduced to time, is 3ʰ 37½ᵐ; that is, IXʰ 37½ᵐ in the forenoon, or IIʰ 22½ᵐ in the afternoon.

Put the altitude = 18°, whose natural sine is .3090170; and thence *A*—*L D* will be = .0491953; which divided by *l* + *d*, gives

.0717179, the sine of 4° 6′½, in time 16½ minutes nearly, before VI in the morning, or after VI in the evening, when the sun's altitude is 18°. LECT. XI.

And, if the declination 20° had been toward the south pole, the sun would have been depressed 18° below the horizon at 16½ minutes after VI in the evening; at which time the twilight would end; which happens about the 22d of November, and 19th of January, in the latitude of 51°½ north. The same way may the end of twilight, or beginning of dawn, be found for any time of the year.

NOTE 1, If in theorem 2 and 3 (page 55) A is put $= 0$, and the value of H is computed, we have the hour of sun-rising and setting for any latitude, and time of the year. And if we put $H = 0$, and compute A, we have the sun's altitude or depression at the hour of VI. And lastly, if H, A, and D are given, the latitude may be found by the resolution of a quadratic equation; for $l = \sqrt{1 - L^2}$.

NOTE 2, When A is equal 0, H is equal $\frac{L\,D}{l\,d} = T\,L \times T\,D$, the tangent of the latitude multiplied by the tangent of the declination.

As, if it was required, *what is the greatest length of day in latitude* 51° 30′?

To the log. tangent of 51° 30′ 0.0993948
Add the log. tangent of 23° 39′ 1.6379563

Their sum 1.7373511

is the log. sine of the hour-distance 33° 7′; in time 2h 12½m. The longest day therefore is

LECT. XI. $12^h + 4^h\ 25^m = 16^h\ 25^m$. And the shortest day is $12^h - 4^h\ 25^m = 7^h\ 35^m$.

And if the longest day is given, the latitude of the place is found; $\frac{H}{TD}$ being equal to TL. Thus, if the longest day is $13\frac{1}{2}^h = 2 \times 6^h + 45^m$ and 45^m in time being equal to $11\frac{1}{4}$ degrees.

From the log. sine of 11° 15′.....1.2902357
Take the log. tang. of 23° 29′.....1.6379562

Remains.....1.6522795
= the logarithmic tangent of lat. 24° 11′.

And the same way, the latitudes, where the several geographical *climates* and parallels begin, may be found; and the latitudes of places, that are assigned in authors from the length of their days, may be examined and corrected.

NOTE 3. The same rule for finding the longest day, in a given latitude, distinguishes the hour-lines that are necessary to be drawn on any dial from those which would be superfluous.

In lat. 52° 10′ the longest day is $16^h\ 32^m$ and the hour-lines are to be marked from 44^m after III in the morning, to 16^m after VIII in the evening.

In the same latitude, let the dial of Art. 7, Fig. 4, be proposed; and the elevation of its stile (or the latitude of the place *d*, whose horizon is parallel to the plane of the dial) being 15° 9′; the longest day at *d*, that is, the longest time that the sun can illuminate the plane of the dial, will (by the rule $H = TL \times TD$) be twice $6^h\ 27^m = 12^h\ 54^m$. The difference of longitude of the planes *d* and Z was found in the same example to be 36° 2′; in time,

$2^h\ 24^m$; and the declination of the plane was from the south toward the west. Adding therefore $2^h\ 24^m$ to $5^h\ 33^m$, the earliest sun-rising on a horizontal dial at *d*, the sum $7^h\ 57^m$ shews that the morning hours, or the parallel dial at Z, ought to begin at 3^m before VIII. And to the latest sun-setting at *d*, which is $6^h\ 27^m$, adding the same $2^h\ 24^m$, the sum $8^h\ 51^m$ exceeding $6^h\ 16^m$, the latest sun-setting at Z, by 35^m, shews that none of the afternoon hour-lines are superfluous. And the $4^h\ 13^m$ from $III^h\ 44^m$, the sun-rising at Z, to $VII^h\ 57^m$; the sun-rising at *d*, belong to the other face of the dial; that is, to a dial declining 36° from north to east, and inclining 15°. LECT. XI.

EXAMPLE III.

From the same data to find the sun's azimuth.

If *H*, *L*, and *D*, are given, then (by Art. 2, of Rule II) from *H*, having found the altitude and its complement Z *d*; and the arc *P D* (the distance from the pole) being given, say, as the co-sine of the altitude is to the sine of the distance from the pole, so is the sine of the hour-distance from the meridian to the sine of the azimuth distance from the meridian.

Let the latitude be 51° 30′ north, the declination 15° 9′ south, and the time $II^h\ 24^m$ in the afternoon, when the sun begins to illuminate a vertical wall, and it is required to find the position of the wall.

Then, by the foregoing theorems, the complement of the altitude will be 81° 32½, and

LECT. XI. *P d* the distance from the pole being 109° 5′, and the horary distance from the meridian, or the angle *d P Z*, 36°.

To log sine 74° 51′.....1.98464
Add log. sine 36° 0′.....1.76922

And from the sum.....1.75386
Take the log. sine 81° 32′½.....1.99525
Remains.....1.75861 = log. sine 35°, the azimuth distance south.

When the altitude is given, find from thence the hour, and proceed as above.

This praxis is of singular use on many occasions: in finding the declination of vertical planes more exactly than in the common way, especially if the transit of the sun's centre is observed by applying a ruler with sights, either plane or telescopical, to the wall or plane, whose declination is required.—In drawing a meridian-line, and finding the magnetic variation.—In finding the bearings of places in terrestrial surveys; the transit of the sun over any place, or his horizontal distance from it being observed, together with the altitude and hour.—And thence determining small differences of longitude.—In observing the variation at sea, &c.

The learned Mr. Andrew Reid invented an instrument several years ago, for finding the latitude at sea from two altitudes of the sun, observed on the same day, and the interval of the observations, measured by a common watch. And this instrument, whose only fault was that of its being somewhat expensive, was made by Mr. Jackson. Tables have been lately computed for that purpose.

But we may often, from the foregoing rules, resolve the same problem without much trouble;

especially if we suppose the master of the ship to know within 2 or 3 degrees what his latitude is, Thus, LECT. XI.

Assume the two nearest probable limits of the latitude, and by the theorem $H = \frac{A + LD}{ld}$, compute the hours of observation for both suppositions. If one interval of those computed hours coincides with the interval observed, the question is solved. If not, the two distances of the intervals computed, from the true interval, will give a proportional part to be added to, or subtracted from, one of the latitudes assumed. And if more exactness is required, the operation may be repeated with the latitude already found.

But whichever way the question is solved, a proper allowance is to be made for the difference of latitude arising from the ship's course in the time between the two observations.

Of the double horizontal Dial, and the Babylonian and Italian Dials.

To the *gnomonic* projection, there is sometimes added a *stereographic* projection of the hour-circles, and the parallels of the sun's declination, on the same horizontal plane; the upright side of the gnomon being sloped into an edge, standing perpendicularly over the centre of the projection: so that the dial being in its due position, the shadow of *that* perpendicular edge is a vertical circle passing through the sun, in the stereographic projection.

The months being duly marked on the dial, the sun's declination, and the length of the day at any time, are had by inspection; as also his

LECT. XI. altitude, by means of a scale of tangents. But its chief property is, that it may be placed true, whenever the sun shines, without the help of any other instrument.

Fig. 3. Let *d* be the sun's place in the stereographic projection, *x d y z* the parallel of the sun's declination, Z *d* a vertical circle through the sun's centre, *P d* the hour-circle; and it is evident, that the diameter *N S* of this projection being placed duly north and south, these three circles will pass through the point *d*. And therefore, to give the dial its due position, we have only to turn its gnomon toward the sun, on a horizontal plane, until the hour on the common gnomonic projection coincides with that marked by the hour-circle *P d*, which passes through the intersection of the shadow Z *d* with the circle of the sun's present declination.

The Babylonian and Italian dials reckon the hours, not from the meridian, as with us, but from the sun's rising and setting. Thus, in Italy, one hour before sun-set is reckoned the 23^{d} hour, two hours before sun-set the 22^{d} hour; and so on the rest. And the shadow that marks them on the hour-lines, is *that* of the point of a stile. This occasions a perpetual variation between their dials and clocks, which they must correct from time to time, before it arises to any sensible quantity, by setting their clocks so much faster or slower. And in Italy they begin their day, and regulate their clocks, not from sun-set, but from about mid-twilight, when the *Ave Maria* is said; which corrects the difference that would otherwise be between the clock and the dial.

PLATE XXIII.

The improvements which have been made in all sorts of instruments and machines for mea-

suring time, have rendered such dials of little account. Yet, as the theory of them is ingenious, and they are really, in some respects, the best contrived of any for vulgar use, a general idea of their description may not be unacceptable. LECT. XI.

Let Fig. 5 represent an erect direct south wall, on which a *Babylonian dial* is to be drawn, shewing the hours from sun-rising; the latitude of the place, whose horizon is parallel to the wall, being equal to the angle KCR. Make, as for a common dial, $KG = KR$, (which is perpendicular to CR) the radius of the equinoctial $\text{Æ}\,Q$, and draw RS perpendicular to CK for the stile of the dial; the shadow of whose point R is to mark the hours, when SR is set upright on the plane of the dial. Fig. 5.

Then it is evident, that in the contingent line $\text{Æ}\,Q$, the spaces $K1$, $K2$, $K3$, &c. being taken equal to the tangents of the hour-distances from the meridian, to the radius KG, one, two, three, &c. hours after sun-rising, on the equinoctial day; the shadow of the point R will be found, at these times, respectively in the points 1, 2, 3, &c.

Draw, for the like hours after sun-rising, when the sun is in the tropic of Capricorn ♑ v, the like common lines CD, CE, CF, &c. and at these hours the shadow of the point R will be found in those lines respectively. Find the sun's altitudes above the plane of the dial at these hours, and with their co-tangents Sd, Se, Sf, &c. to radius SR, describe arcs intersecting the hour-lines in the points d, e, f, &c. so shall the right lines $1d$, $2e$, $3f$, &c. be the lines of I, II, III, &c. hours after sun-rising.

The construction is the same in every other

LECT. XI.

case, due regard being had to the difference of longitude of the place at which the dial would be horizontal, and the place for which it is to serve. And likewise, taking care to draw no lines but what are necessary; which may be done, partly by the rules already given for determining the time that the sun shines on any plane, and partly from this, that on the tropical days the hyperbola described by the shadow of the point *R* limits the extent of all the hour-lines.

The most useful, however, as well as the simplest, of such dials, is that which is described on the two sides of the meridian plane.

That the Babylonian and Italic hours are truly enough marked by right lines, is easily shewn. Mark the three points on a globe, where the horizon cuts the equinoctial, and the two tropics, toward the east or west: and turn the globe on its axis 15°, or 1 hour; and it is plain that the three points which were in a great circle (viz. the horizon) will be in a great circle still; which will be projected geometrically into a straight line. But these three points are universally the sun's places, one hour after sun-set (or one hour before sun-rise) on the equinoctial and solstitial days. The like is true of all other circles of declination, beside the tropics; and therefore, the hours on such dials are truly marked by straight lines limited by the projections of the tropics; and which are rightly drawn, as in the foregoing example.

Note 1. The same dials may be delineated without the hour-lines, *CD*, *CE*, *CF*, &c. by setting off the sun's azimuths on the plane of the dial, from the centre *S*, on either side of the substile *CSK*, and the corresponding co-

tangents of altitude from the same centre *S*, for I, II, III, &c. hours before or after the sun is in the horizon of the place for which the dial is to serve, on the equinoctial and solstitial days. LECT. XI.

2. One of these dials has its name from the hours being reckoned from sun-rising, the beginning of the Babylonian day. But we are not thence to imagine that the *equal* hours, which it shews, were those in which the astronomers of that country marked their observations. These, we know with certainty, were unequal, like the Jewish, as being twelfth parts of the natural day: and an hour of the night was, in like manner, a twelfth part of the night; longer or shorter, according to the season of the year. So that an hour of the day, and an hour of the night, at the same place, would always make $\frac{1}{12}$ of 24, or 2 equinoctial hours. In Palestine, among the Romans, and in several other countries, 3 of these unequal nocturnal hours were a *vigilia*, or *watch*. And the reduction of equal and unequal hours into one another is extremely easy. If, for instance, it is found, by a foregoing rule, that in a certain latitude, at a given time of the year, the length of a day is 14 equinoctial hours, the unequal hours is then $\frac{14}{12}$ or $\frac{7}{6}$ of an hour, that is, 70 minutes; and the nocturnal hour is 50 minutes. The first watch begins at VII (sun-set); the second at three times 50 minutes after, viz. IX ^{h} 30 ^{m}; the third always at midnight; the morning watch at half an hour past II.

If it were required to draw a dial for shewing these unequal hours, or twelfth parts of the day, we must take as many declinations of the sun as are thought necessary, from the equator toward each tropic: and having computed the sun's

LECT. XI.

altitude and azimuth for $\frac{1}{12}$, $\frac{2}{12}$, $\frac{3}{12}$ths parts, &c. of each of the diurnal arcs belonging to the declinations assumed: by these, the several points in the circles of declination, where the shadow of the stile's point falls, are determined; and curve lines drawn through the points of a homologous division will be the hour-lines required. [1]

Of the right placing of dials, and having a true meridian line for the regulation of clocks and watches. [2]

The plane on which the dial is to rest, being duly prepared, and every thing necessary for

---

[1] For the description of a new dial, invented by Lambert, and of a curious Analemmatic dial, which can be properly placed without a mariner's needle, or a meridian line, and which can be drawn in a garden, the spectator being its stile, see Appendix—Ed.

[2] In another work, when speaking upon the placing of sun-dials, our author observes, 'that if the dial be made 'according to the strictest rules of calculation, and be 'truly set at the instant when the sun's centre is on the 'meridian, it will be a minute too fast in the forenoon, 'and a minute too slow in the afternoon, by the shadow 'of the stile; for the edge of the shadow that shews the 'time is even with the sun's foremost edge all the time be-'fore noon, and even with his hindermost all the afternoon 'on the dial. And it is the sun's centre that determines 'the time in the supposed hour-circles of the heavens. 'And as the sun is half a degree in breadth, he takes two 'minutes to move through a space equal to his breadth, 'so that there will be two minutes at noon in which the 'shadow will have no motion at all on the dial; conse-'quently, if the dial be set true by the sun in the fore-'noon, it will be two minutes too slow in the afternoon; 'and

fixing it, you may find the hour tolerably exact by a large equinoctial ring-dial, and set your watch to it. And then the dial may be fixed by the watch at your leisure. LECT. XI.

If you would be more exact, take the sun's altitude by a good quadrant, noting the precise time of observation by a clock or watch. Then, compute the time for the altitude observed (by the rule, page 57); and set the watch to agree with that time, according to the sun. A Hadley's quadrant is very convenient for this purpose; for, by it you may take the angle between the sun and his image, reflected from a bason of water: the half of which angle, subtracting the refraction, is the altitude required. This is best done in summer, and the nearer the sun is to the prime vertical (the east or west azimuth) when the observation is made, so much the better.

Or, in summer, take two equal altitudes of the sun in the same day; one any time between seven and ten in the morning, the other between two and five in the afternoon; noting the moments of these two observations by a clock

---

'and if it be set true in the afternoon, it will be two mi-'nutes too fast in the forenoon. The only way that I 'know of to remedy this is, to set every hour and minute 'division on the dial one minute nearer 12 than the cal-'culation makes it to be. Tables and Tracts, 2d edit. p. 73. These observations are new, and just enough in themselves; but the evil which the author points out may be remedied by observing the middle of the shadow's penumbra, which corresponds with the sun's centre, instead of the border of the real shadow; and I believe it will be found, that every person naturally does this when he determines the hour of the day upon a sun-dial.—Ed.

LECT. XI.

or watch: and if the watch shews the observations to be at equal distances from noon, it agrees exactly with the sun; if not, the watch must be corrected by half the difference of the forenoon and afternoon intervals; and then the dial may be set true by the watch.

Thus, for example, suppose you have taken the sun's altitude when it was twenty minutes past VIII in the morning by the watch, and found, by observing in the afternoon, that the sun had the same altitude ten minutes before IV, then it is plain, that the watch was five minutes too fast for the sun: for five minutes after XII is the middle time between VIII^{h} 20^{m} in the morning, and III^{h} 50^{m} in the afternoon; and therefore, to make the watch agree with the sun, it must be set back five minutes.[3]

A meridian line.

A good *meridian line*, for regulating clocks or watches, may be had by the following method.

Make a round hole, almost a quarter of an inch diameter, in a thin plate of metal; and fix the plate in the top of a south window, in such a manner, that it may recline from the zenith at an angle equal to the co-latitude of your place, as nearly as you can guess; for then the

---

[3] The above method of finding the hour of the day by corresponding altitudes of the sun or stars, is the easiest and most correct that can be employed. Owing, however, to the change that takes place in the sun's declination before the afternoon altitude is taken, it is liable to an error, which, at a maximum, amounts to 30″ in the time of the equinoxes. A table containing this correction, which depends upon the interval between the altitudes, and upon the declination of the sun, may be seen in the Astronomie de la Lande, edit. 3^{e}, tom. i, Tables, p. 37, and in the Tables de Berlin, tom. i, p. 291.

plate will face the sun directly at noon on the equinoctial days. Let the sun shine freely through the hole into the room; and hang a plumb-line to the ceiling of the room, at least five or six feet from the window, in such a place as that the sun's rays, transmitted through the hole, may fall upon the line when it is noon by the clock; and having marked the said place on the ceiling, take away the line. LECT XI.

Having adjusted a sliding bar to a dove-tail groove, in a piece of wood about eighteen inches long, and fixed a hook in the middle of the bar, nail the wood to the above-mentioned place on the ceiling, parallel to the side of the room in which the window is; the groove and bar being toward the window. Then hang the plumb-line upon the hook of the bar, the weight or plummit reaching almost to the floor; and the whole will be prepared for farther and proper adjustment.

This done, find the true solar time by either of the two last methods, and thereby regulate your clock. Then, at the moment of next noon by the clock, when the sun shines, move the sliding bar in the groove until the shadow of the plumb-line bisects the image of the sun (made by his rays transmitted through the hole) on the floor, wall, or on a white screen placed on the north side of the line; the plummet or weight at the end of the line hanging freely in a pail of water placed below it on the floor. But because this may not be quite correct for the first time, on account that the plummet will not settle immediately, even in water; it may be farther corrected on the following days, by the above method, with the sun and clock, and so brought to a very great exactness.

LECT. XI.

N. B. The rays transmitted through the hole will cast but a faint image of the sun, even on a white screen, unless the room be so darkened that no sun-shine may be allowed to enter but what comes through the small hole in the plate. And always, for some time before the observation is made, the plummet ought to be immersed in a jar of water, where it may hang freely; by which means the line will soon become steady, which otherwise would be apt to continue swinging.

As this meridian line will not only be sufficient for regulating clocks and watches to the true time by equation tables, but also for most astronomical purposes, I shall say nothing of the magnificent and expensive meridian lines at Bologna and Rome, nor of the better methods by which astronomers observe precisely the transits of the heavenly bodies over the meridian.[4]

---

[4] For farther information upon dialing, the reader may consult Orontii Finei opera, Fol. lib. iii.—De horologiis Sciothericis a Joanne Voello, Turoni 1608.—Horologiographia per Sebastianum, Munsterum 1533.—Christ. Clavii Bambergensis horologiorum nova descriptio.—Demonstratio et constructio horologiorum novorum, auctore Georgio Schombergero.—Gnomonice Schoner qto.—Wolfii oper. Mathemat. tom. ii, p. 787, Ferguson's Select Exercises, Leybourn's Dialing, Leadbetter's Dialing, and an excellent treatise by the celebrated Deparcieux, published at the end of his *Traite de Trigonometrie rectiligne et spherique*. This subject is treated more profoundly by M. Sejour, in his *Recherches sur la Gnomonique*, 1761, and in his *Traite Analytique*, tom. i, p, 705.

LECTURE XII.

SHEWING HOW TO CALCULATE THE MEAN TIME OF ANY NEW OR FULL MOON, OR ECLIPSE, FROM THE CREATION OF THE WORLD TO THE YEAR OF CHRIST 5800.

Calculation of new and full moons.

IN the following tables, the mean lunation is about a 20th part of a second of time longer than its measure, as now printed in the last edition of my Astronomy; which makes the difference of a hour and thirty minutes in 3000 years. —But this is not material, when only the mean times are required.

PRECEPTS.

To find the mean time of any New or Full Moon in any given year and month after the Christian æra.

1. If the given year be found in the third column of the *table of the moon's mean motion from the sun*, under the title, *years before and after Christ;* write out that year, with the mean motions belonging to it, and thereto join the given month with its mean motions. But, if the given year be not in the table, take out the next lesser one to it that you find, in the same column;

LECT. XII. and thereto add as many *complete years*, as will make up the given year: then, join the month and all the respective mean motions.

2. Collect these mean motions into one sum of signs, degrees, minutes, and seconds; remembering that 60 seconds (″) make a minute, 60 minutes (′) a degree; 30 degrees (°) a sign, and 12 signs (ˢ) a circle. When the signs exceed 12, or 24, or 36 (which are whole circles), reject them, and set down only the remainder; which, together with the odd degrees, minutes, and seconds, already set down, must be reckoned the whole sum of the collection.

3. Subtract the result, or sum of this collection, from 12 signs; and write down the remainder. Then look in the table under *days*, for the next less mean motions to this remainder, and subtract them from it, writing down their remainder.

This done, look in the table under *hours* (marked H) for the next less mean motions to this last remainder, and subtract them from it, writing down their remainder.

Then look in the table under *minutes* (marked M) for the next less mean motions to this remainder, and subtract them from it, writing down their remainder.

Lastly, look in the table under *seconds* (marked S) for the next less mean motion to this remainder, either greater or less; and against it you have the seconds answering thereto.

4. And these times collected, will give the mean time of the *required new moon*; which will be right in common years; and also in January

and February in leap years; but always one day too late in leap years after February. LECT. XII.

EXAMPLE I.

Required the time of new moon in September 1764?

(A year not inserted in the table.)

	Moon from sun. s	°	′	″
To the year after Christ's birth 1753	10	9	24	56
Add complete years 11	0	10	14	20
(sum 1764)				
And join September	2	22	21	8
The sum of these mean motions is	1	12	0	24
Which, being subtracted from a circle, or	12	0	0	0
Leaves remaining	10	27	59	36
Next less mean motion for twenty-six days, subtract	10	16	57	34
And there remains		1	2	2
Next less mean motion for two hours, subtract		1	0	57
And the remainder will be			1	5
Next less mean motion for two minutes, subtract			1	1
Remains the mean motion of twelve seconds, ...				4

These times, being collected, would shew the mean time of the required new moon in September 1764, to be on the 29th day, at $2^h\ 2^m\ 12^s$ past noon. But, as it is in a leap year, and after February, the time is one day too late. So, the true mean time is September the 25th, at $2^m\ 12^s$ past II in the afternoon.

LECT. XII.

N. B. The tables always begin the day at noon, and reckon thenceforward, to the noon of the day following.

To find the mean time of full moon in any given year and month after the Christian æra.

Having collected the moon's mean motion from the sun for the beginning of the given year and month, and subtracted their sum from twelve signs (as in the former example), add six signs to the remainder, and then proceed in all respects as above.

EXAMPLE II.

Required the mean time of full moon in September 1764?

	Moon from sun. s	°	′	″
To the year after Christ's birth 1753	10	9	24	56
Add complete years 11	0	10	14	20
(sum 1764)				
And join September	2	22	21	8
The sum of these mean motions is	1	12	0	24
Which, being subtracted from a circle, or	12	0	0	0
Leaves remaining	10	17	59	36
To which remainder add	6	0	0	0
And the sum will be	4	17	59	36
Next less mean motion for eleven days, subtract	4	14	5	54
And there remains		3	53	42
Next less mean motion for seven hours, subtract		3	33	20
And the remainder will be			20	22
Next less mean motion for forty minutes, subtract			20	19
Remains the mean motion for eight seconds				3

So, the mean time, according to the tables, is the 11th of September, at 7h 40m 8s past noon. One day too late, being after February in a leap year.

And thus may the mean time of any new or full moon be found, in any year after the Christian æra.

To find the mean time of new or full moon in any given year and month before the Christian æra.

If the given year before the year of Christ 1 be found in the third column of the table, under the title of *years before and after Christ*, write it out, together with the given month, and join the mean motions. But, if the given year be not in the table, take out the next greater one to it that you find; which being still farther back than the given year, add as many complete years to it as will bring the time forward to the given year; then join the month, and proceed in all respects as above.

EXAMPLE III.

Required the mean time of new moon in May, the year before Christ 585?

The next greater year in the table is 600; which being 15 years before the given year, add the mean motions for 15 years to those of 600, together with those for the beginning of May.

LECT. XII.		Moon from sun. s	°	′	″
	To the year before Christ 600	5	11	6	16
	Add complete years motion 15	6	0	55	24
	And the mean motion for May	0	22	53	23
	The whole sum is	0	4	55	3
	Which, being subtracted from a circle, or	12	0	0	0
	Leaves remaining	11	25	4	57
	Next less mean motion for twenty-nine days, subtract	11	23	31	54
	And there remains		1	33	3
	Next less mean motion for three hours, subtract		1	31	26
	And the remainder will be			1	37
	Next less mean motion for three minutes, subtract			1	31
	Remains the mean motion of fourteen seconds, ...				6

So the mean time, by the tables, was the 29th of May at $3^h\ 3^m\ 14^s$ past noon: a day later than the truth, on account of its being in a leap year. For as the year of Christ 1 was the first after a leap year, the year 585 before the year 1 was a leap year of course.

If the given year be after the Christian æra, divide its date by 4, and if nothing remains, it is a leap year in the old stile. But if the given year was before the Christian æra (or year of Christ 1), subtract one from its date, and divide the remainder by 4; then, if nothing remains, it was a leap year; otherwise not.

To find whether the sun is eclipsed at the time of any given change, or the moon at any given full.

LECT. XII. Of eclipses.

From the *table of the sun's mean motion* (or distance) *from the moon's ascending node*, collect the mean motions answering to the given time; and if the result shews the sun to be within 18° of either of the nodes at the time of new moon, the sun will be eclipsed at that time. Or, if the result shews the time to be within 12° of either of the nodes at the time of full moon, the moon will be eclipsed at that time, in or near the contrary node; otherwise not.

EXAMPLE IV.

The moon changed on the 26th of September 1764, at 2h 2m (neglecting the seconds) afternoon. (See Example I). Qu. *Whether the sun was eclipsed at that time?*

		Sun from node. s	°	′	″
To the year after Christ's birth	1753	1	28	0	19
Add complete years	11	7	2	3	56
(sum 1764)					
And September		8	12	22	49
26 days			27	0	13
2 hours				5	12
2 minutes					5
Sun's distance from the ascending node		6	9	32	34

Now, as the descending node is just opposite to the ascending (viz. six signs distant from it), and the tables shew only how far the sun has gone from the ascending node, which, by this example, appears to be 6s 9° 32′ 34″, it is

LECT. XII.

plain that he must have then been eclipsed; as he was then only 9^{s} 32′ 34″ short of the descending node.

EXAMPLE V.

The moon was full on the 11th *of September* 1764, *at* 7^{h} 40^{m} *past noon.* (See Example II.) Qu. *Whether she was eclipsed at that time?*

		Sun from node. s	°	′	″
To the year after Christ's birth	1753	1	28	0	19
Add complete years	11	7	2	3	56
(sum 1764)					
And September		8	12	22	49
11 days, ...			11	25	29
7 hours				18	11
40 minutes				1	44
Sun's distance from the ascending node		5	24	12	28

Which being subtracted from six signs, leaves only 5° 47′ 32″ remaining; and this being all the space that the sun was short of the descending node, it is plain that the moon must then have been eclipsed, because she was just as near the contrary node.

EXAMPLE VI.

Q. Whether the sun was eclipsed in May, the year before Christ 585? (See Example III.)

	Sun from node. s	°	′	″	
To the year before Christ 600	9	9	23	51	LECT. XII.
Add the mean motion of 15 complete years	9	19	27	49	
And May	4	4	37	57	
29 days	1	0	7	10	
3 hours			7	48	
3 minutes (neglecting the seconds)				8	
Sun's distance from the ascending node	0	3	44	43	

Which being less than 18°, shews that the sun was eclipsed at that time.

This eclipse was foretold by Thales, and is thought to be the eclipse which put an end to the war between the Medes and Lydians. Thales's eclipse.

The times of the *sun's conjunction with the nodes*, and consequently the *eclipse months* of any given year, are easily found by the *Tables of the sun's mean motion from the moon's ascending node;* and much in the same way as the mean conjunctions of the sun and moon are found by the table of the moon's mean motions from the sun. For, collect the sun's mean motion from the node (which is the same as his distance gone from it) for the beginning of any given *year*, and subtract it from 12 signs; then, from the remainder, subtract the next less mean motions belonging to whatever *month* you find them in the table; and from the remainder subtract the next less mean motion for *days*, and so on for *hours* and *minutes;* the result of all which will shew the time of the sun's mean conjunction with the *ascending node* of the moon's orbit. When eclipses must happen.

EXAMPLE VII.

Required the time of the sun's conjunction with the ascending node in the year 1764 *?*

LECT XII.		Sun from node. s	o	′	″
	To the year after Christ's birth 1753	1	28	0	19
	Add complete years 11	7	2	3	56
	Mean distance at beginning of A. D. ..... 1764 ..	9	0	4	15
	Subtract this distance from a circle, or	12	0	0	0
	And there remains	2	29	55	45
	Next less mean motion for March, subtract	2	1	16	39
	And the remainder will be		28	39	6
	Next less mean motion for 27 days, subtract		28	2	32
	And there remains			36	34
	Next less mean motion for 14 hours subtract			36	21
	Remains, nearly, the mean motion of 5 minutes				13

Hence it appears, that the sun will pass by the moon's *ascending node* on the 27th of March, at 14^{h} 5^{m} past noon, viz. on the 28th day, at 5^{m} past II in the morning, according to the tables; but this being in a leap year, and after February, the time is one day too late. Consequently, the true time is at 5^{m} past II in the morning on the 27th day; at which time the descending node will be directly opposite to the sun.

If 6 signs be added to the remainder arising

from the first subtraction, (viz. from 12 signs) and then the work carried on as in the last example, the result will give the mean time of the sun's conjunction with the descending node. Thus, in

LECT. XII

EXAMPLE VIII.

To find when the sun will be in conjunction with the descending node in the year 1764?

	Sun from node. s	°	′	″
To the year after Christ's birth 1753	1	28	0	19
Add complete years 11	7	2	3	56
Mean distance from ascending node at beginning of 1764	9	0	4	15
Subtract this distance from a circle, or,	12	0	0	0
And the remainder will be, ...	2	29	55	45
To which add half a circle, or	6	0	0	0
And the sum will be	8	29	55	45
Next less mean motion for September subtracted	8	12	22	49
And there remains		17	32	56
Next less mean motion for 16 days subtracted		16	37	4
And the remainder will be			55	52
Next less mean motion for 21 hours subtracted			54	32
Remains, nearly, the mean motion of 31 minutes			1	20

So that, according to the tables, the sun will be in conjunction with the *descending node* on the 16th of September, at 21 hours 31 minutes

LECT. XII.

past noon: one day later than the truth, on account of the leap-year.

The limits of eclipses.

When the moon changes within 18 days before or after the sun's conjunction with either of the nodes, the sun will be eclipsed at that change: and when the moon is full within 12 days before or after the time of the sun's conjunction with either of the nodes, she will be eclipsed at the full: otherwise not.

Their period and restitution.

If to the mean time of any eclipse, either of the sun or moon, we add 557 Julian years 21 days 18 hours 11 minutes and 51 seconds (in which there are exactly 6890 mean lunations) we shall have the mean time of another eclipse.[5] For at

---

[5] Dr. HALLEY's period of eclipses contains only 18 years 11 days 7 hours 43 minutes 20 seconds; in which time, according to his tables, there are just 223 mean lunations: but, as in that time, the sun's mean motion from the node is no more than 11° 29° 31′ 49″, which wants 28′ 11″ of being as nearly in conjunction with the same node at the end of the period as it was at the beginning, this period cannot be of constant duration for finding eclipses, because it will in time fall quite without their limits. The following tables make this period 31″ shorter, as appears by the calculation annexed.[a]

The period.	Moon from the sun.				Sun from node.			
	°	°	′	″	°	°	′	″
Complete years,..... 18—	7	11	59	4—	11	17	46	18
——— days..... 11—	4	14	5	54—		11	25	29
——— hours..... 7—		3	33	20—			18	11
——— minutes..... 42—			21	20—			1	49
——— seconds..... 44—				22—				2
Mean motions..... —0	0	0	0	0—	11	29	31	49

[a] By computing from the new solar tables of De Lambre, and the lunar tables of Mayer, as improved by Mason, this short period of eclipses, which is generally called the period of Pliny, or the Chaldaic period, will amount only to 18 years 11 days 7 hours 42 minutes and 31 seconds; and the sun's distance from the moon's node to 28′ 10′.—ED.

the end of that time the moon will be either new or full, according as we add it to the time of new or full moon; and the sun will be only 45″ farther from the same node, at the end of the said time, than he was at the beginning of it; as appears by the following example.[6] LECT. XII.

The period.	Moon from sun. s	o	′	″	Sun from node. s	o	′	″
Complete years 500	—3	5	32	47	—10	14	45	8
40	—8	26	50	37	— 1	23	58	49
17	—3	2	21	39	—10	28	40	55
days..... 21	—8	16	0	21	—	21	48	38
hours..... 18	—	9	8	35			46	44
minutes.... 11	—		5	35	—			29
seconds.... 51				26	—			2
Mean motions	—0	0	0	0	—0	0	0	45

And this period is so very near, that in 6000 years it will vary no more from the truth as to the restitution of eclipses, than $8\frac{1}{4}$ minutes of a degree; which may be reckoned next to nothing. It is the shortest in which, after many trials, I can find so near a conjunction of the sun, moon, and the same node.

[6] The period here mentioned by Mr. Ferguson amounts only to 557 years 21 days 18 hours 4 minutes 47 seconds; and the sun's distance from the moon's node is fully 1′ 41″. —Ed.

LECT. XII. This table is made by the continual addition of a mean lunation, viz. $29^{d}\ 12^{h}\ 44^{m}\ 3^{s}\ 6^{th}\ 12^{iv}\ 14^{v}\ 24^{vi}\ 0^{vii}$.

Lun.	Contain Days.	H.	M.	S.	Th.
1	29	12	44	3	6
2	59	1	28	6	13
3	88	14	12	9	19
4	118	2	56	12	25
5	147	15	40	15	32
6	177	4	24	18	38
7	206	17	8	21	44
8	236	5	52	24	51
9	265	18	36	27	57
10	295	7	20	31	3
20	590	14	41	2	7
30	885	22	1	33	11
40	1181	5	22	4	14
50	1476	12	42	35	18
100	2953	1	25	10	35
200	5906	2	50	21	11
300	8859	4	15	31	46
400	11812	5	40	42	22
500	14756	7	5	52	57
1000	29530	14	11	45	54
2000	59061	4	23	31	48
3000	88591	18	35	17	42
4000	118122	8	47	3	36
5000	147652	22	58	49	30
10000	295305	21	57	39	0
20000	590611	19	55	18	0
30000	885917	17	52	57	0
40000	1181223	15	50	36	0
50000	1476529	13	48	15	0
100000	2953059	3	36	39	0

In 100000 mean lunations there are 8085 Julian years 12 days 21 hours 36 minutes 30 seconds 2953059 days 3 hours 36 minutes 30 seconds.

Proof of the Table.

		Moon fr. sun. °	'	"
In Jul. years.	4000	1 14	22	12
	4000	1 14	22	12
	80	5 23	41	15
	5	10 0	18	28
Days	12	4 26	17	20
Hours	21	10	40	1
Min.	36		18	7
Sec.	20			15
M. fr. sun.		0 0	0	0

Having by the former precepts computed the mean time of new moon in January, for any given year, it is easy, by this Table, to find the mean time of new moon in January for any number of years afterwards: and by means of a small table of lunations for 12 or 13 months, to make a general table for finding the mean time of new or full moon in any given year and month whatever.

	D.	H.	M.	S.	Th.
In 11 lunations there are	324	20	4	34	10.
In 12 lunations	354	8	48	37	16.
In 13 lunations	383	21	32	40	23.

But then it would be best to begin the year with March, to avoid the inconvenience of losing a day by mistake in leap year.

A Table of the Moon's mean Motion from the Sun.

Years of the Julian period.	Years of the World	Years before and after Christ.	Moon from sun ° ′ ″	Complete years.	Moon from sun. ° ′ ″
706	0	4008	5 28 1 17	11	0 10 14 20
714	8	4000	5 9 23 24	12	5 2 3 11
1714	1008	3000	11 20 28 57	13	9 11 40 35
2714	2008	2000	6 1 34 30	14	1 21 18 0
3714	3008	1000	0 12 40 3	15	6 0 55 24
3814	3108	900	10 19 46 36	16	10 22 44 15
3914	3208	800	8 26 53 9	17	3 2 21 39
4014	3308	700	7 3 59 43	18	7 11 59 4
4114	3408	600	5 11 6 16	19	11 21 36 27
4214	3508	500	3 18 12 49	20	4 13 25 49
4314	3608	400	1 25 19 23	40	8 26 50 37
4414	3708	300	0 2 25 56	60	1 10 15 56
4514	3808	200	10 9 32 29	80	5 23 41 15
4614	3908	100	8 16 39 3	100	10 7 6 33
4714	4008	1	6 23 45 36	200	8 14 13 7
4814	4108	101	5 0 52 9	300	6 21 19 40
4914	4208	201	3 7 58 43	400	4 28 26 13
5014	4308	301	1 15 5 16	500	3 5 32 47
5114	4408	401	11 22 11 49	1000	6 11 5 33
5214	5508	501	9 29 18 23	2000	0 22 11 6
5714	5008	1001	1 4 51 9	3000	7 3 16 39
6414	5708	1701	0 24 37 2	4000	1 14 22 12
6466	5760	1753	10 9 24 56		
6514	5808	1801	6 5 26 15		

After Christ.

Before the Year of Christ 1.

Months.	Moon from sun. ° ′ ″
Jan.	0 0 0 0
Feb.	0 17 54 48
Mar.	11 29 15 16
April	0 17 10 3
May	0 22 53 23
June	1 10 40 11
July	1 16 31 32
Aug.	2 4 6 20
Sept.	2 22 21 8
Oct.	2 28 4 29
Nov.	3 15 59 17
Dec.	3 21 42 7

Complete years.	Moon from sun. ° ′ ″
1	4 9 37 24
2	4 19 14 8
3	0 28 52 13
4	5 20 41 4
5	10 0 18 28
6	2 9 55 52
7	6 19 33 17
8	11 11 22 7
9	3 20 59 32
10	8 0 36 55

Julian years, 3 of which have 365 days, and the 4th 366.

The 4008th year before the year of Christ 1, was the 4007th year before the year of his birth; and is supposed to have been the year of the creation.

This table agrees with the *old stile* until the year 1753; and after that with the *new*.

LECT. XII.

A Table of the Moon's mean motion from the Sun.

Days.	Moon from sun. ° ′ ″				Moon from sun. H. M. S.	° ′ ″ ′ ″ ‴			Moon from sun. M. S. Th.	′ ″ ‴ ″ ″ ⁗ ‴ ⁗ ⁗		
1	0	12	11	27								
2	0	24	22	53								
3	1	6	34	20	1	0	30	29	31	15	44	47
4	1	18	45	47	2	1	0	57	32	16	15	16
5	2	0	57	13	3	1	31	26	33	16	45	44
6	2	13	8	40	4	2	1	54	34	17	16	13
7	2	25	20	7	5	2	32	23	35	17	46	42
8	3	7	31	34	6	3	2	52	36	18	17	10
9	3	19	43	0	7	3	33	20	37	18	47	39
10	4	1	54	27	8	4	3	49	38	19	18	7
11	4	14	5	54	9	4	34	18	39	19	48	36
12	4	26	17	20	10	5	4	46	40	20	19	5
13	5	8	28	47	11	5	35	15	41	20	49	33
14	5	20	40	14	12	6	5	43	42	21	20	2
15	6	2	51	40	13	6	36	12	43	21	50	31
16	6	15	3	7	14	7	6	41	44	22	20	59
17	6	27	14	34	15	7	37	9	45	22	51	28
18	7	9	26	0	16	8	7	38	46	23	21	56
19	7	21	37	27	17	8	38	6	47	23	52	25
20	8	8	48	54	18	9	8	35	48	24	22	54
21	8	16	0	21	19	9	39	4	49	24	53	22
22	8	28	11	47	20	10	9	32	50	25	23	51
23	9	10	23	14	21	10	40	1	51	25	54	19
24	9	22	34	41	22	11	10	30	52	26	24	48
25	10	4	46	7	23	11	40	58	53	26	55	17
26	10	16	57	34	24	12	11	27	54	27	25	45
27	10	29	9	1	25	12	41	55	55	27	56	14
28	11	11	20	27	26	13	12	24	56	28	26	43
29	11	23	31	54	27	13	42	53	57	28	57	11
30	0	5	43	21	28	14	13	21	58	29	27	40
31	0	17	54	48	29	14	43	50	59	29	58	8
32	1	0	6	14	30	15	14	18	60	30	28	37

1 Lunation = $29^{d}\ 12^{h}\ 44^{m}\ 3^{s}\ 6^{th}\ 21^{iv}\ 14^{v}\ 24^{vi}\ 0^{vii}$

In leap years, after February, a day and its motion must be added to the time for which the moon's mean distance from the sun is given. But when the mean time of any new or full moon is required in leap year after February, a day must be subtracted from the mean time thereof, as found by the tables. In common years they give the day right.

A Table of the Sun's mean Motion from the Moon's ascending node.

LECT. XII.

Years of the Julian Period.	Years of the World.	Years before and after Christ.	Sun from node. s	°	′	″
706	0	4008	7	6	17	9
714	8	4000	0	11	4	55
1714	1008	3000	9	10	35	11
2714	2008	2000	6	10	5	28
3714	3008	1000	3	9	35	44
3814	3108	900	7	24	32	46
3914	3208	800	0	9	29	48
4014	3308	700	4	24	26	49
4114	3408	600	9	9	23	51
4214	3508	500	1	24	20	53
4314	3608	400	6	9	17	54
4414	3708	300	10	24	14	56
4514	3808	200	3	9	11	58
4614	3908	100	7	24	8	59
4714	4008	1	0	9	6	1
4814	4108	101	4	24	3	3
4914	4208	201	9	9	0	4
5014	4308	301	1	23	57	6
5114	4408	401	6	8	54	8
5214	4508	501	10	23	51	9
5714	5008	1001	9	8	36	18
6414	5708	1701	4	23	15	30
6466	5760	1753	1	28	0	19
6514	5808	1801	8	25	44	44

Before the year of Christ 1. — After Christ.

The 4008th year yefore the year of Christ 1, was the 4007th year before the year of his birth; and is supposed to have been the year of the creation.

Complete years.	Sun from node. s	°	′	″
1	0	19	5	23
2	1	8	10	47
3	1	27	16	10
4	2	17	23	53
5	3	6	29	16
6	3	25	34	40
7	4	14	40	3
8	5	4	47	46
9	5	23	53	9
10	6	12	58	33

Julian years, 3 of which have 365 days, and the 4th 366.

Complete years.	Sun from node. s	°	′	″
11	7	2	3	56
12	7	22	11	39
13	8	11	17	2
14	9	0	22	25
15	9	19	27	49
16	10	9	35	31
17	10	28	40	55
18	11	17	46	18
19	0	6	51	43
20	0	26	59	24
40	1	23	58	49
60	2	20	58	13
80	3	17	57	37
100	4	14	57	2
200	8	29	54	3
300	1	14	51	5
400	5	29	48	7
500	10	14	45	8
1000	8	29	30	17
2000	5	29	0	33
3000	2	28	30	50
4000	11	28	1	6

Months.	Sun from node. s	°	′	″
Jan.	0	0	0	0
Feb.	1	2	11	48
Mar.	2	1	16	39
April	3	3	28	27
May	4	4	37	57
June	5	6	49	45
July	6	7	59	14
Aug.	7	9	11	1
Sept.	8	12	22	49
Oct.	9	13	32	18
Nov.	10	15	44	5
Dec.	11	16	53	34

This table agrees with the *old stile* until the year 1753; and after that, with the *new*.

LECT. XII.

A Table of the Sun's mean Motion from the Moon's Ascending Node.

Days.	Sun from node. ° ′ ″	Sun from node. H. M. S. ° ′ ″	Sun from node. M. S. Th. ′ ″ ‴
1	0 1 2 19		
2	0 2 4 38		
3	0 3 6 57	1 0 2 36	31 1 20 31
4	0 4 9 16	2 0 5 12	32 1 23 7
5	0 5 11 36	3 0 7 48	33 1 25 43
6	0 6 13 54	4 0 10 23	34 1 28 9
7	0 7 16 13	5 0 12 59	35 1 31 55
8	0 8 18 32	6 0 15 35	36 1 33 31
9	0 9 20 51	7 0 18 11	37 1 36 6
10	0 10 23 10	8 0 20 47	38 1 38 42
11	0 11 25 29	9 0 23 23	39 1 41 18
12	0 12 27 48	10 0 25 58	40 1 43 54
13	0 13 30 7	11 0 28 33	41 1 46 36
14	0 14 32 26	12 0 31 9	42 1 49 5
15	0 15 34 15	13 0 33 45	43 1 51 41
16	0 16 37 4	14 0 36 21	44 1 54 17
17	0 17 39 23	15 0 38 57	45 1 56 53
18	0 18 41 41	16 0 41 32	46 1 59 29
19	0 19 44 0	17 0 44 8	47 2 2 5
20	0 20 46 19	18 0 46 44	48 2 4 41
21	0 21 48 38	19 0 49 20	49 2 7 17
22	0 22 50 57	20 0 51 56	50 2 9 53
23	0 23 53 16	21 6 54 32	51 2 12 29
24	0 24 55 35	22 0 57 8	52 2 15 5
25	0 25 57 54	23 0 59 43	53 2 17 41
26	0 27 0 13	24 1 2 19	54 2 20 17
27	0 28 2 32	25 1 4 55	55 2 22 53
28	0 29 4 51	26 1 7 31	56 2 25 29
29	1 0 7 10	27 1 10 7	57 2 28 4
30	1 1 9 29	28 1 12 43	58 2 30 40
31	1 2 11 48	29 1 15 9	59 2 33 16
32	1 3 14 47	30 1 17 55	60 2 35 52

In leap years, after February, add one day and one day's motion to the time at which the sun's mean distance from the ascending node is required.

A SUPPLEMENT

TO THE

PRECEDING LECTURES,

BY THE AUTHOR.

MECHANICS.

The Description of a new and safe Crane, which has four different powers, adapted to different weights.[1]

THE common crane consists only of a large wheel and axle; and the rope, by which goods are drawn up from ships, or let down from the quay to them, winds or coils round the axle, as the axle is turned by men walking in the wheel. But, as these engines have nothing

Description of a new crane.

[1] Our author received a reward of fifty pounds for the invention of this crane, from the Society for the encouragement of Arts; and a description of it was honoured with a place among the Transactions of the Royal Society of London, see vol. xlv, p. 42.—Ed.

to stop the weight from running down, if any of the men happen to trip or fall in the wheel, the weight descends, and turns the wheel rapidly backward, and tosses the men violently about within it; which has produced melancholy instances, not only of limbs broke, but even of lives lost, by the ill-judged construction of cranes. And besides, they have but one power for all sorts of weights; so that they generally spend as much time in raising a small weight as in raising a great one.

These imperfections and dangers induced me to think of a method for remedying them. And for that purpose, I contrived a crane with a proper stop to prevent the danger, and with different powers suited to different weights; so that there might be as little loss of time as possible: and also, that when heavy goods are let down into ships, the descent may be regular and deliberate.

This crane has four different powers: and, I believe, it might be built in a room eight feet in width: the gib being on the outside of the room.

Three trundles, with different numbers of staves, are applied to the cogs of a horizontal wheel with an upright axle; and the rope that draws up the weight coils round the axle. The wheel has ninety-six cogs, the largest trundle twenty-four staves, the next largest has twelve, and the smallest has six. So that the largest trundle makes four revolutions for one revolution of the wheel: the next makes eight, and the smallest makes sixteen. A winch is occasionally put upon the axis of either of these trundles, for turning it; the trundle being then used that gives a power best suited to the weight:

and the handle of the winch describes a circle in every revolution equal to twice the circumference of the axle of the wheel. So that the length of the winch doubles the power gained by each trundle.

As the power gained by any machine, or engine whatever, is, in direct proportion, as the velocity of the power is to the velocity of the weight; the powers of this crane are easily estimated, and they are as follows.—

If the winch be put upon the axle of the largest trundle, and turned four times round, the wheel and axle will be turned once round: and the circle described by the power that turns the winch, being, in each revolution, double the circumference of the axle, when the thickness of the rope is added thereto; the power goes through eight times as much space as the weight rises through: and therefore (making some allowance for friction) a man will raise eight times as much weight by the crane as he would by his natural strength without it: the power, in this case, being as eight to one.

If the winch be put upon the axis of the next trundle, the power will be as sixteen to one, because it moves sixteen times as fast as the weight moves.

If the winch be put upon the axis of the smallest trundle, and turned round, the power will be as thirty-two to one.

But if the weight should be too great, even for this power to raise, the power may be doubled by drawing up the weight by one of the parts of a double rope, going under a pulley in the moveable block, which is hooked to the weight below the arm of the gib; and then the power will be as sixty-four to one. That is, a man could then

raise sixty-four times as much weight by the crane as he could raise by his natural strength without it; because, for every inch that the weight rises, the working power will move through sixty-four inches.

By hanging a block with two pullies to the arm of the gib, and having two pullies in the moveable block that rises with the weight, the rope being doubled over and under these pullies, the power of the crane will be as 128 to one. And so, by increasing the number of pullies, the power may be increased as much as you please: always remembering, that the larger the pullies are, the less is their friction.

While the weight is drawing up, the ratch-teeth of a wheel slip round below a catch or click that falls successively into them, and so hinders the crane from turning backward, and detains the weight in any part of its ascent, if the man who works at the winch should accidentally happen to quit his hold, or choose to rest himself before the weight be quite drawn up.

In order to let down the weight, a man pulls down one end of a lever of the second kind, which lifts the catch of the ratchet-wheel, and gives the weight liberty to descend. But, if the descent be too quick, he pulls the lever a little farther down, so as to make it rub against the outer edge of a round wheel; by which means he lets down the weight as slowly as he pleases: and, by pulling a little harder, he may stop the weight, if needful, in any part of its descent. If he accidentally quits hold of the lever, the catch immediately falls, and stops both the weight and the whole machine.

PLATE I, Sup. This crane is represented in Plate I, where *A* is the great wheel, and *B* its axle on which the

rope *C* winds. This rope goes over a pulley *D* in the end of the arm of the gib *E*, and draws up the weight *F*, as the winch *G* is turned round. *H* is the largest trundle, *I* the next, and *K* is the axis of the smallest trundle, which is supposed to be hid from view by the upright supporter *L*. A trundle *M* is turned by the great wheel, and on the axis of this trundle is fixed the ratchet-wheel *N*, into the teeth of which the catch *O* falls. *P* is the lever, from which goes a rope *QQ*, over a pulley *R* to the catch; one end of the rope being fixed to the lever, and the other end to the catch. *S* is an elastic bar of wood, one end of which is screwed to the floor: and, from the other end goes a rope (out of sight in the figure) to the further end of the lever, beyond the pin or axis on which it turns in the upright supporter *T*. The use of this bar is to keep up the lever from rubbing against the edge of the wheel *U*, and to let the catch keep in the teeth of the ratchet-wheel: but a weight hung to the farther end of the lever would do full as well as the elastic bar and rope.

When the lever is pulled down, it lifts the catch out of the ratchet-wheel, by means of the rope *QQ*, and gives the weight *F* liberty to descend: but if the lever *P* be pulled a little farther down than what is sufficient to lift the catch *O* out of the ratchet-wheel *N*, it will rub against the edge of the wheel *U*, and thereby hinder the too quick descent of the weight; and will quite stop the weight if pulled hard. And if the man who pulls the lever, should happen inadvertently to let it go, the elastic bar will suddenly pull it up, and the catch will fall down and stop the machine.

WW are two upright rollers above the axis or upper gudgeon of the gib *E*: their use is to let the rope *C* bend upon them, as the gib is turned to either side, in order to bring the weight over the place where it is intended to be let down.

N. B. The rollers ought to be so placed, that if the rope *C* be stretched close by their utmost sides, the half thickness of the rope may be perpendicularly over the centre of the upper gudgeon of the gib. For then, and in no other position of the rollers, the length of the rope between the pulley in the gib and the axle of the great wheel will be always the same, in all positions of the gib: and the gib will remain in any position to which it is turned.

When either of the trundles is not turned by the winch in working the crane, it may be drawn off from the wheel, after the pin near the axis of the trundle is drawn out, and the thick piece of wood is raised a little behind the outward supporter of the axis of the trundle. But this is not material; for, as the trundle has no friction on its axis but what is occasioned by its weight, it will be turned by the wheel without any sensible resistance in working the crane.

A Pyrometer, that makes the expansion of metals by heat visible to the five-and-forty thousandth part of an inch.

Description of a new pyrometer.

The upper surface of this machine is represented by Fig. 1 of Plate II. Its frame *ABCD* is made of mahogany wood, on which is a circle divided into 360 equal parts; and within that circle is another, divided into eight equal parts.

Plate II, Fig. 1, Sup.

If the short bar *E* be pushed one inch forward (or toward the centre of the circle) the index *e* will be turned 125 times round the circle of 360 parts or degrees. As 125 times 360 is 45,000, it is evident, that if the bar *E* be moved only the 45,000th part of an inch, the index will move one degree of the circle. But as in my pyrometer the circle is nine inches in diameter, the motion of the index is visible to half a degree, which answers to the ninety thousandth part of an inch in the motion or pushing of the short bar *E*.

One end of a long bar of metal *F* is laid into a hollow place in a piece of iron *G*, which is fixed to the frame of the machine; and the other end of this bar is laid against the end of the short bar *E*, over the supporting cross bar *H I*: and, as the end *f* of the long bar is placed close against the end of the short bar, it is plain, that if *F* expands, it will push *E* forward, and turn the index *e*.

The machine stands on four short pillars, high enough from a table, to let a spirit-lamp be put on the table under the bar *F*; and when that is done, the heat of the flame of the lamp expands the bar, and turns the index.

There are bars of different metals, as silver, brass, and iron, all of the same length as the bar *F*, for trying experiments on the different expansions of different metals, by equal degrees of heat applied to them for equal lengths of time; which may be measured by a pendulum, that swings seconds. Thus,

Put on the brass bar *F*, and set the index to the 360th degree: then put the lighted lamp under the bar, and count the number of seconds in which the index goes round the plate, from

Method of using it.

360 to 360 again; and then blow out the lamp, and take away the bar.

This done, put on an iron bar *F* where the brass one was before, and then set the index to the 360th degree again. Light the lamp and put it under the iron bar, and let it remain just as many seconds as it did under the brass one; and then blow it out, and you will see how many degrees the index has moved in the circle; and by that means you will know in what proportion the expansion of iron is to the expansion of brass; which I find to be as 210 is to 360, or as seven is to twelve.—By this method, the relative expansions of different metals may be found.

The bars ought to be exactly of equal size; and to have them so, they should be drawn, like wire, through a hole.

When the lamp is blown out, you will see the index turn backward: which shews that the metal contracts as it cools.

The inside of this pyrometer is constructed as follows.—

Fig. 2. In Fig. 2, *A a* is the short bar which moves between rollers; and, on the side *a* it has fifteen teeth in an inch, which take into the leaves of a pinion *B* (twelve in number) on whose axis is the wheel *C* of 100 teeth, which take into the ten leaves of the pinion *D*, on whose axis is the wheel *E* of 100 teeth, which take into the ten leaves of the pinion *F*, on the top of whose axis is the index above mentioned.

Now, as the wheels *C* and *E* have 100 teeth each; and the pinions *D* and *F* have ten leaves each, it is plain, that if the wheel *C* turns once round, the pinion *F* and the index on its axis will turn 100 times round. But, as the first

pinion *B* has only twelve leaves, and the bar *A a* that turns it has fifteen teeth in an inch, which is twelve and a fourth part more; one inch motion of the bar will cause the last pinion *F* to turn a hundred times round, and a fourth part of a hundred over and above, which is twenty-five. So that if *A a* be pushed one inch, *F* will be turned 125 times round.

A silk thread *b* is tied to the axis of the pinion *D*, and wound several times round it; and the other end of the thread is tied to a piece of slender watch-spring *G*, which is fixed into the stud *H*. So that as the bar *f* expands, and pushes the bar *A a* forward, the thread winds round the axle, and draws out the spring: and as the bar contracts, the spring pulls back the thread, and turns the work the contrary way, which pushes back the short bar *A a* against the long bar *f*. This spring always keeps the teeth of the wheels in contact with the leaves of the pinions, and so prevents any shake in the teeth.

In Fig. 1, the eight divisions of the inner circle are so many thousandth parts of an inch in the expansion or contraction of the bars; which is just one thousandth part of an inch for each division moved over by the index. Fig. 1.

A water-mill, invented by Dr. Barker, that has neither wheel nor trundle.

This machine is represented by Fig. 1 of Plate III, in which *A* is a pipe or channel that brings water to the upright tube *B*. The water runs down the tube, and thence into the horizontal trunk *C*, and runs out through holes at *d* and *e* Barker's water-mill. PLATE III, Fig. 1, Sup.

near the ends of the trunk on the contrary sides thereof.

The upright spindle *D* is fixed in the bottom of the trunk, and screwed to it below by the nut *g;* and is fixed into the trunk by two cross bars at *f:* so that, if the tube *B* and trunk *C* be turned round, the spindle *D* will be turned also.

The top of the spindle goes square into the rynd of the upper mill-stone *H*, as in common mills; and, as the trunk, tube, and spindle, turn round, the mill-stone is turned round thereby. The lower, or quiescent, mill-stone is represented by *I;* and *K* is the floor on which it rests, and wherein is the hole *L* for letting the meal run through, and fall down into a trough, which may be about *M*. The hoop or case that goes round the mill-stone rests on the floor *K*, and supports the hopper, in the common way. The lower end of the spindle turns in a hole in the bridge-tree *G F*, which supports the mill-stone, tube, spindle, and trunk. This tree is moveable on a pin at *h*, and its other end is supported by an iron rod *N* fixed into it, the top of the rod going through the fixed bracket *O*, and having a screw nut *o* upon it, above the bracket. By turning this nut forward or backward, the mill-stone is raised or lowered at pleasure.

While the tube *B* is kept full of water from the pipe *A*, and the water continues to run out from the ends of the trunk; the upper mill-stone *H*, together with the trunk, tube, and spindle, turns round. But, if the holes in the trunk were stopped, no motion would ensue; even though the tube and trunk were full of water. For,

If there were no hole in the trunk, the pressure

of the water would be equal against all parts of its sides within. But, when the water has free egress through the holes, its pressure there is entirely removed: and the pressure against the parts of the sides which are opposite to the holes, turns the machine.[a]

---

[a] See Appendix for farther information on the construction of Dr. Barker's mill.—Ed.

HYDROSTATICS.

A machine for demonstrating that, on equal bottoms, the pressure of fluids is in proportion to their perpendicular heights, without any regard to their quantities.

Hydrostatical Paradox.

THIS is termed *the Hydrostatical Paradox:* and the machine for shewing it is represented in Fig. 2 of Plate III.—In which *A* is a box that holds about a pound of water, *a b c d e* a glass-tube fixed in the top of the box, having a small wire within it; one end of the wire being hooked to the end *F* of the beam of a balance, and the other end of the wire fixed to a moveable bottom, on which the water lies, within the box; the bottom and wire being of equal weight with an empty scale (out of sight in the figure) hanging at the other end of the balance. If this scale be pulled down, the bottom will be drawn up within the box, and that motion will cause the water to rise in the glass-tube.

PLATE III, Fig. 2, Sup.

Put one pound weight into the scale, which will move the bottom a little, and cause the water to appear just in the lower end of the tube at *a;* which shews that the water presses with the force of one pound on the bottom; put another pound into the scale, and the water will rise from *a* to *b* in the tube, just twice as high above the bottom as it was when at *a;* and then, as its pressure on the bottom supports two pound weight in the scale, it is plain that the pressure on the bottom is then equal to two

pounds. Put a third pound weight in the scale, and the water will be raised from *b* to *c* in the tube, three times as high above the bottom as when it began to appear in the tube at *a*; which shews, that the same quantity of water that pressed, but with the force of one pound on the bottom, when raised no higher than *a*, presses with the force of three pounds on the bottom when raised three times as high to *c* in the tube. Put a fourth pound weight into the scale, and it will cause the water to rise in the tube from *c* to *d*, four times as high as when it was all contained in the box, which shews that its pressure then upon the bottom is four times as great as when it lay all within the box. Put a fifth pound weight into the scale, and the water will rise in the tube from *d* to *e*, five times as high as it was above the bottom, before it rose in the tube; which shews that its pressure on the bottom is then equal to five pounds, seeing that it supports so much weight in the scale. And so on, if the tube was still longer; for it would still require an additional pound put into the scale, to raise the water in the tube to an additional height equal to the space *de*; even if the bore of the tube was so small as only to let the wire move freely within it, and leave room for any water to get round the wire.

Hence we infer, that if a long narrow pipe or tube was fixed in the top of a cask full of liquor, and if as much liquor was poured into the tube as would fill it, even though it were so small as not to hold an ounce weight of liquor; the pressure arising from the liquor in the tube would be as great upon the bottom, and be in as much danger of bursting it out, as if the cask was continued up, in its full size,

to the height of the tube, and filled with liquor.

Solution of the paradox.

In order to account for this surprising affair, we must consider that fluids press equally in all manner of directions; and consequently that they press just as strongly upward as they do downward. For, if another tube, as *f*, be put into a hole made into the top of the box, and the box be filled with water; and then, if water be poured in at the top of the tube *a b c d e*, it will rise in the tube *f* to the same height as it does in the other tube: and if you leave off pouring, when the water is at *c*, or any other place in the tube *a b c d e*, you will find it just as high in the tube *f*: and if you pour in water to fill the first tube, the second will be filled also.

Now, it is evident, that the water rises in the tube *f*, from the downward pressure of the water in the tube *a b c d e*, on the surface of the water, contiguous to the inside of the top of the box; and as it will stand at equal heights in both tubes, the upward pressure in the tube *f* is equal to the downward pressure in the other tube. But, if the tube *f* were put in any other part of the top of the box, the rising of the water in it would still be the same: or, if the top was full of holes, and a tube put into each of them, the water would rise as high in each tube as it was poured into the tube *a b c d e*; and then the moveable bottom would have the weight of the water in all the tubes to bear, beside the weight of all the water in the box.

And seeing that the water is pressed upward into each tube, it is evident that, if they be all taken away, excepting the tube *a b c d e*, and the holes in which they stood be stopped up; each part, thus stopped, will be pressed as much up-

ward, as was equal to the weight of water in each tube. So that, the upward pressure against the inside of the top of the box, on every part equal in breadth to the width of the tube *abcde*, will be pressed upward with a force equal to the whole weight of water in the tube. And consequently, the whole upward pressure against the top of the box, arising from the weight or downward pressure of the water in the tube, will be equal to the weight of a column of water of the same height with that in the tube, and of the same thickness as the width of the inside of the box: and this upward pressure against the top will re-act downward against the bottom, and be as great thereon, as would be equal to the weight of a column of water as thick as the moveable bottom is broad, and as high as the water stands in the tube. And thus, the paradox is solved.

The moveable bottom has no friction against the inside of the box, nor can any water get between it and the box. The method of making it so, is as follows.—

Construction of the moveable bottom.

In Fig. 3, *ABCD* represents a section of the box, and *a b c d* is the lid or top thereof, which goes on tight, like the lid of a common paper snuff-box. *E* is the moveable bottom, with a groove around its edge, and it is put into a bladder *f g*, which is tied close around it in the groove by a strong waxed thread; the bladder coming up like a purse within the box, and put over the top of it at *a* and *d* all round, and then the lid pressed on. So that, if water be poured in through the hole *ll* of the lid, it will lie upon the bottom *E*, and be contained in the space *f E g h* within the bladder; and the bottom may be raised by pulling the wire *i*, which is fixed to

Fig. 3.

it at *E*: and by thus pulling the wire, the water will be lifted up in the tube *k*, and as the bottom does not touch the inside of the box, it moves without friction.

Now, suppose the diameter of this round bottom to be three inches (in which case, the area thereof will be nine circular inches), and the diameter of the bore of the tube to be a quarter of an inch; the whole area of the bottom will be 144 times as great as the area of the top of a pin that would fill the tube like a cork.

And hence it is plain, that if the moveable bottom be raised only the 144th part of an inch, the water will thereby be raised a whole inch in the tube; and consequently, that if the bottom be raised one inch, it would raise the water to the top of a tube 144 inches, or twelve feet in height.

N. B. The box must be open below the moveable bottom, to let in the air. Otherwise, the pressure of the atmosphere would be so great upon the moveable bottom, if it be three inches in diameter, as to require 108 pounds in the scale, to balance that pressure, before the bottom could begin to move.

A machine, to be substituted in place of the common hydrostatical bellows.

Substitute for the hydrostatical bellows.

In Fig. 1 of Plate IV, *ABCD* is an oblong square box, in one end of which is a round groove, as at *a*, from top to bottom, for receiving the upright glass tube *I*, which is bent to a right angle at the lower end (as at *i* in Fig. 2), and to that part is tied the neck of a large bladder *K* (Fig. 2), which lies in the bottom of the

PLATE IV, Fig. 1, 2, 3, Sup.

box. Over this bladder is laid the moveable board *L* (Fig. 1 and 3), in which is fixed an upright wire *M*; and leaden weights *NN*, to the amount of sixteen pounds, with holes in their middle, which are put upon the wire, over the board, and press upon it with all their force.

The cross bar *p* is then put on, to secure the tube from falling, and keep it in an upright position: and then the piece *EFG* is to be put on, the part *G* sliding tight into the dove-tailed groove *H*, to keep the weights *NN* horizontal, and the wire *M* upright; there being a round hole *e* in the part *EF* for receiving the wire.

There are four upright pins in the four corners of the box within, each almost an inch long, for the board *L* to rest upon: to keep it from pressing the sides of the bladder below it close together at first.

The whole machine being thus put together, pour water into the tube at top; and the water will run down the tube into the bladder below the board; and after the bladder has been filled up to the board, continue pouring water into the tube, and the upward pressure which it will excite in the bladder, will raise the board with all the weight upon it, even though the bore of the tube should be so small, that less than an ounce of water would fill it.[1]

---

[1] Upon this principle, it has been justly affirmed by some writers on natural philosophy, that a certain quantity of water, however small, may be rendered capable of exerting a force equal to any assignable one, by increasing the height of the column, and diminishing the base on which it presses. Dr. Goldsmith observes, that he has seen a strong hogshead split in this manner. A small, though strong tube of tin, twenty feet high, was inserted in

This machine acts upon the same principle as the one last described, concerning the *Hydrostatical paradox.* For, the upward pressure against every part of the board (which the bladder touches), equal in area to the area of the bore of the tube, will be pressed upward with a force equal to the weight of the water in the tube; and the sum of all these pressures against so many areas of the board, will be sufficient to raise it with all the weights upon it.

In my opinion, nothing can exceed this simple machine, in making the upward pressure of fluids evident to sight.

The cause of reciprocating springs, and of ebbing and flowing wells, explained.[2]

Cause of reciprocating springs.

PLATE V, Fig. 1, Sup.

IN Fig. 1 of Plate V, let *a b c d* be a hill, within which is a large cavern *A A* near the top, filled or fed by rains and melted snow on the top *a*, making their way through chinks and

---

in the bung-hole of the hogshead. Water was then poured into the tube till the hogshead was filled, and the water had reached within a foot of the top of the tin tube. By the pressure of this column of water, the hogshead burst with incredible force, and the water was scattered in every direction. By diminishing the area of the tube one half, or doubling its height, the same quantity of water would have a double force.—ED.

[2] Dr. Atwell of Oxford seems to have been the first person that pointed out the cause of reciprocating springs. The theory of this gentleman, of which the article in the text is an abridgement, was published in Number 424 of the Philosophical Transactions, and was suggested by the phenomena of *Laywell* spring, at *Brixam* in Devonshire.—See Desagulier's Experimental Philosophy, vol. ii, p. 173, and vol. i, of this work, p. 141.—ED.

crannies into the said cavern, from which proceeds a small stream *CC* within the body of the hill, and issues out in a spring at *G* on the side of the hill, which will run constantly while the cavern is fed with water.

From the same cavern *AA*, let there be a small channel *D*, to carry water into the cavern *B*; and from that cavern let there be a bended channel *EeF*, larger than *D*, joining with the former channel *CC*, as at *f* before it comes to the side of the hill; and let the joining at *f* be below the level of the bottom of both these caverns.

As the water rises in the cavern *B*, it will rise as high in the channel *EeF*: and when it rises to the top of that channel at *e*, it will run down the part *eFG*, and make a swell in the spring *G*, which will continue till all the water is drawn off from the cavern *B*, by the natural syphon *EeF* (which carries off the water faster from *B* than the channel *D* brings water to it), and then the swell will stop, and only the small channel *CC* will carry water to the spring *G*, till the cavern *B* is filled to *B* again by the rill *D*; and then the water being at the top *e* of the channel *EeF*, that channel will act again as a syphon, and carry off all the water from *B* to the spring *G*, and so make a swelling flow of water at *G* as before.

Illustrated by a machine.

To illustrate this by a machine (Fig. 2), let *A* be a large wooden box, filled with water; and let a small pipe *CC* (the upper end of which is fixed into the bottom of the box) carry water from the box to *G*, where it will run off constantly, like a small spring. Let another small pipe *D* carry water from the same box to the box or well *B*, from which let a syphon *EeF*

Fig. 2.

proceed, and join with the pipe *CC* at *f*: the bore of the syphon being larger than the bore of the feeding-pipe *D*. As the water from this pipe rises in the well *B*, it will also rise as high in the syphon *E e F*; and when the syphon is full to the top *e*, the water will run over the bend *e*, down the part *e F*, and go off at the mouth *G*; which will make a great stream at *G*: and that stream will continue, till the syphon has carried off all the water from the well *B*; the syphon carrying off the water faster from *B* than the pipe *D* brings water to it: and then the swell at *G* will cease, and only the water from the small pipe *C C* will run off at *G*, till the pipe *D* fills the well *B* again; and then the syphon will run, and make a swell at *G* as before.

And thus, we have an artificial representation of an ebbing and flowing well, and of a reciprocating spring, in a very natural and simple manner.

An account of the principles by which Mr. Blakey proposes to raise water from mines, or from rivers, to supply towns, and gentlemen's seats, by his new-invented fire-engine, for which he has received his majesty's letters patent.

ALTHOUGH I am not at liberty to describe the whole of this simple engine, yet I have the patentee's leave to describe such a one as will shew the principles by which it acts. Blakey's fire engine. Plate IV, Fig. 4, Sup.

In Fig. 4 of Plate IV, let *A* be a large, strong, close, vessel, immersed in water up to the cock *b*, and having a hole in the bottom, with a valve *a* upon it, opening upward within the vessel. A pipe *B C* rises from the bottom of this vessel, and has a cock *c* in it near the top, which is small there, for playing a very high jet *d*. *E* is the little boiler (not so big as a common tea-kettle) which is connected with the vessel *A* by the steam-pipe *F*; and *G* is a funnel, through which a little water must be occasionally poured into the boiler, to yield a proper quantity of steam; and a small quantity of water will do for that purpose, because steam possesses upward of 14,000 times as much space or bulk as the water does from which it proceeds.

The vessel *A* being immersed in water up to the cock *b*, open that cock, and the water will rush in through the bottom of the vessel at *a*, and fill it as high up as the water stands on its outside; and the water, coming into the vessel,

will drive the air out of it (as high as the water rises within it) through the cock *b*. When the water has done rushing into the vessel, shut the cock *b*, and the valve *a* will fall down, and hinder the water from being pushed out that way, by any force that presses on its surface. All the part of the vessel above *b* will be full of common air when the water rises to *b*.

Shut the cock *c*, and open the cocks *d* and *e*; then pour as much water into the boiler *E* (through the funnel *G*) as will about half fill the boiler; and then shut the cock *d*, and leave the cock *e* open.

This done, make a fire under the boiler *E*, and the heat thereof will raise a steam from the water in the boiler; and the steam will make its way thence, through the pipe *F*, into the vessel *A*; and the steam will compress the air (above *b*) with a very great force upon the surface of the water in *A*.

When the top of the vessel *A* feels very hot by the steam under it, open the cock *c* in the pipe *C*; and the air being strongly compressed in *A*, between the steam and the water therein, will drive all the water out of the vessel *A*, up the pipe *BC*, from which it will fly up in a jet to a very great height. In my fountain, which is made in this manner after Mr. Blakey's, three tea-cup-fulls of water in the boiler will afford steam enough to play a jet thirty feet high.

When all the water is out of the vessel *A*, and the compressed air begins to follow the jet, open the cocks *b* and *d* to let the steam out of the boiler *E* and vessel *A*, and shut the cock *e* to prevent any more steam from getting into *A*; and the air will rush into the vessel *A* through the cock *b*, and the water through the valve *a*:

and so the vessel will be filled with water, up to the cock *b* as before. Then shut the cock *b*, and the cocks *c* and *d*, and open the cock *e*; and then the next steam that rises in the boiler will make its way into the vessel *A* again; and the operation will go on, as above.

When all the water in the boiler is evaporated, and gone off into steam, pour a little more into the boiler, through the funnel *G*.

In order to make this engine raise water to any gentleman's house, if the house be on the bank of a river, the pipe *BC* may be continued up to the intended height, in the direction *HI*. Or, if the house be on the side or top of a hill, at a distance from the river, the pipe, through which the water is forced up, may be laid along on the hill, from the river or spring to the house.

The boiler may be fed by a small pipe *K*, from the water that rises in the main pipe *BCHI*: the pipe *K* being of a very small bore, so as to fill the funnel *G* with water in the time that the boiler *E* will require a fresh supply. And then, by turning the cock *d*, the water will fall from the funnel into the boiler. The funnel should hold as much water as will about half fill the boiler.

When either of these methods of raising water, perpendicularly or obliquely, is used, there will be no occasion for having the cock *c* in the main pipe *BCHI*: for such a cock is requisite only when the engine is used as a fountain.

A contrivance may be very easily made, from a lever to the cocks *b*, *d*, and *e*; so that, by pulling the lever, the cocks *b* and *d* may be opened when the cock *e* must be shut; and the cock *e* be opened when *b* and *d* must be shut.

The boiler *E* should be inclosed in a brick Boiler.

wall, at a little distance from it, all around; to give liberty for the flames of the fire under the boiler to ascend round about it. By which means (the wall not covering the funnel *G*) the force of the steam will be prodigiously increased by the heat round the boiler; and the funnel and water in it will be heated from the boiler; so that the boiler will not be chilled by letting cold water into it; and the rising of the steam will be so much the quicker.

Mr. Blakey is the only person who ever thought of making us of air as an intermediate body between steam and water: by which means, the steam is always kept from touching the water, and consequently from being condensed by it. And on this new principle he has obtained a patent: so that no one (vary the engine how he will) can make use of the air between steam and water, without infringing on the patent, and being subject to the penalties of the law.

This engine may be built for a trifling expence, in comparison of the common fire engine now in use. It will seldom need repairs, and will not consume half so much fuel. As it has no pumps with pistons, it is clear of all their friction: and the effect is equal to the whole strength or compressive force of the steam; which the effect of the common fire-engine never is, on account of the great friction of the pistons in their pumps.

Archimedes's screw-engine for raising water.

In Fig. 1 of Plate VI, *ABCD* is a wheel, which is turned round, according to the order of the letters, by the fall of water *EF*, which need not be more than three feet. The axle *G* of the wheel is elevated so as to make an angle of about 44° with the horizon; and on the top of that axle is a wheel *H*, which turns such another wheel *I* of the same number of teeth: the axle *K* of this last wheel being parallel to the axle *G* of the two former wheels. Archimedes's screw-engine. PLATE VI, Fig. 1, Sup.

The axle *G* is cut into a double-threaded screw (as in Fig. 2), exactly resembling the screw on the axis of the fly of a common jack, which must be (what is called) a right-handed screw, like the wood-screws, if the first wheel turns in the direction *ABCD*; but must be a left-handed screw, if the stream turns the wheel the contrary way. And, whichever way the screw on the axle *G* be cut, the screw on the axle *K* must be cut the contrary way; because these axles turn in contrary directions. Fig. 2.

The screws being thus cut, they must be covered close over with boards, like those of a cylindrical cask; and then they will be spiral tubes. Or, they may be made of tubes of stiff leather, and wrapt round the axles in shallow grooves cut therein, as in Fig. 3.

The lower end of the axle *G* turns constantly in the stream that turns the wheel, and the lower ends of the spiral tubes are open into the water; so that, as the wheel and axle are turned round, the water rises in the spiral tubes, and runs out at *L*, through the holes *MN*, as they come about below the axle. These holes (of which there Fig. 3.

may be any number, as four or six) are in a broad close ring on the top of the axle, into which ring the water is delivered from the upper open ends of the screw-tubes, and falls into the open box *N*.

The lower end of the axle *K* turns on a gudgeon, in the water in *N*; and the spiral tubes in that axle take up the water from *N*, and deliver it into such another box under the top of *K*; on which there may be such another wheel as *I*, to turn a third axle by such a wheel upon it. And in this manner, water may be raised to any given height, when there is a stream sufficient for that purpose to act on the broad float-boards of the first wheel.[3]

---

[3] As Mr. Ferguson has not explained the reason why the water rises in the spirals of the screw engine, we hope the reader will understand it from the following remarks. When the screw *B F*, in Figure 3, Plate VI, is in a vertical position, the spiral excavations will be inclined to the horizon, and if a portion of water be introduced at the top *A*, it will descend to *F*, the bottom of the tube. If the screw be in a horizontal position, and the water introduced at *B*, it will fall to *C*, and remain there. But if the screw be turned upon its axis from *B* towards *A*, so that the lowest point *C* of the tube may ascend to *D*, while the point *B* is depressed to *C*, the water will, by its own gravity, move from *C* to *B*, where it will be discharged: So that water introduced into one extremity of the screw engine, in a horizontal position, will be discharged at the other. Now, let the end *B*, of the engine *B F*, be elevated so as to be inclined to the horizon, and the same effect will be produced: the water at *C* will rise towards *B*, till the angle of inclination which the machine makes with the horizon is equal to the angle formed by the spirals with the axis of the engine. At this particular angle the water will have as great a tendency to flow towards *D* as towards *C*, because the surface of the tube between these two points is parallel to the horizon; but it

A quadruple pump-mill for raising water.

Quadruple pump-mill. PLATE VII, Sup.

This engine is represented on Plate VII, in which *ABCD* is a wheel, turned by water according to the order of the letters. On the horizontal axis are four small wheels, toothed almost half round: and the parts of their edges on which there are no teeth are cut down so, as to be even with the bottoms of the teeth where they stand.

The teeth of these four wheels take alternately into the teeth of four racks, which hang by two chains over the pulleys *Q* and *L*; and to the lower ends of these racks there are four iron rods fixed, which go down into the four forcing pumps, *S*, *R*, *M*, and *N*. And, as the wheels turn, the rack and pump-rods are alternately moved up and down.

Thus, suppose the wheel *G* has pulled down

---

at a greater angle, the fluid will descend towards *D*, and flow out at the extremity *F*. The ascension of the water, therefore, in the Archimedean screw engine arises from its tendency to occupy the lowest parts of the spiral, while the rotatory motion withdraws this part of the spiral from the fluid, and causes it to ascend to the top of the tube. By wrapping a right angled triangle round a cylindrical pin, so that the hypothenuse may form a spiral upon its surface, and by attending to the position of the spirals at different angles of inclination, the preceding observations will be easily understood. In practice, the angle of inclination should be about 50°, and the angle which the spirals form with the axis should exceed the angle of the engine's inclination by about 15°. The theory of this engine is treated at great length by *Hennert*, in his *Dissertation sur la vis D'Archimede*, Berlin, 1767; and by *Euler*, in the *Nov. Comment. Petrop.* tom. v. See also Gregory's Mechanics, vol. ii, p. 343.—Ed.

the rack *I*, and drawn up the rack *K* by the chain; as the last tooth of *G* just leaves the uppermost tooth of *I*, the first tooth of *H* is ready to take into the lowermost tooth of the rack *K*, and pull it down as far as the teeth go; and then the rack *I* is pulled upward through the whole space of its teeth, and the wheel *G* is ready to take hold of it, and pull it down again, and so draw up the other. In the same manner, the wheels *E* and *F* work the racks *O* and *P*.[4]

These four wheels are fixed on the axle of the great wheel in such a manner, with respect to the positions of their teeth, that while they continue turning round, there is never one instant of time in which one or other of the pump-rods is not going down, and forcing the water. So that, in this engine, there is no occasion for having a general air-vessel to all the pumps, to procure a constant stream of water flowing from the upper end of the main pipe.

The pistons of these pumps are solid plungers, the same as described in Lecture fifth, volume first. See Plate XI, Fig. 4, *with the description of the figure.*

From each of these pumps, near the lowest end, in the water, there goes off a pipe, with a valve on its farthest end from the pump; and these ends of the pipes all enter one close box, into which they deliver the water: and into this box, the lower end of the main conduit-pipe is

---

[4] For the proper form which must be given to the teeth of the wheels and racks, in order to produce an equable and uniform motion, see Appendix. This method of moving the pistons is preferable to the crank motion employed in the engine which is represented in Plate XII, Vol. i.—Ed.

fixed; so that, as the water is forced or pushed into this box, it is also pushed up the main pipe to the height that it is intended to be raised.

There is an engine of this sort, described in Ramelli's work: but I can truly say, that I never saw it till some time after I had made this model.

The said model is not above twice as big as the figure of it, here described. I turn it by a winch fixed on the gudgeon of the axle behind the water wheel; and when it was newly made, and the pistons had valves in good order, I put tin pipes 15 feet high upon it, when they were joined together, to see what it could do; and I found, that in turning it moderately by the winch, it would raise a hogshead of water in an hour, to the height of 15 feet.

DIALING.

The universal Dialing Cylinder.

Universal dialing cylinder. PLATE VIII, Fig. 1, Sup.

IN Fig. 1, of Plate VIII, *ABCD* represents a cylindrical glass tube, closed at both ends with brass plates, and having a wire or axis *EFG* fixed in the centres of the brass plates at top and bottom. This tube is fixed to a horizontal board *H*, and its axis makes an angle with the board equal to the angle of the earth's axis with the horizon of any given place, for which the cylinder is to serve as a dial. And it must be set with its axis parallel to the axis of the world in that place; the end *E* pointing to the elevated pole. Or, it may be made to move upon a joint; and then it may be elevated for any particular latitude.

There are 24 straight lines, drawn with a diamond, on the outside of the glass, equi-distant from each other, and all of them parallel to the axis. These are the hour-lines; and the hours are set to them as in the figure: the XII next *B* stands for midnight, and the opposite XII, next the board *H*, stands for mid-day or noon.

The axis being elevated to the latitude of the place, and the foot-board set truly level, with the black line along its middle in the plane of the meridian, and the end *N* toward the north; the axis *EFG* will serve as a stile or gnomon, and

cast a shadow on the hour of the day, among the parallel hour-lines when the sun shines on the machine, For, as the sun's apparent diurnal motion is equable in the heavens, the shadow of the axis will move equably in the tube; and will always fall upon *that* hour-line which is opposite to the sun, at any given time.

The brass plate *AD*, at the top, is parallel to the equator, and the axis *EFG* is perpendicular to it. If right lines be drawn from the centre of this plate to the upper ends of the equi-distant parallel lines on the outside of the tube; these right lines will be the hour-lines on the equinoctial dial *AD*, at 15° distance from each other: and the hour letters may be set to them, as in the figure. Then, as the shadow of the axis within the tube comes on the hour-lines of that tube, it will cover the like hour-lines on the equinoctial plate *AD*.

If a thin horizontal plate *ef* be put within the tube, so as its edge may touch the tube all around; and right lines be drawn from the centre of the plate to these points of its edge which are cut by the parallel hour-lines on the tube; these right-lines will be the hour-lines of a horizontal dial, for the latitude to which the tube is elevated. For, as the shadow of the axis comes successively to the hour-lines of the tube, and covers them, it will then cover the like hour-lines on the horizontal plate *ef*, to which the hours may be set, as in the figure.

If a thin vertical plate *g C*, be put within the tube, so as to front the meridian, or 12 o'clock line, thereof, and the edge of this plate touch the tube all around: and then, if right lines be drawn from the centre of the plate to those points of its edge which are cut by the parallel hour-

lines on the tube; these right lines will be the hour-lines of a vertical south dial; and the shadow of the axis will cover them at the same times when it covers those of the tube.

If a thin plate be put within the tube so as to decline, or incline, or recline, by any given number of degrees; and right lines be drawn from its centre to the hour-lines of the tube; these right lines will be the hour-lines of a declining, inclining, or reclining, dial, answering to the like number of degrees, for the latitude to which the tube is elevated.

And thus, by this simple machine, all the principles of dialing are made very plain and evident to the sight. And the axis of the tube (which is parallel to the axis of the world in every latitude to which it is elevated) is the stile or gnomon for all the different kinds of sun-dials.

And, lastly, if the axis of the tube be drawn out, with the plates *AD*, *ef*, and *gC* upon it; and set it up in sun-shine, in the same position as they were in the tube; you will have an equinoctial dial *AD*, a horizontal dial *ef*, and a vertical south dial *gC*; on all which the time of the day will be shewn by the shadow of the axis or gnomon *EFG*.

Let us now suppose that, instead of a glass tube, *ABCD* is a cylinder of wood, on which the 24 parallel hour lines are drawn all around, at equal distances from each other; and that, from the points at top, where these lines end, right lines are drawn toward the centre, on the flat surface *AD*: these right lines will be the hour-lines on an equinoctial dial, for the latitude of the place to which the cylinder is elevated above the horizontal foot or pedestal *H*; and they are equidistant from each other, as in Fig. 2,

which is a full view of the flat surface or top *AD* of the cylinder, seen obliquely in Fig. 1. And the axis of the cylinder (which is a straight wire *EFG* all down its middle) is the stile or gnomon, which is perpendicular to the plane of the equinoctial dial, as the earth's axis is perpendicular to the plane of the equator. Fig. 2.

To make a horizontal dial, by the cylinder, for any latitude to which its axis is elevated; draw out the axis and cut the cylinder quite through, as at *ehfg*, parallel to the horizontal board *H*, and take off the top part *eADfe*; and the section *ehfge* will be of an elliptical form, as in Fig. 3. Then, from the points of this section (on the remaining part *eBCf*), where the parallel lines on the outside of the cylinder meet it, draw right lines to the centre of the section; and they will be the true hour-lines for a horizontal dial, as *abcda* in Fig. 3, which may be included in a circle drawn on that section. Then put the wire into its place again, and it will be a stile for casting a shadow on the time of the day, on that dial. So *E* (Fig. 3) is the stile of the horizontal dial, parallel to the axis of the cylinder. Fig. 3.

To make a vertical south dial by the cylinder, draw out the axis, and cut the cylinder perpendicularly to the horizontal board *H*, as at *giChg*, beginning at the hour-line (*BgeA*) of XII, and making the section at right angles to the line *SHN* on the horizontal board. Then, take off the upper part *gADC*, and the face of the section thereon will be elliptical, as shewn in Fig. 4. From the points in the edge of this section, where the parallel hour-lines on the round surface of the cylinder meet it, draw right lines to the centre of the section; and they will Fig. 4.

be the true hour-lines on a vertical direct south dial, for the latitude to which the cylinder was elevated; and will appear as in Fig. 4, on which the vertical dial may be made of a circular shape, or of a square shape, as represented in the figure; and *F* will be its stile parallel to the axis of the cylinder.

And thus, by cutting the cylinder any way, so as its section may either incline, or decline, or recline, by any given number of degrees; and from those points in the edge of the section, where the outside parallel hour-lines meet it, draw right lines to the centre of the section; and they will be the true hour-lines for the like declining, reclining, or inclining, dial: and the axis of the cylinder will always be the gnomon or stile of the dial; for, whichever way the plane of the dial lies, its stile (or the edge thereof that casts the shadow on the hours of the day) must be parallel to the earth's axis, and point toward the elevated pole of the heaven.

To delineate a sun-dial on paper, which, when pasted round a cylinder of wood, shall shew the time of the day, the sun's place in the ecliptic, and his altitude, at any time of observation. See Plate IX. *Sup.*

PLATE IX, Sup. Draw the right line *a A B*, parallel to the top of the paper; and with any convenient opening of the compasses set one foot in the end of the line at *a*, as a centre, and with the other foot describe the quadrantal arc *A E*, and divide it into 90 equal parts or degrees. Draw the right line *A C*, at right angles to *a A B*, and touching the quadrant *A E* at the point *A*. Then, from the

centre *a*, draw right lines through as many degrees of the quadrant as are equal to the sun's altitude at noon, on the longest day of the year, at the place for which the dial is to serve; which altitude at London is 62 degrees: and continue these right lines till they meet the tangent line *AC*, and from these points of meeting, draw straight lines across the paper, parallel to the first right line *AB*, and they will be the parallels of the sun's altitude, in whole degrees, from sun-rise till sun-set, on all the days of the year. —These parallels of altitude must be drawn out to the right line *BD*, which must be parallel to *AC*, and as far from it as is equal to the intended circumference of the cylinder on which the paper is to be pasted, when the dial is drawn upon it.

Divide the space between the right lines *AC* and *BD* (at top and bottom) into twelve equal parts, for the twelve signs of the ecliptic; and, from mark to mark of these divisions at top and bottom, draw right lines parallel to *AC* and *BD*; and place the characters of the 12 signs in these twelve spaces, at the bottom, as in the figure: beginning with ♑ or Capricorn, and ending with ♓ or Pisces. The spaces including the signs should be divided by parallel lines into halves; and if the breadth will admit of it without confusion, into quarters also.

At the top of the dial, make a scale of the months and days of the year, so as the days may stand over the sun's place for each of them in the signs of the ecliptic. The sun's place, for every day of the year, may be found by any common ephemeris: and here it will be best to make use of an ephemeris for the second year after leap-year; as the nearest means for the sun's

place on the days of the leap-year, and on those of the first, second, and third year after.

Compute the sun's altitude for every hour (in the latitude of your place), when he is in the beginning, middle, and end, of each sign of the ecliptic; his altitude at the end of each sign being the same as at the beginning of the next. And, in the upright parallel lines, at the beginning and middle of each sign, make marks for those computed altitudes among the horizontal parallels of altitude, reckoning them downward, according to the order of the numeral figures set to them at the right hand, answering to the like division of the quadrant at the left; and, through these marks, draw the curve hour-lines, and set the hours to them, as in the figure, reckoning the forenoon hours downward, and the afternoon hours upward. The sun's altitude should also be computed for the half hours; and the quarter-lines may be drawn, very nearly in their proper places, by estimation and accuracy of the eye. Then, cut off the paper at the left hand, on which the quadrant was drawn, close by the right line AC, and all the paper at the right hand close by the right line BD; and cut it also close by the top and bottom horizontal lines; and it will be fit for pasting round the cylinder.

PLATE X, Fig. 1, Sup. This cylinder is represented in miniature by Fig. 1, Plate X. It should be hollow, to hold the stile DE when it is not used. The crooked end of the stile is put into a hole in the top AD of the cylinder; and the top goes on tightish, but must be made to turn round on the cylinder, like the lid of a paper snuff box. The stile must stand straight out, perpendicular to the side of the cylinder, just over the right line AB in

Plate IX, where the parallels of the sun's altitude begin: and the length of the stile, or distance of its point *e* from the cylinder, must be equal to the radius *a A* of the quadrant *A E* in Plate IX. PLATE IX, Sup.

The method of using this dial is as follow.—

Place the horizontal foot *B C* of the cylinder on a level table where the sun shines, and turn the top *A D* till the stile stands just over the day of the then present month. Then turn the cylinder about on the table, till the shadow of the stile falls upon it, parallel to those upright lines, which divide the signs, that is, till the shadow be parallel to a supposed axis in the middle of the cylinder: and then, the point, or lowest, end of the shadow, will fall upon the time of the day, as it is before or after noon, among the curve hour-lines; and will shew the sun's altitude at that time, among the cross parallels of his altitude, which go round the cylinder; and, at the same time, it will shew in what sign of the ecliptic the sun then is, and you may very nearly guess at the degree of the sign, by estimation of the eye. PLATE X, Fig. 1, Sup.

The ninth plate, on which this dial is drawn, may be cut out of the book, and pasted round a cylinder whose length is 6 inches and 6 tenths of an inch below the moveable top; and its diameter 2 inches and 24 hundred parts of an inch.—Or, I suppose the copper-plate prints of it may be had of the booksellers in London. But it will only do for London, and other places of the same latitude.

When a level table cannot be had, the dial

may be hung by the ring *F* at the top; and when it is not used, the wire that serves for a stile may be drawn out, and put up within the cylinder; and the machine carried in the pocket.

To make three Sun-dials upon three different planes, so as they may all shew the time of the day by one gnomon.

PLATE X, Fig. 2, Sup. On the flat board *A B C*, describe a horizontal dial, according to any of the rules laid down in the Lecture on Dialing; and to it fix its gnomon *F G H*, the edge of the shadow from the side *F G* being that which shews the time of the day.

To this horizontal or flat board, join the upright board *E D C*, touching the edge *G H* of the gnomon. Then, making the top of the gnomon at *G* the centre of the vertical south dial, describe a south dial on the board *E D C*.

Lastly, on a circular plate *I K* describe an equinoctial dial, all the hours of which dial are equidistant from each other; and making a slit *c d* in that dial, from its edge to its centre, in the XII o'clock line, put the said dial perpendicularly on the gnomon *F G*, as far as the slit will admit of; and the triple dial will be finished; the same gnomon serving all the three, and shewing the same time of the day on each of them.[1]

---

[1] This dial may be converted into a portable and universal one by a very simple contrivance. Remove the stile *F H G* and the dial *K*, and make *E D C* turn upon *H C* as a hinge, so that it may fold down upon *A B*, and thus go into very small compass when not used. Fix a silk thread at *F*, and having divided the line *G H* continued, into a line of tangents for the radius *F H*, make a small hole

An universal Dial on a plain cross.

This dial is represented by Fig. 1, of Plate XI, and is moveable on a joint *C*, for elevating it to any given latitude, on the quadrant *C* 90, as it stands upon the horizontal board *A*. The arms of the cross stand at right angles to the middle part; and the top of it from *a* to *n*, is of equal length with either of the arms *n e* or *m k*. Universal dial. PLATE XI, Fig. 1, Sup.

Having set the middle line *t u* to the latitude of your place, on the quadrant, the board *A* level, and the point *N* northward by the needle; the plane of the cross will be parallel to the plane of the equator; and the machine will be rectified.

Then, from III o'clock in the morning, till VI, the upper edge *k l* of the arm *i o* will cast a shadow on the time of the day on the side of the arm *c m*: from VI till IX the lower edge *i* of the arm *i o* will cast a shadow on the hours on the side *o q*. From IX in the morning till XII at noon, the edge *a b* of the top part *a n* will cast a shadow on the hours on the arm *n e f*: from XII to III in the afternoon, the edge *c d* of the top part will cast a shadow on the hours on the

---

hole through the board at every degree of the line of tangents. Extend the silk thread from *F* towards *G*, making it pass through the hole at the degree of the line of tangents answering to the latitude of the place. The thread will then be the gnomon of the horizontal dial *A B C*, which is set due south, by means of a small mariner's compass placed between *F* and *H*, allowance being made for the variation. The vertical south dial *E C* serves only for a place, the tangent of whose latitude is equal to *H G*. This dial is not altogether correct, but is remarkably convenient for carrying in the pocket.—ED.

arm *k l m*: from III to VI in the evening the edge *g h* will cast a shadow on the hours on the part *p s*; and from VI till IX, the shadow of the edge *e f* will shew the time on the top part *a n*.

The breadth of each part *a b*, *e f*, &c. must be so great as never to let the shadow fall quite without the part or arm on which the hours are marked, when the sun is at his greatest declination from the equator.

To determine the breadth of the sides of the arms which contain the hours, so as to be in just proportion to their length, make an angle *A B C* (Fig. 2) of $23\frac{1}{2}°$, which is equal to the sun's greatest declination: and suppose the length of each arm, from the side of the long middle part, and also the length of the top part above the arms, to be equal to *B d*.

Fig. 2.

Then, as the edges of the shadow from each of the arms, will be parallel to *B o*, making an angle of $23\frac{1}{2}°$ with the side *B n* of the arm when the sun's declination is $23\frac{1}{2}°$; it is plain, that if the length of the arm be *B n*, the least breadth that it can have, to keep the edge *B o* of the shadow *B o g d* from going off the side of the arm *n o* before it comes to the end *o n* thereof, must be equal to *o n* or *d B*. But in order to keep the shadow within the quarter divisions of the hours, when it comes near the end of the arm, the breadth thereof should be still greater, so as to be almost doubled, on account of the distance between the tips of the arms.

To place the hours right on the arms, take the following method.—

Fig. 3.

Lay down the cross *a b c d* (Fig. 3) on a sheet of paper; and with a black lead pencil, held

close to it, draw its shape and size on the paper. Then, taking the length *a e* in your compasses, and setting one foot in the corner *a*, with the other foot describe the quadrantal arc *e f*.—Divide this arc into six equal parts, and through the division marks draw right lines *a g*, *a h*, &c. continuing three of them to the arm *c e*, which are all that can fall upon it; and they will meet the arm in these points through which the lines that divide the hours from each other (as in Fig. 1) are to be drawn right across it.

Divide each arm, for the three hours it contains in the same manner; and set the hours to their proper places (on the sides of the arms), as they are marked in Fig. 3. Each of the hour spaces should be divided into four equal parts, for the half hours and quarters, in the quadrant *e f*; and right lines should be drawn through these division marks in the quadrant, to the arms of the cross, in order to determine the places thereon where the sub-divisions of the hours must be marked.

This is a very simple kind of universal dial; it is very easily made, and will have a pretty uncommon appearance in a garden.—I have seen a dial of this sort, but never saw one of the kind that follows.

An universal Dial, shewing the hours of the day by a terrestrial globe, and by the shadows of several gnomons at the same time: together with all the places of the earth which are then enlightened by the sun; and those to which the sun is then rising, or on the meridian, or setting.

Universal dial by a terrestrial globe and several gnomons. PLATE XII, Sup.

This dial (See Plate XII.) is made of a thick square piece of wood, or hollow metal. The sides are cut into semicircular hollows, in which the hours are placed; the stile of each hollow coming out from the bottom thereof, as far as the ends of the hollows project. The corners are cut out into angles, in the insides of which, the hours are also marked; and the edge of the end of each side of the angle serves as a stile for casting a shadow on the hours marked on the other side.

In the middle of the uppermost side or plane, there is an equinoctial dial: in the centre whereof an upright wire is fixed, for casting a shadow on the hours of that dial, and supporting a small terrestrial globe on its top.

The whole dial stands on a pillar, in the middle of a round horizontal board, in which there is a compass and magnetic needle, for placing the *meridian* stile toward the south. The pillar has a joint with a quadrant upon it, divided into 90 degrees (supposed to be hid from sight under the dial in the figure), for setting it to the latitude of any given place, the same way as already described in the dial on the cross.

The equator of the globe is divided into 24 equal parts, and the hours are laid down upon

it at these parts. The time of the day may be known by these hours, when the sun shines upon the globe.

To rectify and use this dial, set it on a level table, or sole of a window, where the sun shines, placing the meridian stile due south, by means of the needle; which will be, when the needle points as far from the north fleur-de-lis toward the west, as it declines westward, at your place.[a] Then bend the pillar in the joint, till the black line on the pillar comes to the latitude of your place in the quadrant.

The machine being thus rectified, the plane of its dial-part will be parallel to the equator, the wire or axis that supports the globe will be parallel to the earth's axis, and the north pole of the globe will point toward the north pole of the heaven.

The same hour will then be shewn in several of the hollows, by the ends of the shadows of their respective stiles. The axis of the globe will cast a shadow on the same hour of the day, in the equinoctial dial, in the centre of which it is placed, from the 20th of March to the 22d of September; and, if the meridian of your place on the globe be set even with the meridian stile, all the parts of the globe that the sun shines upon, will answer to those places of the real earth which are then enlightened by the sun. The places where the shade is just coming upon the globe, answer all to those places of the earth to which the sun is then setting; as the places

[a] As the declination of the needle is very uncertain, and varies even at the same place, the dial should be rectified by means of a meridian line, drawn upon the side of the window.—Ed.

where it is going off, and the light coming on, answer to all those places of the earth where the sun is then rising. And, lastly, if the hour of VI be marked on the equator in the meridian of your place (as it is marked on the meridian of London in the figure), the division of the light and shade on the globe will shew the time of the day.

The northern stile of the dial (opposite to the southern or meridian one) is hid from sight in the figure, by the axis of the globe. The hours in the hollow to which that stile belongs, are also supposed to be hid by the oblique view of the figure; but they are the same as the hours in the front hollow. Those also in the right and left hand semicircular hollows are mostly hid from sight; and so also are all those on the sides next the eye of the four acute angles.

The construction of this dial is as follows. See Plate XIII.

PLATE XIII, Sup.

On a thick square piece of wood, or metal, draw the lines *a c* and *b d*, as far from each other as you intend for the thickness of the stile *a b c d*, and in the same manner, draw the like thickness of the other three stiles, *e f g h*, *i k l m*, and *n o p q*, all standing outright as from the centre.

With any convenient opening of the compasses, as *a A* (so as to leave proper strength of stuff when *K I* is equal to *a A*) set one foot in *a*, as a centre, and with the other foot describe the quadrantal arc *A c*. Then, without altering the compasses, set one foot in *b* as a centre, and with the other foot describe the quadrant *d B*. All the other quadrants in the figure must be described in the same manner, and with the same opening of the compasses, on their centres *e*, *f*; *i*, *k*; and *n*, *o*: and each

quadrant divided into six equal parts, for so many hours, as in the figure; each of which parts must be subdivided into four, for the half hours and quarters.

At equal distances from each corner, draw the right lines *Ip* and *Kp*, *Lq* and *Mq*, *Nr*, and *Or*, *Ps*, and *Qs*; to form the four angular hollows *lpK*, *LqM*, *NrO*, and *PsQ*: making the distances between the tips of the hollows, as *IK*, *LM*, *NO*, and *PQ*, each equal to the radius of the quadrants; and leaving sufficient room within the angular points, *p*, *q*, *r*, and *s*, for the equinoctial circle in the middle.

To divide the insides of these angles properly for the hour-spaces thereon, take the following method.

Set one foot of the compasses in the point *I*, as a centre; and open the other to *K*, and with that opening describe the arc *Kt*: then, without altering the compasses, set one foot in *K*, and with the other foot describe the arc *It*. Divide each of these arcs, from *I* and *K* to their intersection at *t*, into four equal parts; and from their centres *I* and *K*, through the points of division, draw the right lines *I* 3, *I* 4, *I* 5, *I* 6, *I* 7; and *K* 2, *K* 1, *K* 12, *K* 11; and they will meet the sides *Kp* and *Ip* of the angle *IpK* where the hours thereon must be placed. And these hour-spaces in the arcs must be subdivided into four equal parts, for the half hours and quarters. Do the like for the other three angles, and draw the dotted lines, and set the hours in the insides where those lines meet them, as in the figure: and the like hour-lines will be parallel to each other in all the quadrants and in the angles.

Mark points for all these hours, on the upper

side, and cut out all the angular hollows, and the quadrantal ones, quite through the places where their four gnomons must stand; and lay down the hours on their insides, as in Plate XII, and then set in their four gnomons, which must be as broad as the dial is thick; and this breadth and thickness must be large enough to keep the shadows of the gnomons from ever falling quite out at the sides of the hollows, even when the sun's declination is at the greatest.

Lastly, draw the equinoctial dial in the middle, all the hours of which are equidistant from each other; and the dial will be finished.

As the sun goes round, the broad end of the shadow of the stile *a b c d* will shew the hours in the quadrant *A c*, from sun-rise till VI in the morning; the shadow from the end *M* will shew the hours on the side *L q* from V to IX in the morning; the shadow of the stile *e f g h* in the quadrant *D g* (in the long days) will shew the hours from sun-rise till VI in the morning; and the shadow of the end *N* will shew the morning hours, on the side *O r*, from III to VII.

Just as the shadow of the northern stile *a b c d* goes off the quadrant *A c*, the shadow of the southern stile *i k l m* begins to fall within the quadrant *F l*, at VI in the morning; and shews the time, in that quadrant, from VI till XII at noon; and from noon till VI in the evening in the quadrant *m E*. And the shadow of the end *O* shews the time from XI in the forenoon till III in the afternoon, on the side *r N*; as the shadow of the end *P* shews the time from IX in the morning till I o'clock in the afternoon, on the sides *Q s*.

At noon, when the shadow of the eastern stile *e f g h* goes off the quadrant *h C* (in which it

shewed the time from six in the morning till noon, as it did in the quadrant *g D* from sun-rise till VI in the morning (the shadow of the western stile *n o p q* begins to enter the quadrant *H p*; and shews the hours thereon from XII at noon till VI in the evening; and after *that* till sun-set, in the quadrant *q G*; and the end *Q* casts a shadow on the side *P s* from V in the evening till IX at night, if the sun be not set before that time.

The shadow of the end *I* shews the time on the side *K p* from III till VII in the afternoon; and the shadow of the stile *a b c d* shews the time from VI in the evening till the sun sets.

The shadow of the upright central wire, that supports the globe at top, shews the time of the day, in the middle or equinoctial dial, all the summer half year, when the sun is on the north side of the equator.

In this Supplement to my book of Lectures, all the machines that I have added to my apparatus, since that book was printed, are described, excepting two; one of which is a model of a mill for sawing timber, and the other is a model of the great engine at London bridge, for raising water. And my reasons for leaving them out are as follows.

First, I found it impossible to make such a drawing of the saw-mill as could be understood; because in whatever view it be taken, a great many parts of it hid others from sight. And, in order to shew it in my Lectures, I am obliged to turn it into all manner of positions.[3]

---

[3] For the plan and elevation of a Saw-mill, see Gray's Experienced Mill-wright, lately published, p. 68. For the method

Secondly, because any person who looks on Fig. 1 of Plate XII in the book, and reads the account of it in the fifth Lecture therein, will be able to form a very good idea of the London-bridge engine, which has only two wheels and two trundles more than there are in Mr. Aldersea's engine, from which the said figure was taken.

---

method of constructing one, see Wolfii Opera Mathematica, tom. i, p. 694, and Boecklerus's Theatrum Machinarum. An excellent saw-mill was invented by Mr. James Stanfield, in the year 1765, for which he received a reward of one hundred pounds from the society for the encouragement of arts. The original mill which Mr. Stanfield constructed, was worked for five successive years, in consequence of successive premiums offered and paid by the society, amounting, in all, to two hundred and twenty pounds. A description of this machine, illustrated by five folio plates, will be found in *Bailey's Designs of Machines*, &c. *approved and adopted by the society for the encouragement of arts*, vol. i, p. 137.—Ed.

APPENDIX

TO

FERGUSON'S LECTURES

ON

MECHANICS, &c.

BY THE EDITOR.

APPENDIX

TO

FERGUSON'S LECTURES

ON

MECHANICS, &c.

MECHANICS.

ON THE CONSTRUCTION OF UNDERSHOT WATER WHEELS FOR TURNING MACHINERY.

ALTHOUGH no country has been more distinguished than this, by its discoveries and improvements in the mathematical sciences, yet nowhere have these improvements less effectually contributed to the advancement of the mechanical arts. The discoveries of our philosophers, particularly in the construction of machinery, have been locked up in the recesses of algebraical formulæ; and one would have imagined, that they deemed it beneath their dignity to level their speculations to the capacity of common artists. On this account, the mill-wrights of this country are still guided by their own prejudices; and, if they are furnished with some useful hints and maxims by the few practical

treaties which are to be met with, they are left in the dark to be directed by their own judgment, in the most important parts of the construction. In the preceding lectures, Mr. Ferguson has given some useful directions for the construction of corn mills; but as these are too limited to be of extensive utility, we shall endeavour to supply the defect, by treating this important subject at considerable length. Let us begin, then, by shewing the method of constructing the mill course, and delivering the water on the wheel.

On the construction of the Mill Course.

On the mill course. As it is of the highest importance to have the height of the fall as great as possible, the bottom of the canal, or dam, which conducts the water from the river, should have a very small declivity; for the height of the water-fall will diminish in proportion as the declivity of the canal is increased. On this account, it will be sufficient to make *A B* (Fig. 1) slope about one inch in 200 yards, taking care to make the declivity about half an inch for the first 48 yards, in order that the water may have a velocity sufficient to prevent it from flowing back into the river. The inclination of the fall, represented by the angle *G C R*, should be 25° 50′; or *C R*, the radius, should be to *G R* the tangent of this angle, as 100 to 48, or as 25 to 12; and since the surface of the water *S b* is bent from *a b* into *a c*, before it is precipitated down the fall, it will be necessary to incurvate the upper part *B C D* of the course into *B D*, that the water at the bottom may move parallel to the water at

PLATE I, *App.*

the top of the stream. For this purpose, take the points *B*, *D*, about 12 inches distant from *C*, and raise the perpendiculars *B E*, *D E*: the point of intersection *E* will be the centre from which the arch *B D* is to be described; the radius being about $10\frac{1}{8}$ inches. Now, in order that the water may act more advantageously upon the float-boards of the wheel *W W*, it must assume a horizontal direction *H K*, with the same velocity which it would have acquired when it came to the point *G*: But, in falling from *C* to *G*, the water will dash upon the horizontal part *H G*, and thus lose a great part of its velocity; it will be proper, therefore, to make it move along *F H* an arch of a circle to which *D F* and *K H* are tangents in the points *F* and *H*. For this purpose make *G F* and *G H* each equal to three feet, and raise the perpendiculars *H I*, *F I*, which will intersect one another in the point *I* distant about 4 feet 9 inches and 4-10^{ths} from the points *F*, and *H*, and the centre of the arch *F H* will be determined. The distance *H K*, through which the water runs before it acts upon the wheel, should not be less than two or three feet, in order that the different portions of the fluid may have obtained a horizontal direction: and if *H K* be much larger, the velocity of the stream would be diminished by its friction on the bottom of the course. That no water may escape between the bottom of the course *K H* and the extremities of the float-boards, *K L* should be about 3 inches, and the extremity *o* of the float-board *n o* should be beneath the line *H K X*, sufficient room being left between *o* and *M* for the play of the wheel, or *K L M* may be formed into the arch of a circle *K M* concentric with the wheel. The line *L M V*,

called by *M. Fabre*, the *course of impulsion* (*le coursier d'impulsion*) should be prolonged, so as to support the water as long as it can act upon the float-boards, and should be about 9 inches distant from *O P*, a horizontal line passing through *O* the lowest point of the fall; for if *O L* were much less than 9 inches, the water having spent the greater part of its force in impelling the float-boards, would accumulate below the wheel and retard its motion. For the same reason, another *course*, which is called by *M. Fabre*, the *course of discharge* (*le coursier de decharge*) should be connected with *L M V*, by the curve *V N*, to preserve the remaining velocity of the water, which would otherwise be destroyed by falling perpendicularly from *V* to *N*. The course of discharge is represented by *V Z*, sloping from the point *O*. It should be about 16 yards long, having an inch of declivity in every two yards. The canal which reconducts the water from the course of discharge to the river, should slope about 4 inches in the first 200 yards, 3 inches in the second 200 yards, decreasing gradually till it terminates in the river. But if the river to which the water is conveyed, should, when swoln by the rains, force the water back upon the wheel, the canal must have a greater declivity, in order to prevent this from taking place. Hence it will be evident, that very accurate levelling is necessary for the proper formation of the mill course.

In order to find the breadth of the course of discharge, multiply the quantity of water expended in a second,[1] measured in cubic feet, by

---

[1] The quantity of water expended in a second may be found pretty accurately by measuring the depth of the water

756, for a first number. Multiply the square root of dK (dK being found by subtracting OK or PR, each equal to a foot, from dO or bR, the height of the fall) by OL, or $\frac{1}{4}$ of a foot, and also by 1000, and the product will be a second number. Divide the first number by the second, and the quotient will be nearly the least breadth of the course of discharge. If the breadth of the course, thus found, should be too great or too small, the point L has been placed too far from O or too near it. Increase, therefore, or diminish OL; and having subtracted from dO or bP, the quantity by which OK is greater or less than a foot, repeat the operation with this new value of dK, and a more convenient answer will be found. The preceding rule will give too large a breadth to the course, when the expence of water is great, and the height of the fall inconsiderable. But the course of discharge ought always to have a very considerable breadth, and which should be greater than that of the course of impulsion, that the water having room to spread, may have less depth; and that a greater height may be procured to the fall, by making OL, and consequently OK, as small as possible; for the breadth of the course is inversely as OL, that is, it increases as OL diminishes, and diminishes as it increases. The reader may

---

ter at a, (AB, the bottom of the canal, being nearly horizontal, and its sides perpendicular), and the breadth of the canal at the same place. Take the cube of the depth of the water in feet, and extract the square root of it. Multiply this root by the breadth of the canal, and also by 507. Divide the product by 100, and the quotient will be the expence of water in a second, measured in cubic feet. This rule is founded on the formula, $x=5.07, b \times d^{\frac{3}{2}}$; where x is the quantity of water expended in a second, b the breadth of the canal, and d its depth.

suppose that this rule still leaves us to guess at the breadth of the course of discharge; but, from the purposes for which it is used, it is easy to know when it is excessively large or small; and it is only when this is the case, that we have any occasion to seek for another breadth, by taking a new value of *O L*.

The section of the fluid at *K* should be rectangular, the breadth of the stream having a determinate relation to its depth. If there is very much water, the breadth should be triple the depth; if there is a moderate quantity, the breadth should be double the depth; and, if there is very little water, the breadth and depth should be equal. That this relation may be preserved, the course at the point *K* must have a certain breadth, which may be thus found:— Divide the square-root of *d K* (found as before) by the quantity of water expended in a second, and extract the square-root of the quotient. Multiply this root by .623, if the breadth is to be triple the depth; by .515, if it is to be double; and by .364, if they are to be equal, and the product will be the breadth of the course at *K*. The depth of the water at *K* is therefore known, being either one third, or one half of the breadth of the course, or equal to it, according to the quantity of water furnished by the stream.

PLATE I, *App.* In Fig. 1, *b P* is called the *absolute fall*, which is found by levelling. Draw the horizontal lines *b d*, *P O*; *d O* will thus be equal to *b P*, and will likewise be the absolute fall. The *relative fall* is the distance of the point *d* from the surface of the water at *K*, when the depth of the water is considerably less than *d K*, but is reckoned from the middle of the water at *K*, when *d K* is

very small.[2] The relative fall, therefore, may be determined by subtracting OK, which is generally a foot, from the absolute fall dO, and by subtracting also either the whole, or one half of the natural depth of the water at K, according as dK is great or small in proportion to this depth.

Breadth of the course at the top of the fall.

The next thing to be determined, is the breadth of the course at the top of the fall B, and the breadth of the canal at the same place. To find this; multiply the quantity of water expended in a second by 100, for a first number; take such a quantity as you would wish, for the depth of the water, and, having cubed it, extract its square-root, and multiply this root by 507, for a second number; divide the first number by the second, and the quotient will be the breadth required. The breadth, thus found, may be too great or too small in relation to the depth. If this be the case, take one half of the breadth, thus found, and add to it the number taken for the depth of the water; the sum will be the true depth, with which the operation is to be repeated, and the new result will be better proportioned than the first.

Quantity of water furnished in a second.

The mill-course being thus constructed, we may now find more exactly the quantity of water furnished in a second. For this purpose, subtract one half the depth of the water at K from dK, and having multiplied the remainder

[2] The depth of the water, here alluded to, is its natural depth, or that which it would have if it did not meet the float-boards. The effective depth is generally two and a half times the natural depth, and is occasioned by the impulse of the water on the float-boards, which forces it to swell, and increases its action upon the wheel.

by .5719, extract the square root of the product. Multiply this root by the breadth of the course at *K* multiplied into the depth of the water there,[3] and the result will be the true expence of the source in cubic feet.

In order to know whether the water will have sufficient force to move the least millstone which should be employed, namely, a millstone weighing, along with its axis and trundle, 1550 pounds avoirdupois, take the relative fall increased by one half the natural depth of the water at *K*, viz. *dK*, and multiply it by the expence of the source in cubic feet; if the product is 32.95, or above it, the machine will move without interruption. If the product be less than this number, the weight of the millstone ought to be less than 1550 pounds, and the meal will not be ground sufficiently fine; for the resistance of the grain will bear up the millstone, and allow the meal to escape before it is completely ground.

Fig. 1.

As it is of great consequence that none of the water should escape, either below the float-boards, or at their sides, without contributing to turn the wheel, the course of impulsion, *KV*, should be wider than the course at *K*, as represented in Fig. 2, where *CD*, the course of impulsion, corresponds with *LV* in Fig. 1, *AB* corresponds with *HK*, and *BC* with *KL*. The breadth of the float-boards, therefore, should be wider than *m n*, and their extremities should reach a little below *B*, like *n o* in Fig. 1. When this precaution is taken, no water can escape, without exerting its force upon the float-boards.

PLATE I, *App.* Fig. 1 & 2.

---

[3] That is, by the area of the rectangular section of the stream at *K*.

On the size of the water wheel, and on the number, magnitude, and position, of its float-boards.

The diameter of the wheel should be as great as possible, unless some particular circumstances in the construction prevent it; but ought never to be less than seven times the natural depth of the stream at *K*, the bottom of the course.[4] It has been much disputed among philosophers, whether the wheel should be furnished with a small or a great number of float-boards. M. Pitot has shewn, that when the float-boards have different degrees of obliquity, the force of impulsion upon the different surfaces will be reciprocally as their breadth: thus, in Fig. 3, the force upon *h e* will be to the force upon *DO* as *DO* to *h e*.[5] He therefore concludes, that the distance between the float-boards should be equal to one half of the arch plunged in the stream, or that, when one is at the bottom of the wheel, and perpendicular to the current, as *DE*, the preceding float-board *BC* should be leaving the stream, and the succeeding one *FG* just entering into it.[6] For, when the three float-boards *FG*, *DE*, *BC*, have the same position as in the figure, the whole force of the current *NM* will act upon *DE*, having the most advantageous position for receiving it:

Size of the water wheel.

PLATE I.

Number of float-boards according to Pitot.

[4] The diameter here meant is double the *mean radius*, or the distance between the centre of the wheel and the middle of the natural stream, which impels it, or what is called the centre of impulsion. By adding or subtracting the half of the stream's natural depth, to or from the mean radius, we have the *exterior* and *interior* radius of the wheel.

[5] See Traite d'Hydrodynamique, § 771.

[6] Mem. de l'Acad. Paris. 1729, 8vo, p. 359.

whereas, if another float-board *d e* were inserted between *FG* and *DE*, the part *i g* would cover *DO*, and, by thus substituting an oblique for a perpendicular surface, the effect would be diminished in the proportion of *DO* to *i g*. Upon this principle it is evident, that the depth of the float-board *DE* should always be equal to the versed sine of the arch between any two float-boards, *DE* being the versed sine of *EG*. For the use of those who may wish to follow M. Pitot, though we are of opinion that he recommends too small a number of floats, we have calculated the following table upon the above principles. It exhibits the proper diameter of water wheels, the number of float-boards they should contain, and the size of the float-boards, when any two of these quantities are given. According to M. Pitot, the proper relation between these is of so great importance, that if a water wheel, 16 feet diameter, with its float-boards three feet deep, should have nine instead of seven, one twelfth of the whole force of impulsion would be lost.[7]

---

[7] Desaguliers has adopted the rule given by Pitot. See his Experimental Philosophy, vol. ii, p. 424.

Table of the number of float-boards in undershot wheels.

Diam^{r} of the wheel in feet.	Depth of the float-boards in feet.						
	1	1.5	2	2.5	3	3.5	4
10	10	8	7	6	5	5	5
11	10	8	7	6	5	5	5
12	11	9	8	7	6	6	5
13	11	9	8	7	6	6	5
14	12	9	8	7	7	6	6
15	12	9	8	7	7	6	6
16	12	10	9	8	7	7	6
17	12	10	9	8	7	7	6
18	13	11	9	8	8	7	6
19	13	11	10	9	8	7	7
20	14	11	10	9	8	7	7
21	14	12	10	9	8	7	7
22	15	12	10	9	8	8	7
23	15	12	10	9	8	8	7
24	15	12	11	10	9	8	8
25	16	13	11	10	9	8	8
26	16	13	11	10	9	8	8
27	16	13	11	10	9	8	8
28	17	13	12	10	9	9	8
29	17	14	12	11	10	9	8
30	17	14	12	11	10	9	9
32	18	14	12	11	10	9	9

In order to find from the preceding table the number of float-boards for a wheel 20 feet in diameter, (the diameter of the wheel being reckoned from the extremity of the float-boards), their depth being two feet;—enter the left hand column with the number 20, and the top of the table with the number 2, and in a line with these numbers will be found 10, the number of float-boards which such a wheel would require.

As the numbers representing the depths of the float-boards, and the diameter of the wheel, increase more rapidly than the numbers in the other columns, the preceding table will not shew us with accuracy the diameter of the wheel when the number and depth of the float-boards are given; ten float-boards, for example, two feet deep, answering to a wheel either 19, 20, 21, 22, or 23 feet diameter. This defect, however, may be supplied by the following method.—Divide 360 degrees by the number of float-boards, and the quotient will be the arch between each. Find the natural versed sine of this arch, and say, as 1000 is to this versed sine, so is the wheel's radius to the depth of the float-boards; and to find the diameter of the wheel, say, as the above versed sine is to 1000, so is the depth of the float-boards to the wheel's radius.

The rule of Pitot inaccurate.

We have already said, that the number of floatboards found by the preceding table is too small. Let us attend to this point, as it is of considerable importance. It is evident from Fig. 3, that when one of the floats, as *DE*, is perpendicular to the stream, it receives the whole impulse of the water in the most advantageous manner; but when it arrives at the position *de*, and the succeeding one *FG* into the position *fg*, so that the angle *eAg* may be bisected by the

PLATE I. Fig. 3.

perpendicular *AE*, they will have the most disadvantageous situation; for a great part of the water will escape below the extremities *g* and *e*, of the float-boards, without having any effect upon the wheel; and the part *i g* of the float-board, which is really impelled, is less than *DE*, and oblique to the current. The wheel, therefore, must move irregularly, sometimes quick, and sometimes slow, according to the position of the floats with respect to the stream; and this inequality will increase with the arch plunged in the water. M. Pitot proceeds upon the supposition, that if another float *f g*, were placed between *FG* and *DE*, it would destroy the force of the water that impels it, and cover the corresponding part *DO* of the preceding float-board. But this is not the case. The water, after acting upon *f g*, still retains a part of its motion, and bending round the extremity *g*, strikes *DE* with its remaining force. Considerable advantage, therefore, must be gained by using more float-boards that M. Pitot recommends.[8]

Number of float-boards according to Bossut.

M. Bossut[9] has shewn, that when the wheel has an uniform velocity, the most advantageous

[8] In Mr. Smeaton's experiments, the water wheel, which was 25 inches in diameter, had 24 floats; and he observes, 'that, when the number was reduced to 12, it caused a 'diminution of the effect, on account of a greater quan-'tity of water escaping between the floats and the floor; 'but a circular sweep being adapted thereto, of such a 'length, that one float entered the course before the pre-'ceding one quitted it, the effect came so near to the form-'er, as not to give hopes of advancing it by increasing 'the number of floats beyond 24 in this particular wheel.' Smeaton's Experimental Enquiry, p. 24; or, Phil. Trans. 1759, v. 51.

[9] Traite d'Hydrodynamique, notes on chap. x; also § 778.

number of floats is determined. Having fixed upon the radius and velocity of the wheel, and on the portion of its circumference that ought to be plunged in the stream, he imagines the wheel to have different numbers of float-boards, and then computes the momentum of the water against all the parts of those that are immersed. The number of float-boards which gives the greatest momentum should be adopted as the most advantageous. When the velocity of the stream was thrice that of the wheel, and when 72 degrees of the circumference were immersed, Bossut found that the number of float-boards should be 36. When a greater arch is plunged in the stream, the velocity continuing the same, the number should be increased, and *vice versa*.

The float-boards should be as numerous as possible.

This rule, however, is too difficult to be of use to the practical mechanic. From what has been said, it is evident, that in order to remove any inequality of motion in the wheel, and prevent the water from escaping beneath the tips of the float-boards, the wheel should be furnished with the greatest number of float-boards possible, without loading it, or weakening the rim on which they are placed.[1] This rule was first given by Dupetit Vandin,[2] and afterwards by M. Fabre,[3] and it is not difficult to see, that if the millwright should err in furnishing the wheel with too many float-boards, the error will be perfectly trifling, and that he would lose much more by erring on the other side. The float-boards should not be rectan-

[1] Brisson (Traite Elementaire de Physique) observes, that there should be 48 floats, instead of 40, as generally used in a wheel 20 feet in diameter.

[2] Mem. des Savans Etrangers, tom. i.

[3] Sur les Machines Hydrauliques, p. 55, N°. 103

gular, like *a b n c* in Fig. 3, but should be bevelled like *a b m c*. For if they were rectangular, the extremity *b n* would interrupt a portion of the water, which would otherwise fall on the corresponding part of the preceding float-board. The angle *a b m* may be found thus.—Subtract from 180° the number of degrees contained in the immersed arch *CEG*, and the half of the remainder will be the angle required. It has been already observed, that the effective depth of the water at *K* (Fig. 1) is generally two and a half times greater than the natural depth. The height *DE*, therefore, of the float-boards should be two and a half times the natural depth of the current at *K*. The breadth of the float-boards should always be a little greater than the breadth of the course at *K*, the method of finding which has been already pointed out. Fig. 3. Fig. 1.

Inclination of the float-boards.

M. Pitot has shewn,[4] that the float-boards should be perpendicular to the rim, or, in other words, a continuation of the radius. This, indeed, is true in theory, but it appears from the most unquestionable experiments, that they should be inclined to the radius. This was discovered by Deparcieux, in 1753, (not in 1759, as Fabre asserts), who shews, that the water will thus heap up on the float-boards, and act, not only by its impulse, but also by its weight.[5] This discovery has been confirmed also by the Abbe Bossut,[6] who found, that when the velocity of the water is about $\frac{100}{27}$ of a foot, or 11 feet per second, the inclination of the float-board to

[4] Mem. Acad. Royale 1729, 8vo, p. 350.
[5] Mem. de l'Acad. 1754, 4to, p. 614, 8vo, p. 944.
[6] Traite d'Hydrodynamique, § 814 and § 817.

the radius should be between 15 and 30 degrees. M. Fabre, however, is of opinion that when the velocity of the stream is 11 feet per second, or above this, the inclination should never be less than 30 degrees; that when this velocity diminishes, the inclination should diminish in proportion; and that when it is four feet, or under, the inclination should be nothing. In order to find the inclination for wheels of different radii, let Fig. 3. AH (Fig. 3) be the radius, bisect PH, the height of the float-board, in i, and having drawn PK perpendicular to PA, set off PK equal to Pi, and join HK; HK will be the position of the float-board inclined to the radius AH by the angle KHP. This construction supposes the greatest value of the angle KHP to be 26° 34′.

On the formation of the spur wheel and trundle.

Size of the spur wheel. The radius of the spur wheel is found by multiplying the mean radius of the water-wheel by that of the lantern, which may be of any size, and also by the number of turns, which the spindle or axis of the lantern performs in a second,[7] and then by the number 2.151. This product being divided by the square-root of the relative fall, the quotient will be the radius required. The number of teeth in the wheel should be to the number of staves in the trundle as their respective radii. In order to find the

Number of teeth in the wheel and trundle.

[7] The method of determining the velocity of the spindle, or the mill-stone, will be afterwards pointed out. The axis of the lantern should, in general, make about 90 turns in a minute.

exact number, take the proper diameter of the teeth and the staves, which ought to be two and a half inches each in common machines, and determine also how much is to be allowed for the play of the teeth, which should be about two and a half tenths of an inch; add these three numbers, and divide by this sum the mean circumference of the spur wheel,[8] the quotient will be nearly the number of teeth in the wheel. Let us call this quotient x, to avoid circumlocution. Multiply x by the mean radius of the trundle, and divide the product by the radius of the spur wheel. If the quotient is a whole number, it will be the exact number of staves in the trundle, and x, if it were an integer, will be the exact number of teeth in the wheel. But should the quotient be a mixed number, diminish the integer, which may still be called x, by the numbers 1, 2, 3, &c. successively, and at every diminution, multiply x, thus diminished, by the radius of the trundle, and divide the product by the radius of the wheel. If any of these operations give a quotient without a remainder, this quotient will be the number of staves in the trundle, and x, diminished by one or more units, will be the number of teeth in the wheel. Thus let the radius of the trundle be one foot, that of the wheel four feet, the thickness of the teeth and the staves two and a half inches, or $\frac{30}{144}$ of a foot, and the space for the play of the teeth two and a half tenths of an inch, or $\frac{3}{144}$; the sum of the three quantities will be $\frac{63}{144}$ or $\frac{7}{16}$ of a foot; and 25 feet, or $\frac{176}{7}$ of a foot, the circumference

[8] The mean radius is reckoned from the centre of the wheel to the centre of the teeth.

of the wheel, divided by $\frac{7}{16}$ will give $\frac{2816}{49}$, or $57\frac{23}{49}$ feet. Multiply the integer x or 57 by 1, the radius of the lantern; but as the product 57 will not divide by 4, the radius of the wheel, let us diminish x, or 57, by unity, and the remainder 56 being multiplied by 1, the radius of the trundle, and divided by four, the radius of the wheel, gives 14 without a remainder, which, therefore, will be the number of staves, while 56, or x diminished by unity, is the number of teeth in the spur-wheel.

Had it been possible to make the number of teeth equal to $57\frac{23}{49}$, $2\frac{1}{2}$ inches would be the proper thickness for the teeth and the staves; but, as the number must be diminished to 56, there will be an interval left, which must be distributed among the teeth and staves, so that a small addition must be made to each. To do this, divide the circumference of the wheel $\frac{176}{7}$ of a foot by the number of teeth 56, and, from the quotient $\frac{450}{1000}$ subtract the interval for the play of the teeth $\frac{3}{144}$ or $\frac{20}{1000}$, the remainder $\frac{430}{1000}$ being halved, will give $\frac{215}{1000}$ of a foot, or 2 inches and 5.8 tenths, for the thickness of every tooth and stave, $\frac{8}{100}$ of an inch being added to each tooth and stave to fill up the interval.

It may sometimes happen, however, that, in diminishing x successively by unity, a quotient will never be found without a remainder. When this is the case, seek out the mixed number which approaches nearest an integer, and take the integer to which it approximates for the number of staves in the lantern. Thus, when the radius of the wheel is $4\frac{1}{13}$ feet, the different quotients obtained, after diminishing x by one, two, three, four, will be $14\frac{226}{1000}$, $13\frac{981}{1000}$, $13\frac{735}{1000}$, $13\frac{490}{1000}$, and $13\frac{245}{1000}$. The nearest of these to

an integer is $13\frac{981}{1000}$, being only $\frac{19}{1000}$ less than 14, which will therefore be the number of staves in the trundle. [9]

In a succeeding article on the teeth of wheels, we have shewn what form must be given them in order to produce an uniformity of action. The following method, however, will be pretty accurate for common works. In Plate IV, Fig. 7, take EB, equal to the radius of the trundle, [1] and describe the acting part BA, and with the same radius describe CD. When the teeth of the wheel are perpendicular to its plane, as in the spur wheels of corn mills, we must bisect CD in n, and drawing mn perpendicular to BD, make the plane $BACD$ move round upon mn as an axis; the figure thus generated like abc, Fig. 8, will be the proper shape for the teeth.

Form of the teeth.

Plate IV, Fig. 7.

Fig. 8.

The pivots, or gudgeons, on which vertical axes move, should be conical; and those which are attached to horizontal arbors, should be cylindrical, and as small and short as possible. A gudgeon two inches in diameter will support a weight of 3239 pounds avoirdupois, though we often meet with gudgeons three or four inches in diameter, when the weight to be supported is considerably less. By attending to this, the friction of the gudgeons will be much diminished, and the machine greatly improved. Particular care, too, should be taken, that the axis of the gudgeons be exactly in a line with the axis of

Size of the gudgeons.

---

[9] See Fabre sur les Machines Hydrauliques, p. 304, § 546.

[1] The staves of the trundle should be as short as possible.

the arbor which they support,[2] otherwise the action or motion of the wheels which they carry will be affected with periodical inequalities.

On the formation, size, and velocity, of the millstone, &c.

On the surfaces of the mill-stones.

In the fourth lecture,[3] Mr. Ferguson has given several useful directions for the formation of the grinding surfaces of the millstones; to which we have only to add, that when the furrows are worn shallow, and consequently new dressed with the chisel, the same quantity of stone must be taken from every part of the grinding surface, that it may have the same convexity or concavity as before. As the upper millstone should always have the same weight when its velocity remains unchanged, it will be necessary to add to it as much weight as it lost in the dressing. This will be most conveniently done by covering its top with a layer of plaster, of the same diameter as the layer of stone taken from its grinding surface, and as much thicker than the layer of stone, as the specific gravity of the stone exceeds the specific gravity of the plaster.[4] That the reader may have some idea of the manner in which the furrows, or channels, are arranged, we have represented in Plate 1, Fig. 4, the grinding surface of the upper millstone, upon

PLATE I, Fig. 4.

---

[2] The diameter of the gudgeon must be proportional to the square-root of the weight which it supports.

[3] Vol. i, p. 85.

[4] The relative weights of the stone and plaster may be determined from the table of specific gravities at the end of vol. i.

the supposition that it moves from east to west, or for what is called a right-handed mill. When the millstone moves in the opposite direction, the position of the furrows must be reversed.

In Fig. 5 we have a section of the millstone spindle and lantern. The under millstone *MPHG*, which never moves, may be of any thickness. Its grinding surface must be of a conical form, the point *b* being about an inch above the horizontal line *PR*, and *Ma* and *Pb* being straight lines. The upper millstone *EFPM*, which is fixed to the spindle *CD* at *C*, and is carried round with it, should be so hollowed that the angle *OMa*, formed by the grinding surfaces, may be of such a size that *On* being taken equal to *nM*, *ns* may be equal to the thickness of a grain of corn.[5] The diameter *ON* of the mill eye *mC* should be between 8 and 14 inches; and the weight of the upper millstone *EP* joined to the weight of the spindle *CD* and the trundle *x* (the sum of which three numbers is called the *equipage* of the turning millstone), should never be less than 1550 pounds avoirdupois, otherwise the resistance of the grain would bear up the millstone, and the meal be ground too coarse. Fig. 5.

In order to find the weight of the equipage;—Divide the third of the radius of the gudgeon by the radius of the water-wheel which it supports, and having taken the quotient from 2.25, Weight of the equipage.

[5] In note 6, p. 93, vol. i, we have said that the corn does not begin to be ground till it has insinuated itself as far as two thirds of the radius, or the centre of gyration; but for reasons which may be seen in *Fabre sur les Machines Hydrauliques*, p. 238, the grinding should commence at the point *n*, equidistant from *O* and *M*.

multiply the remainder by the expence of the source, by the relative fall, and by the number 19911, and you will have a first quantity, which may be regarded as pounds. Multiply the square root of the relative fall by the weight of the arbor of the water wheel, by the radius of its gudgeon, and by the number 1617, and a second quantity will be had, which will also represent pounds. Divide the third part of the radius of the gudgeon by the radius of the water-wheel, and having augmented the quotient by unity, multiply the sum by 1005, and a third quantity will be obtained. Subtract the second quantity from the first, divide the remainder by the third, and the quotient will express the number of pounds in the equipage of the millstone.

The weight of the equipage being thus found, extract its square root, expressed in pounds, and multiply it by .039, and the product will be the radius of the millstone in feet.[6]

Size of the millstones.

In order to find the weight and thickness of the upper millstone, the following rules must be observed.—

1. To find the weight of a quantity of stone equal to the mill eye;—Take any quantity which seems most proper for the weight of the spindle *CD* and the lantern *X*, and subtract this quantity from the weight of the millstone's equipage, for a first quantity. Find the area of the mill eye, and multiply it by the weight of a cubic foot of stone of the same kind as the millstone, (found from the table of specific gravities, vol. i) and a second quantity will be had. Multiply

[6] This rule supposes, that when the diameter of the millstone is 5 feet, the weight of the equipage should be 430.7 avoirdupois pounds.

the area of the millstone by the weight of a cubic foot of the same stone, for a third quantity. Multiply the first quantity by the second, and divide the product by the third, and the quotient will be the weight required.

2. To find the number of cubic feet in the turning millstone, supposing it to have no eye; —From the weight of the spindle and lantern subtract the quantity found by the preceding rule, for the first number. Subtract this first number from the weight of the equipage, and a second number will be obtained. Divide this second quantity by the weight of a cubic foot of stone of the same quality as the millstone, and the quotient will be the number of cubic feet in $EMPF$, mC being supposed to be filled up. Fig. 5.

3. To find the quantities mN and EM, *i. e.* the thickness of the millstone at its centre and circumference;—Divide the solid content of the millstone, as found by the preceding rule, by its area, and you will have a first quantity. Add bR, which is generally about an inch, to twice the diameter of a grain of corn, for a second quantity. Add the first quantity to one third of the second, and the sum will be the thickness of the millstone at the circumference. Subtract the third of the second quantity from the first quantity, and the remainder will be its thickness at the centre.[7]

The size of the mill-stone being thus found, its velocity is next to be determined. M. Fabre observes, that the flour is the best possible when a millstone 5 feet in diameter makes from 48 to 61 revolutions in a second. Mr. Ferguson al- Velocity of the millstone.

[7] These rules are founded upon formulæ, which may be seen in *Fabre sur les Machines Hydrauliques*, pp. 172, 239.

lows 60 turns to a millstone 6 feet in diameter, and Mr. Imison 120 to a millstone $4\frac{1}{2}$ feet in diameter. In mills upon Mr. Imison's construction, the great heat that must be generated by such a rapid motion of the millstone, must render the meal of a very inferior quality: much time, on the contrary, will be lost, when such a slow motion is employed as is recommended by M. Fabre and Mr. Ferguson. In the best corn mills in this country, a millstone 5 feet in diameter revolves, at an average, 90 times in a minute.[5] The number of revolutions in a second, therefore, which must be assigned to millstones of a different size, may be found by dividing 450 by the diameter of the millstone in feet.

Spindle. The spindle $c\,D$, which is commonly 6 feet long, may be made either of iron or wood. When it is of iron, and the weight of the millstone 7558 pounds avoirdupois, it is generally three inches in diameter; and when made of wood, it is 10 or 11 inches in diameter. For millstones of a different weight, the thickness of the spindle may be found by proportioning it to the square root of the millstone's weight, or, which is nearly the same thing, to the weight of the millstone's equipage.

Pivots. The greatest diameter of the pivot D, upon which the millstone rests, should be proportional to the square root of the equipage, a pivot half an inch diameter being able to support an equipage of 5398 pounds. In most machines,

---

[5] Mr. Fenwick of Newcastle, an excellent practical mechanic, observes, that, in the best corn mills in England, mill-stones from $4\frac{1}{2}$ to 5 feet in diameter revolve from 90 to 100 times in a second.

the diameter of the pivots is by far too large, being capable of supporting a much greater weight than they are obliged to bear. The friction is therefore increased, and the performance of the machine diminished.

The bridge-tree *AB* is generally from eight to 10 feet long, and should always be elastic, that it may yield to the oscillatory motion of the mill-stone.[6] When its length is 9 feet, and the weight of the equipage 5182 pounds, it should be 6 inches square; and when the length remains unchanged, and the equipage varies, the thickness of the bridge-tree should be proportional to the square root of the equipage. Fig. 5. Bridge-tree.

On the performance of Undershot Mills.

The performance of any machine may be properly represented by the number of pounds which it will elevate, in a given time, by means of a rope *KL* (Fig. 5), wound upon the spindle *CD*, and passing over the pulley *L*.[7] In order to find the weight which a given machine will raise;—Divide the third part of the radius of the gudgeon of the water-wheel, by the mean radius of the wheel itself, and, having subtracted the quotient from 2.25, multiply the remainder by the expence of water in a second in cubic feet, by the height of the relative fall, and by the number 19911, for a first quantity. Multiply the weight of the arbor of the water-wheel, and Performance of undershot mills.

[6] See *Belidor, Architecture Hydraulique*, 638; or Desaguliers' Exper. Philos. vol. ii, p. 429.

[7] It was in this way that Smeaton measured the performance of his models.

its appendages (viz. the water-wheel itself and the spur wheel), by the radius of the gudgeon in decimals of a foot, by the square root of the relative fall, and the number 1617, and divide the product by the mean radius of the water wheel, and a second quantity will be had. Divide the third part of the gudgeon's radius by the mean radius of the water-wheel, augment the quotient by unity, and multiply the sum by the radius of the spindle *CD* for a third quantity. Subtract the second quantity from the first, and divide the remainder by the third quantity, the quotient will be the number of pounds which the machine will raise. Multiply the diameter of the spindle *CD* by 3.1416, and you will have a quantity equal to the height which *W* will rise by one turn of the spindle; this quantity, therefore, being multiplied by the number of turns which the spindle performs in a minute, will give the height through which the weight *W* will rise in the space of a minute.

According to Mr. Fenwick.

Mr. Fenwick [8] found, by a variety of accurate experiments made upon good corn-mills, whose upper millstone, being from $4\frac{1}{2}$ to 5 feet in diameter, revolved from 90 to 100 times in a minute, that a mill, or any power capable of raising 800 pounds avoirdupois with a velocity of 210 feet per minute, will grind *one* boll of good corn in an hour; and that two, three, four, or five bolls will be ground in an hour, when a weight of 300 pounds is raised with a velocity of 350 506, 677, or 865 feet respectively in a minute.[9]

---

[8] Four Essays on Practical Mechanics, 2d edit. 1802, p. 60.

[9] As the differences of these numbers increase nearly by 16, they may be continued by always augmenting the difference

Or, to arrange the numbers more properly:

Number of bolls ground in an hour..... 1	2	3	4	5	6
Number of feet through which 300lb. is raised in a minute... 210	350	506	677	865	1069

Supposing it, therefore, to be found, by the preceding rules, that a mill would raise 600 pounds through 253 feet in a minute of time, we have 300 : 600 = 253 : 506; that is, the same power that can raise 600 pounds through 253 feet, will raise 300 pounds through 506 feet, consequently such a mill will be able to grind three bolls of corn in an hour.[1]

According to M. Fabre. According to M. Fabre, the quantity of meal ground in an hour may be determined by multiplying 62.4 Paris pounds by the square of the radius of the millstone, and the product will be the number of pounds of meal. But, as this rule is founded upon an erroneous supposition, that the quality of the flour is best when a millstone, 5 feet in diameter, performs 48 revolutions in a minute, we have made the calculation

---

difference between the two last numbers by 16, and adding the difference thus augmented to the last number, for the number required. Thus, by adding 16 to 188, the difference between 677 and 865, we have 204, which being added to 865, gives 1069 for the number of feet, nearly, through which the power must be able to raise a weight of 300 pounds in a minute, in order to grind six bolls of corn in an hour.

[1] The proper result of Mr. Fenwick's experiment was, that a power requisite to raise a weight of 300 pounds avoirdupois, with a velocity of 190 *feet per minute*, would grind one boll of good corn in an hour; but, in order to make the above numbers accurate in practice, he increased the velocity $\frac{1}{10}$, and made it 210 feet per minute.

anew, upon the supposition, that the velocity of a millstone, five feet diameter, should be 90 revolutions in a minute, and have found, that, when mills are constructed upon this principle, the quantity of flour ground in an hour, in pounds avoirdupois, will be equal to the product of the square of the millstone's radius, and the number 125.

According to the editor.

The following important maxims have been deduced from Mr. Smeaton's accurate experiments on undershot mills, and merit the attention of every practical mechanic.

Explanation of Smeaton's maxims.

Maxim 1. That the virtual or effective head of water being the same,[2] the effect will be nearly as the quantity of water expended.—That is, if a mill, driven by a fall of water whose virtual head is 10 feet, and which discharges 30 cubic feet of water in a second, grinds four bolls in an hour; another mill having the same virtual head, but which discharges 60 cubic feet of water, will grind eight bolls of corn in an hour.

Maxim 2. That the expence of water being the same, the effect will be nearly as the height of the virtual or effective head.

---

[2] The *virtual*, or *effective head* of water moving with a certain velocity, is equal to the height from which a heavy body must fall in order to acquire the same velocity. The height of the virtual head, therefore, may be easily determined from the water's velocity, for the heights are as the squares of the velocities, and the velocities, consequently, as the square roots of the heights. Mr. Smeaton observes, that, in the large openings of mills and sluices, where great quantities of water are discharged from moderate heads, the real head of water, and the virtual head, as determined from the velocity, will nearly agree. See his Experiments on Mills, p. 23.

Maxim 3. That the quantity of water expended being the same, the effect is nearly as the square of its velocity.—That is, if a mill, driven by a certain quantity of water, moving with the velocity of four feet per second, grinds three bolls of corn in an hour; another mill, driven by the same quantity of water, moving with the velocity of five feet per second, will grind nearly $4\frac{7}{10}$ bolls of corn in an hour, because $3 : 4\frac{7}{10} = 4^2 : 5^2$ nearly, that is, as 16 to 25, the squares of the respective velocities of the water.

Maxim 4. The aperture being the same, the effect will be nearly as the cube of the velocity of the water.—That is, if a mill driven by water, moving through a certain aperture, with the velocity of four feet per second, grind three bolls of corn in an hour; another mill driven with water, moving through the same aperture with the velocity of five feet per second, will grind $5\frac{1}{10}$ bolls nearly in an hour, for $3 : 5\frac{1}{10} = 4^3 : 5^3$ nearly, that is as 64 to 125, the cubes of the water's respective velocities.

On the method of constructing Mill-wrights' Tables, on new principles.

Construction of a new mill-wrights' table.

Although a mill-wright's table has been constructed by Mr. Ferguson,[5] and afterwards altered a little by Mr. Imison, so far as concerns the velocity of the millstone; yet, as we shall now shew, the principles upon which it is computed are far from being correct. It is evident that the

[5] See vol. i, p. 97.

great wheel must always move with less velocity than the water, even when there is no work to be performed; for a part of the impelling power is necessarily spent in overcoming the inertia of the wheel itself; and if the wheel has little or no velocity, it is equally manifest that it will produce a very small effect. There is consequently a certain proportion between the velocity of the water and the wheel, when the effect is a maximum. Parent and Pitot found this proportion to be as 1 to 3; and Desaguliers,[6] Maclaurin,[7] and Ferguson, have adopted their determination.[8] But Mr. Smeaton has shewn, that instead of the wheel moving with $\frac{1}{3}$ of the velocity of the water, when the effect is a maximum, as Parent imagined, the greatest effect is produced when the velocity of the wheel is between $\frac{1}{3}$ and $\frac{1}{2}$, the maximum being much nearer to $\frac{1}{2}$ than $\frac{1}{3}$. He observes also, that $\frac{1}{2}$ would be the true maximum 'if nothing were lost by the resistance of the air, the 'scattering of the water carried up by the wheel, 'and thrown off by the centrifugal force, &c. 'all which tend to diminish the effect more at 'what would be the maximum if these did not 'take place, than they do when the motion is a 'little slower.'[9] But in making this alteration

Relative velocity of the water and the wheel.

---

[6] Desaguliers' Experimental Philosophy, vol. ii, p. 424, Lect. 12.

[7] Maclaurin's Fluxions, Art. 907, p. 728.

[8] M. Lambert has also adopted the determination of Parent, in his Memoir on Undershot Mills in the *Nouv. Mem. de l'Acad. de Berlin*, 1775, p. 63.

[9] Smeaton on Mills, p. 77. M. Bossut and M. Fabre, along with Smeaton, make the velocity of the wheel $\frac{1}{2}$ of the velocity of the water. See Traite d'Hydrodynamique par Bossut, § 808.9, Fabre, § 66. The great hydraulic

we are warranted not merely by the results of Mr. Smeaton's experiments, but also by deductions of theory. In the investigations from which Parent and Pitot concluded that the velocity of the wheel should be $\frac{1}{3}$ of the velocity of the water in order to produce a maximum effect, they considered the impulse of the stream upon one float-board only, and therefore made the force of impulsion proportional to the square of the difference between the velocities of the stream and the float-board. The action of the current, however, is not confined to one float-board, but is exerted on several at the same time, so that the float-boards which are accurately fitted to the mill-course, abstract from the water its excess of velocity, and the force of impulsion becomes proportional only to the difference between the velocities of the stream and the float-boards. From this circumstance, the Chevalier de Borda has shewn in his *Memoire sur les Roues Hydrauliques*,[1] that in theory the

---

machine at Marly was found to produce a maximum effect when the velocity of the wheel was $\frac{3}{7}$ that of the current.

[1] Memoires de l'Acad. Paris, 1767, 4to, p. 285.—Although the memoir of the Chevalier de Borda was published so early as 1767, yet, in the year 1793, there appeared in the Transactions of the American Philosophical Society, vol. iii, p. 144, a paper, by Mr. Waring, containing the same observations on the maximum effect of undershot wheels. We would willingly believe that Mr. Waring was guided solely by his own investigations; and that the similarity between his memoir and that of Borda's, was owing to a casual coincidence of sentiment. Unfortunately, however, in the same volume of the American Transactions, Mr. Waring describes an improvement, by a Mr. Rumsey, on Barker's mill, which was published in 1775, by M. Mathon de la Cour in Rozier's Journal de

velocity of the wheel is $\frac{1}{2}$ that of the current, and that in practice it is never more than $\frac{1}{3}$ of the stream's velocity, when the effect is a maximum.

The constant number, too, which is used by Mr. Ferguson for finding the velocity of the water from the height of the fall, viz. 64.2882 is not correct. From the recent experiments of Mr. Whitehurst on pendulums, it appears, that a heavy body falls 16.087 feet in a second of time; consequently the constant number should be 64.348.

In Mr. Ferguson's table, the velocity of the millstone is too small; and Mr. Imison, in correcting this mistake, has made the velocity too great. From this circumstance, the mill-wrights' table, as hitherto published, is fundamentally erroneous, and is more calculated to mislead than to direct the practical mechanic. Proceeding, therefore, upon the practical deductions of Smeaton, as confirmed by theory, and employing a more correct constant number, and a more suitable velocity for the millstone, we may construct a new mill-wrights' table by the following rules.

Method of constructing the table.

Fig. 1.

1, Find the perpendicular height of the fall of water in feet above the bottom of the mill-course at K (Fig. 1, Plate 1); and having diminished this number by one half of the natural depth of the water at K, call that the height of the fall.[a]

Physique. Such unequivocal instances of literary robbery cannot be too severely reprobated.

[a] The height of the fall here meant is the relative or virtual height, and it is supposed that the mill-course is so accurately constructed, that the water will have the same velocity at K as it would have at R by falling perpendicu-

2, Since bodies acquire a velocity of 32.174 feet in a second, by falling through 16.087 feet, and since the velocities of falling bodies are as the square roots of the heights through which they fall, the square root of 16.087 will be to the square root of the height of the fall as 32.174 to a fourth number, which will be the velocity of the water. Therefore the velocity of the water may be always found by multiplying 32.174, by the square root of the height of the fall, and dividing that product by the square root of 16.087.—Or it may be found more easily by multiplying the height of the fall by the constant number 64.348, and extracting the square root of the product, which, abstracting the effects of friction, will be the velocity of the water required.[3]

---

larly through *CR*. This will be nearly the case when the mill-course is formed according to the directions formerly given; though in general a few inches should be taken from the fall, in order to obtain accurately its relative or virtual height.

[3] That the velocity of the water is equal to the square root of the product of the height of the fall, and the constant number 64.348, may be shewn in the following manner. Let x be the velocity of the water, m the height of the fall, $a = 16.087$, and consequently $2a = 32.174$. Then by the first part of the second rule $\sqrt{a} : \sqrt{m} = 2a : x$ therefore $x = \frac{2a\sqrt{m}}{\sqrt{a}}$; multiplying by $\sqrt{a}$ we have $x\sqrt{a} = 2a\sqrt{m}$; putting all the quantities under the radical sign there comes out $\sqrt{x^2 a} = 4a^2 m$; extracting the square root of both sides, we have $x^2 a = 4a^2 m$, dividing by a gives $x^2 = 4am$ or $x = \sqrt{4am}$. But since the constant number 64.348 is double of 32.174, it will be equal to $4a$; then by the latter part of rule second we have $x = \sqrt{4am}$, which is the same value of x, as was found from the first part of the rule.

3, Take *one half* of the velocity of the water, and it will be the velocity which must be given to the float-boards, or the number of feet they must move through in a second, in order that the greatest effect may be produced.

4, Divide the circumference of the wheel by the velocity of its float-boards per second, and the quotient will be the number of seconds in which the wheel revolves.

5, Divide 60 by this last number, and the quotient will be the number of revolutions which the wheel performs in a minute.—Or the number of revolutions performed by the wheel in a minute, may be found by multiplying the velocity of the float-boards by 60, and dividing the product by the circumference of the wheel, which in the present case is 47.12.

6, Divide 90 (the number of revolutions which a millstone 5 feet diameter should perform in a minute) by the number of revolutions made by the wheel in a minute, and the quotient will be the number of turns which the millstone ought to make for one revolution of the wheel.

7, Then, as the number of revolutions of the wheel in a minute is to the number of revolutions of the millstone in a minute, so must the number of staves in the trundle be to the number of teeth in the wheel, in the nearest whole numbers that can be found.[4]

---

[4] We have filled up the *sixth* column of the tables in the common way; but, for the proper method of finding the relation between the radius of the spur wheel and trundle, and the exact number of teeth in the one, and staves in the other, we must refer the reader to pp. 154-5 of this volume.

8, Multiply the number of revolutions performed by the wheel in a minute, by the number of revolutions made by the millstone for one of the wheel, and the product will be the number of revolutions performed by the millstone in a minute.

In this manner the following table has been calculated for a water-wheel fifteen feet in diameter, which is a good medium size, the millstone being five feet in diameter, and revolving 90 times in a minute.

TABLE I.

A NEW MILL-WRIGHT'S TABLE,
In which the velocity of the wheel is one-half the velocity of the stream, the effects of friction not being considered.

Height of the effective fall of water.	Velocity of the water per second, friction not being considered.	Velocity of the wheel per second, being one half that of the water.	Revolutions of the wheel per minute, its diameter being 15 feet.	Revolutions of the mill-stone for one of the wheel.	Teeth in the wheel and staves in the trundle.		Revolutions of the mill-stone per minute by these staves and teeth.
Feet.	Feet. 100 parts of a foot.	Feet. 100 parts of a foot.	Revol. 100 parts of a revol.	Revol. 100 parts of a revol.	Teeth.	Staves.	Revol. 100 parts of a revol.
1	8.02	4.01	5.10	17.65	106	6	90.01
2	11.34	5.67	7.22	12.47	87	7	90.03
3	13.89	6.95	8.85	10.17	81	8	90.00
4	16.04	8.02	10.20	8.82	79	9	89.96
5	17.94	8.97	11.43	7.87	71	9	89.95
6	19.65	9.82	12.50	7.20	65	9	90.00
7	21.22	10.61	13.51	6.66	60	9	89.98
8	22.69	11.34	14.45	6.23	56	9	90.02
9	24.06	12.03	15.31	5.88	53	9	90.02
10	25.37	12.69	16.17	5.57	56	10	90.06
11	26.60	13.30	16.95	5.31	53	10	90.00
12	27.79	13.90	17.70	5.08	51	10	89.91
13	28.92	14.46	18.41	4.89	49	10	90.02
14	30.01	15.01	19.11	4.71	47	10	90.00
15	31.07	15.53	19.80	4.55	48	11	90.09
16	32.09	16.04	20.40	4.45	44	10	89.96
17	33.07	16.54	21. 5	4.28	47	11	90.09
18	34.03	17. 2	21.66	4.16	50	12	90.10
19	34.97	17.48	22.26	4.04	44	11	89.93
20	35.97	17.99	22.86	3.94	48	12	90.07
1	2	3	4	5	6		7

TABLE II.

A NEW MILL-WRIGHT'S TABLE,
In which the velocity of the wheel is three-sevenths of the velocity of the water, and the effects of friction on the velocity of the stream reduced to computation.

Height of the fall of water.	Velocity of the water per second, friction being considered.	Velocity of the wheel per second, being 3-7ths that of the water.	Revolutions of the wheel per minute, its diameter being 15 feet.	Revolutionsof mill-stone for one of the wheel.	Teeth in the wheel and staves in the trundle.		Revolutions of the mill-stone per minute, by these staves and teeth.
Feet.	Feet. 100 parts of a foot.	Feet. 100 parts of a foot	Revol. 100 parts of a revol.	Revol. 100 parts of a revol.	Teeth.	Staves.	Revol. 100 parts of a revol.
1	7.62	3.27	4.16	21.63	130	6	89.98
2	10.77	4.62	5.88	15.31	92	6	90.02
3	13.20	5.66	7.20	12.50	100	8	90.00
4	15.24	6.53	8.32	10.81	97	9	89.94
5	17.04	7.30	9.28	9.70	97	10	90.02
6	18.67	8.00	10.19	8.83	97	11	89.98
7	20.15	8.64	10.99	8.19	90	11	90.01
8	21.56	9.24	11.76	7.65	84	11	89.96
9	22.86	9.80	12.47	7.22	72	10	90.03
10	24.10	10.33	13.15	6.84	82	12	89.95
11	25.27	10.83	13.79	6.53	85	13	90.05
12	26.40	11.31	14.40	6.25	72	12	90.00
13	27.47	11.77	14.99	6.00	72	12	89.94
14	28.51	12.22	15.56	5.78	75	13	89.94
15	29.52	12,65	16.13	5.58	67	12	90.01
16	30.48	13.06	16.63	5.41	65	12	89.97
17	31.42	13.46	17.14	5.25	63	12	89.99
18	32.33	13.86	17.65	5.10	61	12	90.01
19	33.22	14.24	18.13	4.96	64	13	89.92
20	34.17	14.64	18.64	4.83	58	12	89.84
1	2	3	4	5	6		7

Explanation and Use of the Mill-wrights' Tables.

It has already been observed, that, according to theory, an undershot wheel will produce the greatest possible effect, when the velocity of the stream is double the velocity of the wheel; and, upon this principle, the first of the preceding tables has been computed. When we consider, however, that, after every precaution is observed, a small quantity of water will escape between the mill-course and the extremities of the float-boards; and that the effect is diminished by the resistance of the air, and the dispersion of the water carried up by the wheel, the propriety of making the wheel move with $\frac{3}{7}$ of the velocity of the water will readily appear. The Chevalier de Borda supposes it never to exceed $\frac{3}{8}$, and Mr. Smeaton found it to be much nearer $\frac{1}{2}$ than $\frac{3}{5}$. With $\frac{3}{7}$, therefore, as a proper medium, the numbers in Table II have been computed for this new velocity of the wheel.—In Table I, the water is supposed to move with the same velocity as falling bodies. Owing to its friction on the mill-course, &c. this is not exactly the case; but the error, arising from the neglect of friction, might be in a great measure removed, by diminishing the height of the fall a few inches, in order to have the effective height, with which the other numbers are to be taken out of the table[1]. As this mode of estimating the effects of friction is rather uncertain, we have deduced the velocity of the water

The velocity of the wheel should, in practice, be 3-7ths that of the stream.

[1] See page 170, note.

from the following formula, $V = \sqrt{\frac{17^2}{3} \times Rb - \frac{1}{2} Hh}$, in which V is the velocity of the water, Rb the absolute height of the fall, and Hh the depth of the water at the bottom of the course. This formula is founded on the experiments of Bossut, from which it appears, that if a canal be inclined $\frac{1}{10}$ part of its length, this additional declivity will restore that velocity to the water which was destroyed by friction.

Velocity of the water diminished by friction.

We would not advise the mechanic, however, to trust to the second column of Table II for the true velocity of the stream, or to any theoretical results, even when deduced from formula that are most agreeable to experience. Bossut, with great justice, remarks, 'It would not be exact, 'in practice, to compute the velocity of a cur-'rent from its declivity. This velocity ought to 'be determined by immediate experiment in 'every particular case.'[1]—Let the velocity of the water, where it strikes the wheel, be determined by the method which we shall now explain. With this velocity, as an argument, enter column second of either of the tables, according to the velocity which is required for the wheel, and take out the other numbers from the table.

Method of measuring the Velocity of Water.

A variety of methods have been proposed, by different philosophers, for measuring the velocity of running water. The method by floating bodies, employed by Mariotte; the bent tube (*tube*

Different methods of ascertaining the velocity of running water.

[1] Traite d'Hydrodynamique, § 645.

recourbe) of Pitot;[3] the regulator of Guglielmini;[4] the quadrant,[5] the little wheel,[6] and the method proposed by the Abbé Mann,[7] have each their advantages and disadvantages. The little wheel was employed by Bossut. It is the most convenient mode of determining the superficial velocity of the water; and when constructed, in the following manner, it will be more accurate, I presume, than any instrument that has hitherto been used. The small wheel *WW* should be formed of the lightest materials. It should be about 10 or 12 inches in diameter, and furnished with 14 or 16 float-boards. This wheel moves upon a delicate screw *aB* passing through its axle *Bb*; and when impelled by the stream, it will gradually approach towards *D*, each revolution of the wheel corresponding with a thread of the screw. The number of revolutions performed, in a given time, are determined upon the scale *m a*, by means of the index *O h*, fixed at *O*, and moveable with the wheel, each division of the scale being equal to the breadth of a thread of the screw, and the extremity *h* of the index *Oh* coinciding with the beginning of the scale, when the shoulder *b* of the wheel is screwed close to the scale *a*. The parts of a revolution are indicated by the bent index *m n* pointing to the periphery of the wheel, which is divided into 100 parts. When this instrument is to be used, take it by the handles *C*, *D*, screw the shoulder *b* of the wheel close to *a*, so that the indices may both

Plate XII, Fig. 1. App. Simple instrument for measuring the velocity of running water.

---

[3] Mem. de l'Acad. Paris 1732.
[4] Aquarum fluentium Mensura, lib. iv.
[5] Bossut, Traite d'Hydrodynamique, § 654.
[6] Id. Id. § 655.
[7] Phil. Trans. v. lxix.

point to 0, the commencement of the scales; then, by means of a stop-watch, or a pendulum, find how many revolutions of the wheel are performed in a given time. Multiply the mean circumference of the wheel, or the circumference deduced from the mean radius, which is equal to the distance of the centre of impulsion from the axis *bB*, by the number of revolutions, and the product will be the number of feet which the water moves through in the given time. On account of the friction of the screw, the resistance of the air, and the weight of the wheel, its circumference will move with a velocity a little less than that of the stream; but the diminution of velocity, arising from these causes, may be estimated with sufficient precision for all the purposes of the practical mechanic.

ON HORIZONTAL MILLS.

Horizontal mills.

Although horizontal water wheels are very common on the Continent, and are strongly recommended to our notice by the simplicity of their construction, yet they have almost never been erected in this country, and are therefore not described in any of our treatises on practical mechanics. In order to supply this defect, and recommend them to the attention of the mill-wright, we shall give a brief account of their construction. In Fig. 6, we have a representation of one of these mills. *AB* is the large water-wheel, which moves horizontally upon its arbor *CD*. This arbor passes through the immoveable mill-stone *EF* at *D;* and, being fixed to the upper one *GH*, carries it once round, for every revolution of the great wheel; *N* is the hopper, and *I* the mill-

Plate I, Fig. 6.

shoe, the rest of the construction being the same as in vertical corn mills.

Mill-course.

The mill-course is constructed in the same manner for horizontal as for vertical wheels, with this difference only, that the part *mBnC*, Fig. 2, of which *KL*, in Fig. 1, is a section, instead of being rectilineal like *m n*, must be circular like *mP*, and concentric with the rim of the wheel, sufficient room being left between it and the tips of the float-boards, for the play of the wheel.

The equipage[8] of the mill-stone of a horizontal mill may be found by multiplying the product of the 100th part of the expence of the water in cubic feet, and the relative fall, by 5078, and the product will be the weight of the equipage in pounds avoirdupois.

The mean radius of the wheel *AB* is to be determined by multiplying the product of the relative fall, and the square root of the expence of water in a second by 0.062.

Number, position, and form of the float-boards.

What has been said respecting the number, position, and form of the float-boards, of vertical wheels, may be applied also to horizontal ones. In the latter, however, the float-boards must be inclined, not only to the radius, but also to the plane of the wheel, with the same angle as they are inclined to the radius, so that the lowest and the outermost sides of the float-boards may be farthest up the stream.

Velocity of the mill-stone.

Since the millstone of horizontal mills performs the same number of revolutions as the water-wheel; and since a millstone five feet in diameter should never make less than 48 turns in a minute, the wheel must perform the same

[8] The equipage comprehends the mill-stone, the water-wheel, and its arbor.

number of revolutions in the same time; and in order that the effect may be a *maximum*, or the greatest possible, the velocity of the current must be *double* that of the wheel. Suppose the millstone, for example, to be five feet diameter, and the water-wheel six feet, it is evident that the millstone and wheel must at least revolve 48 times in a minute; and since the circumference of the wheel is 18.8 feet, the float-boards will move through that space in the 48th part of a minute, that is nearly at the rate of 15 feet per second, which being doubled makes the velocity of the water 30 feet, answering, as appears from the preceding table, to a fall of 14 feet. But if the given fall of water be less than 14 feet, we may procure the same velocity to the millstone by diminishing the diameter of the wheel. If the wheel, for instance, is only five feet diameter, its circumference will be 15.7 feet, and its floats will move at the rate of 12.56 feet in a second, the double of which is 25.12 feet per second, which answers to a head of water less than ten feet high. As the diameter of the water-wheel, however, should never be less than seven times the breadth of the mill-course at *K*, (Fig. 1), there will be a certain height of the fall beneath which we cannot employ horizontal wheels,[9] without making the millstone revolve too slowly. This height will be found by the following table.

---

[9] This applies only to mills for grinding corn, where the millstone is fixed on the arbor of the water-wheel, and must move with a determinate velocity. For any other purpose horizontal wheels may be used, however small be the fall of water.

Method of finding whether horizontal or vertical mills should be erected.

When the natural depth of the water at the bottom of the fall is to the breadth of the mill-course at the same place, as	3 to 1	2 to 1	1 to 1 Equal.	$\frac{1}{2}$ to 1	$\frac{1}{3}$ to 1
The relative fall beneath which we cannot employ horizontal mills, will be	7.314	8.602	11.350	14.976	17.613
	Ft. Dec	Ft. Dec.	Ft. Dec.	Ft. Dec.	Ft. Dec.

Thus, if the natural depth of the water at *K*, Fig. 1, is three times the width of the mill-course at the same place, the relative fall beneath which we cannot employ a horizontal wheel will be 7.314 feet. Since the depth of the water is so great in this case, a great quantity of it will be discharged in a second, and therefore it requires a less velocity, or a less height of the fall, to impel the wheel, whereas if the depth of the water had been only one third of the width of the mill-course, such a small quantity would be discharged in a second that we must make up for the want of water by giving a great velocity to what we have, or by making the height of the fall 17.613 feet.

In order to find the radius of the millstone in horizontal mills, multiply the expence of water in cubic feet in a second, by the relative fall; extract the square root of the product, and multiply this root by 0.267, the product will be the radius of the millstone in feet.

Performance of horizontal mills.

The quantity of meal ground in an hour may be found by the rules already given for vertical mills, or by multiplying the product of the ex-

pence of water, and the relative fall, by 45616, and the result will be the quantity required.

The thickness of the millstone at the centre and circumference, the thickness of the arbor and pivots, may be determined by the rules already laid down for vertical mills.

Horizontal mills with inclined float-boards.

In horizontal wheels, the mill-course is sometimes differently constructed. Instead of the water assuming a horizontal direction before it strikes the wheel, as in the case of undershot-mills, the float-board is so inclined as to receive the impulse perpendicularly, and in the direction of the declivity of the waterfall. When this construction is adopted, the greatest effect will be produced when the velocity of the float-boards is not less than $\frac{5.67\sqrt{H}}{2 \text{ Sin. } A}$, in which H represents the height of the waterfall, and A the angle which the direction of the fall makes with a vertical line. But since this quantity increases as the sine of A decreases, it follows, that without taking from the effect of these wheels, we may diminish the angle A, and thus augment considerably the velocity of the float-boards, according to the nature of the machinery employed; whereas, in vertical wheels, there is only one determinate velocity, which produces a maximum effect.[s]

With curvilineal float-boards.

In the southern provinces of France, where horizontal wheels are very generally employed, the float-boards are made of a curvilineal form, so as to be concave towards the stream. The Chevalier de Borda observes, that in theory a double effect is produced when the float-boards

[s] See Memoire sur les Roues Hydrauliques, Mem. de L'Acad. Royal. Par. 1767, p. 285.

are concave, but that this effect is diminished in practice, from the difficulty of making the fluid enter and leave the curve in a proper direction. Notwithstanding this difficulty, however, and other defects which might be pointed out, horizontal wheels with concave float-boards are always superior to those in which the float-boards are plain, and even to vertical wheels, when there is a sufficient head of water. When the float-boards are plain, the wheel is driven merely by the impulse of the stream; but when they are concave, a part of the water acts by its weight, and increases the velocity of the wheel. If the fall of water be five or six feet, a horizontal wheel with concave float-boards may be erected, whose maximum effect will be to that of ordinary vertical wheels as 3 to 2.

Conical horizontal wheel with spiral float-boards.

In the provinces of Guyenne and Languedoc, another species of horizontal wheels is employed for turning machinery. They consist of an inverted cone, *A B*, with spiral float-boards of a curvilineal form winding round its surface. The wheel moves on a vertical axis in the building *D D*, and is driven chiefly by the impulse of the water conveyed by the canal *C* to the oblique float-boards. When the water has spent its impulsive force, it descends along the spirals, and continues to act by its weight till it reaches the bottom, where it is carried off by the canal *M*.

PLATE XIII, Fig. 2, *App.*

ON DOUBLE CORN MILLS.

Double corn mills.

It frequently happens that one water-wheel drives two millstones, in which case the mill is said to be double; and when there is a copious discharge of water from a high fall, the same

water-wheel may give sufficient velocity to three, four, or five millstones. Mr. Ferguson has given a brief description of a double mill in vol. i, p. 101, and a drawing of one in Plate VII, Fig. 4, but has laid down no maxim of construction for the use of the practical mechanic. In supplying this defect, let us first attend to double horizontal mills, in which the axis *CD*, Fig. 6, is furnished with a wheel which gives motion to two trundles, the arbors of which carry the millstones. Fig. 6.

In order to find the weight of the equipage for each millsone, multiply the product of the expence of water, and the relative fall, by 48116lb, and divide the product by 2000, if there are two millstones, 3000 if there are three, and so on, the quotient will be the weight of the equipage of each millstone.

Size of the wheel that drives the trundles.

To determine the radius of the wheel that drives the trundles, find first the radius of the millstones by the rules already given, and having added it to half the distance between the two neighbouring millstones,[a] subtract from this *sum* the radius of the lantern, which may be taken at pleasure, and the remainder will be the radius required when there are two millstones. But if there are three millstones, or four, or five, or six, before subtracting the radius of the lantern, divide the sum by 0.864, 0.705, 0.587, 0.5, respectively.

Size of the water-wheel.

The mean radius of the water-wheel may be found by multiplying the square root of the relative fall by the radius of the millstone, by the

[a] This quantity may be taken at pleasure, and should never be less than 2 feet, however great be the number of the millstones.

radius of the wheel that drives the trundles, and by 231, and then dividing the product by the radius of the lantern multiplied by 1000, the quotient will be the wheel's radius. It may happen, however, that the diameter of the wheel found in this way is too great. When this is the case, we may be certain that the radius of the lantern has been taken too small. In order then to get a less value for the wheel's radius, increase a little the radius of the lantern, and find new numbers both for the water-wheel, and that which drives the trundles, by the preceding rule. It may happen also, that in giving an arbitrary value to the radius of the lantern, the diameter of the wheel found by the rule may be too small, that is, less than seven times the breadth of the mill-course at the bottom of the fall. When this takes place, make the diameter of the water-wheel seven times the width of the mill-course, and you may find the radius of the other wheel and lanterns by the following rules.

Size of the wheel that drives the, trundle.

1. To find the radius of the wheel that impels the trundles; add the radius of the millstone to half the distance between any two adjoining millstones for a first quantity. Multiply the square root of the relative fall by the radius of the millstone and by .231; and having divided the product by the radius of the water-wheel, add unity to the quotient, and multiply the sum by 1 if there are two millstones, by .864 if there are three, by .705 if there are four, by .587 if there are five, and by .5 if there are six, and the result will be a second quantity. Divide the first by the second quantity, and the quotient will be the radius of the wheel that drives the trundles.

2. To find the radius of the lantern, multiply

the radius of the wheel as found by the preceding rule, by the square root of the relative fall, and by .231, and divide the product by the radius of the water-wheel, the quotient will be the lantern's radius. Size of the lantern.

By the rules formerly given find the quantity of meal ground by one millstone, and having multiplied this by the number of millstones, the result will be the quantity ground by the compound mill.

If the equipage of the millstone of a vertical mill, as found in p. 159, should be too great, that is, if it should require too large a millstone, then we must employ a double mill, like that which is represented in Plate VII, Fig. 4, or one which has more than two millstones.

In order to know the equipage of each millstone, find it by the rule for a single mill, and having multiplied the quantity by .947, divide the product by the number of millstones, and the quotient will be the equipage of each millstone.

The radius of the wheel *D*, Plate VII, Fig. 4, will be found by the same rule which was given for horizontal mills; but it must be attended to, that the lantern whose radius is there employed is not *BB*, but *FG*, or *EH*.

To determine the mean radius of the large spur-wheel *AA*, which is fixed upon the arbor of the water-wheel, multiply the square of the radius of the lanterns *FG* or *EH*, by the radius of the water-wheel, and also by 4302, and a first quantity will be had. Multiply the square root of the relative fall by the radius of one of the millstones, and by the radius of the wheel *D*, and by 1000, and a second quantity will be obtained. Divide the first quantity by the second, and the quotient will be the mean radius of the wheel *AA*. Size of the spur-wheel.

The quantity of meal ground by a compound mill of this kind, is found by the same rule that was employed for compound mills driven by a horizontal water-wheel.

ON BREAST MILLS.

Breast mills.

PLATE II, Fig. 1.

A breast water-wheel partakes of the nature both of an overshot and an undershot wheel: it is driven partly by the impulse, but chiefly by the weight of the water. Fig. 1, of Plate II, represents a water-wheel of this description, where *MC* is the stream of water falling upon the float-board *o*, with a velocity corresponding to the height *m n*, and afterwards acting by its weight upon the float-boards between *o* and *B*. The mill-course *o B* is concentric with the wheel, which is fitted to it in such a manner that very little water is permitted to escape at the sides and extremities of the float-boards. The effect of a mill driven in this manner, is equal, according to Mr. Smeaton, 'to the effect of an under-'shot mill, whose head is equal to the differ-'ence of level between the surface of water in 'the reservoir and the point where it strikes the 'wheel, added to that of an overshot, whose 'height is equal to the difference of level be-'tween the point where it strikes the wheel and 'the level of the tail water.'[3] That is, the effect of the wheel *A* is equal to that of an undershot wheel driven by a fall of water equal to *m n*, added to that of an overshot wheel whose height is equal to *n D*. M. Lambert of the Academy

[3] Smeaton on Mills, *Scholium*, p. 36.

of Sciences at Berlin,[4] has shewn, that when the float-boards arrive at the position *o p*, they should be horizontal, or the point *p* should be lower than *o*, in order that the whole space between any two adjacent float-boards may be filled with water; and that *C m* should be equal to the depth of the float-boards. He observes also, that a breast wheel should be used when the fall of water is above four feet, and below ten, provided the discharge of water is sufficiently copious; that an undershot wheel should be preferred when the fall is below four feet, and an overshot wheel when the fall exceeds ten feet; and that, when the fall exceeds 12 feet, it should be divided into two, and two breast mills erected. This, however, is only a general rule which many circumstances may render it necessary to overlook. The following table, which may be of essential utility to the practical mechanic, is calculated from the formulæ of Lambert, and exhibits at one view the result of his investigations.

---

[4] Nouv. Mem. de l'Acad. de Berlin, 1775, p. 71.

Table for Breast Mills.

Height of the fall in feet = CD, Fig. 1, Plate II.	Breadth of the float-boards.	Depth of the float-boards.	Radius of the water wheel reckoned from the extremity of the float-boards.	Velocity of the wheel per second.	Time in which the wheel performs one revolution.	Turns of the mill-stone for one of the wheel.	Force of the water upon the float-boards.	The length of $m\ n$ in Fig. 1, Plate II.	The length of $n\ o$ in Fig. 1, Plate II.	Water required per second to turn the wheel.
	Ft. Dec.	Ft. Dec.	Ft. Dec.	Ft. Dec.	Secs. Dec.		lbs. Avoir.	Ft. Dec.	Ft. Dec.	Cub. Ft.
1	0.17	198. 6	0.75	2.18	1.92	4.80	1536	0.08	0.23	74.30
2	0.34	35. 1	1.50	3.09	2.72	6.80	1084	0.15	0.46	37.15
3	0.51	12. 7	2.26	3.78	3.33	8.32	886	0.23	0.68	24.77
4	0.69	6. 2	3.01	4.36	3.84	9.60	768	0.30	0.91	18.57
5	0.86	3.57	3.76	4.88	4.28	10.70	686	0.38	1.14	14.86
6	1.03	2.25	4.51	5.35	4.70	11.76	626	0.46	1.37	12.38
7	1.20	1.53	5.26	5.77	5.08	12.70	581	0.53	1.60	10.61
8	1.37	1.10	6.02	6.17	5.48	13.58	543	0.60	1.83	9.29
9	1.54	0.81	6.77	6.55	5.76	14.40	512	0.68	2.05	8.26
10	1.71	0.77	7.52	6.90	6.07	15.18	486	0.76	2.28	7.43
1	2	3	4	5	6	7	8	9	10	11

It is evident from the preceding table, that, when the height of the fall is less than 3 feet, the depth of the float-boards is so great, and their breadth so small, that the breast-wheel cannot well be employed; and, on the contrary, when the height of the fall approaches to 10 feet, the depth of the float-boards is too small in proportion to their breadth. These two extremes, therefore, must be avoided in practice. The eleventh column contains the quantity of water necessary for impelling the wheel, but the total expence of water should always exceed this by the quantity, at least, which escapes between the mill-course and the sides and extremities of the float-boards.

Dimensions of a breast wheel.

Mr. Siebike, son of the inspector of mills at Berlin, has given the following dimensions of an excellent breast water-wheel, differing very little from that which is represented in Fig. 1, Plate 2. The water, however, instead of falling through the height *c n*, which is 16 inches Rhynland measure,[5] is delivered on the float-board *o p*, through an adjutage $6\frac{1}{2}$ inches high. The height *n D* is 4 feet 2 inches; consequently, the whole height *C D* must be $5\frac{1}{2}$ feet. The radius of the wheel *A B* is $6\frac{1}{2}$ feet, the breadth of each float-board $6\frac{1}{2}$ inches, and its depth 28 inches. The point *P* of the wheel moves at the rate 7,588 feet in a second. The expence of water in a second is 5,266 cubic feet, and the force upon the float-boards 356 pounds avoirdupois. The turning millstone weighed 1976 lbs. avoirdupois; its diameter was 3 feet $8\frac{1}{2}$ inches, and it performed $2\frac{1}{2}$ revolutions in a second.

Plate II, Fig. 1.

[5] A Rhynland foot is to an English foot as 1033 to 1000, or one Rhynland foot is equal to 12 inches and 4 lines English.

MECHANICS.

PRACTICAL REMARKS ON THE PERFORMANCE AND CONSTRUCTION OF OVERSHOT WATER WHEELS.

On the method of computing the effective power of overshot wheels in turning machinery.

On the power of water on overshot wheels.

In overshot mills, where the wheel is moved by the weight of the water in the buckets, each bucket has a different power to turn the wheel; and this power is proportioned to the distance of the bucket from the top or bottom of the wheel; or more accurately, to the sine of the arch contained between the centre of the bucket and the top or bottom of the wheel, according as the bucket is above or below its centre. The bucket, for instance, placed upon the top of the wheel, has no power to turn it; the bucket next to this contributes but a little to turn the wheel, because it is virtually placed at the extremity of a very short lever; whereas the bucket, which is equally distant from the top and bottom of the wheel, and which is level with the centre, has the greatest power to turn it, because it acts at the extremity of a lever equal to the wheel's semidiameter. If we suppose, then, that each bucket contains

one gallon of water, equal in weight to 10.2 lb avoirdupois; we may, by the simplest operations in trigonometry, compute, in pounds avoirdupois, the power which each bucket exerts in turning the wheel; and, by taking the sum of these, we will have the effective weight of the water[3] in the buckets, and, consequently, its proportion to the real weight of the water, with which the semi-circumference of the wheel is loaded. Those who choose to make this calculation, will find that the total weight of water upon the semi-circumference of an overshot wheel is to the effective weight as 1 to .637; but, as two or three of the buckets at the bottom of the arch are always empty, the proportion will rather be as 1 to .75 nearly. From these principles, we may deduce the following method, simpler than any hitherto given, of computing the effective weight of water upon overshot wheels of any diameter.

RULE.—Multiply the constant number 6.12 by half the number of buckets, and this product by the number of gallons in each bucket, and the result will be the effective weight of the water upon the wheel, three buckets being supposed empty at the bottom. This rule is pretty accurate for wheels from 20 to 32 feet in diameter. But when the diameter of the wheel is

Rule for finding it.

[3] This phrase, which is used by practical mechanics, is very exceptionable; as every drop of water in the buckets, excepting the vertical bucket, is *effective*. By the effective weight of the water, therefore, we must understand that weight which, if suspended at the opposite extremity of the wheel, would keep it in *equilibrio*, or balance the loaded arch.

less than 20 feet, the answer given by the rule must be diminished one pound avoirdupois for every foot which the wheel is less than 20.

Suppose that it is required to find the effective weight of water upon a wheel 18 feet in diameter, having 40 buckets, each containing two gallons ale measure. Then $6.12 \times 20 \times 2 = 244.8$. But as the diameter of the wheel is two feet below 20, we must deduct two pounds from the preceding answer, and the result will be 242.8 lb avoirdupois.

On the performance of Overshot and Undershot Mills.

Performance of overshot and undershot wheels.

From a number of accurate experiments made by the ingenious Mr. Fenwick, upon a variety of excellent overshot mills, it appears, that when the water wheel is 20 feet in diameter, 392 gallons of water per minute (ale measure) will grind one boll of corn per hour (Winchester measure); 675 gallons per minute will grind 2 bolls; 945 gallons will grind 3 bolls; 1270 gallons will grind 4 bolls, and 1623 gallons will grind 5 bolls. From these data it will be easy to compute the performance of an overshot mill, whatever be the diameter of the wheel and the supply of water.

Examples.

EXAMPLE 1.—Let it be required to find how many bolls of corn will be ground by an overshot mill, driven by a wheel 25 feet in diameter, upon which 1150 gallons of water are discharged in a minute. Say, as the nearest number

Galls. Bolls. Galls. Bolls.

1270 : 4 = 1150 : 3.62, the quantity of corn

ground by a wheel 20 feet in diameter. Then to find the quantity which a 25 feet wheel will
Feet. Bolls. Feet. Bolls.
grind, say, as 20 : 3.62 = 25 : 4.52 the answer required.

EXAMPLE 2.—If it is required to grind $3\frac{1}{2}$ bolls of corn per hour, where the stream discharges 2220 gallons in a minute, what must be the diameter of the wheel? Find the number of gallons which a 20 feet wheel will require for grinding the given quantity of corn by the following proportion.
Bolls. Galls. Bolls. Galls.
As 4 : 1270 = 3.5 : 1111. Then, by inverse
Galls. Feet. Galls. Feet.
proportion, 1111 : 20 = 2220 : 10 the diameter of the wheel required.

Performance of undershot mills.

In order to find the quantity of corn ground by an undershot mill, which is moved by a similar wheel, and a similar quantity of water, as an overshot mill; divide the quantity ground in an overshot mill by 2.4, and the quotient will be the answer. If it is required to know what size of wheel is necessary for making an undershot mill grind a certain quantity of corn, the supply of water being given; find the size of an overshot wheel necessary for producing the same effect, and multiply this by 2.4; the product will be the required diameter of the undershot wheel.

On the formation of the Buckets, and the proper Velocity of Overshot Wheels.

Plate III, Fig. 4.

Let *AM* (Plate III, Fig. 4) be part of the shrouding, or ring, of buckets of an overshot wheel, *GOFABCD* is the form of one of these buckets. The shoulder, *AB*, of the bucket should be one half of *AE*, the depth of the shrouding; *AF* should be $\frac{1}{5}$ more than *AE*. The arm, *BC*, of the bucket must be so inclined to *AB*, that *HC* may be $\frac{1}{6}$ of *AE*; and *CD*, the wrist of the bucket, must make such an angle with *BCn*, the direction of the arm, that *Dn* may be $\frac{1}{5}$ of *En*.

Form of the buckets of overshot wheels.

Improvement by Mr. Burns.

A very considerable improvement, in the construction of the bucket, has been made, by Mr. Robert Burns, at Cartside, Renfrewshire. He divides the bucket, by a partition, *mB*, of such a height, that the portions of the bucket, on each side of it, may be of equal capacity. Dr. Robison observes, that this principle is susceptible of considerable extension, and recommends two or more partitions, particularly when the wheel is made of iron. By this means, the fluid is retained longer in the lower buckets, and when there is a small supply of water, it may be delivered into the outer portion of the bucket, which, being at a greater distance from the centre of motion, increases the power of the water to turn the wheel. Dr. Robison advises, that the rim of the wheel, and consequently the breadth of the buckets, should be pretty large, in order that the quantity of water, which they receive from the spout, may not nearly fill the bucket. The spout,

which conveys the water, should be considerably narrower than the breadth of the bucket; and the shoulder *AB* should be perforated with a few holes, in order to prevent the water from being lifted up by the ascending buckets. The distance of the spout, from the receiving bucket, should, in general, be two or three inches, that the water may be delivered with a velocity a little greater than that of the rim of the wheel; otherwise the wheel will be retarded, by the impulse of the buckets against the stream, and much power would be lost, by the water dashing over them.[5]

Velocity of overshot wheels.

The proper velocity of an overshot wheel is a point, upon which some celebrated mechanicians have entertained different sentiments. From a variety of experiments, Mr. Smeaton infers, in general, that the circumference of the wheel should move with the velocity of a little more than *three feet per second.* 'Experience,' says he, 'confirms, that this velocity of three feet 'in a second is applicable to the highest over-'shot wheels, as well as the lowest; and all 'other parts of the work being properly adapted 'thereto, will produce, very nearly, the greatest 'effect possible; however, this also is certain, 'from experience, that high wheels may deviate 'farther from this rule, before they will lose

---

[5] If the spout be *one inch and seven-tenths* above the receiving bucket, it will deliver the water with the velocity of the wheel, that is about three feet per second. In order, therefore, to make the velocity of the water exceed a little that of the wheel, the height of the spout should be $2\frac{1}{2}$ inches, and the water will move at the rate of three feet seven inches per second. Dr. Robison recommends three or four inches; but this is evidently too great, as four inches gives a velocity of four feet seven inches per second. Height of the spout above the wheel.

'their power, by a given aliquot part of the 'whole, than low ones can be admitted to do; for 'a wheel of 24 feet high may move at the rate 'of six feet per second, without losing any con-'siderable part of its power; and, on the other 'hand, I have seen a wheel of 33 feet high, that 'has moved very steadily and well with a velocity 'but little exceeding two feet.'[6]

Experiments of Deparcieux.

M. Deparcieux[7] shews, that most work is performed by an overshot mill, when it moves slowly, and that the more we retard its motion, by increasing the work to be performed, the greater will be the performance of the wheel.

The effect of overshot wheels inversely as their velocity.

—This important conclusion was deduced, by Deparcieux, from experiments made upon a small wheel, 20 inches in diameter, furnished with 48 buckets, which received the water like a breast-wheel. On the axis of this wheel were placed cylinders of different sizes, the smallest being one inch, and the largest four inches, in diameter, around which was wrapped a cord, with a weight attached to it.[8] When the one-inch cylinder was used, a weight of 12 ounces was elevated to the height of 69 inches and 9 lines; and a weight of 24 ounces was elevated 40 inches. When the four-inch cylinder was employed, a weight of 12 ounces was raised to the altitude of 87 inches and 9 lines, and a weight of 24 ounces to the height of 45 inches and 3 lines. From these results, it is evident, that, with the

[6] Smeaton on Mills, p. 33.

[7] Mem. de l'Acad. Paris, 1754, p. 603, 671, 4to.; p. 928, 1033, 8vo.

[8] The model employed, in Mr. Smeaton's experiments, resembles very much that of Deparcieux, though their experiments were made about the same time.

four-inch cylinder, when the motion was slowest the effect was greatest, and that, when a double weight was used, which diminished the wheel's velocity, the weight was raised to more than half its former height.[1]

This increase of performance, by diminishing the wheel's velocity, has been ascribed to different causes. Deparcieux and Brisson account for it, by saying, that when the motion of the wheel is slow, the same portion of water acts more efficaciously. Dr. Robison and Mr. Smeaton ascribe it to a greater quantity of water pressing on the wheel; for, when the wheel's motion is slow, the buckets receive more water as they pass the spout. One of the most powerful causes, however, is, a diminution of the centrifugal force

Causes of this.

---

[1] Mr. J. Albert Euler, whose memoir, on the best Method of employing the Force of Water and other Fluids, gained the prize, proposed by the Royal Society of Gottingen, in 1754, has also shewn, that the more slowly an overshot, or breast-wheel, with buckets, moves, the greater will be its performance. See the Comment. Gotting. 1754, or the *Journal Etranger, Dec.* 1756. Mr. Smeaton, too, deduces, from his experiments, this general rule, that, *ceteris paribus*, the less the velocity of the wheel, the greater will be its effect. But he obſerves, on the other hand, that, when the wheel of his model made about 20 turns in a minute, the effect was nearly the greatest; when it made 30 turns, the effect was diminished about $\frac{1}{10}$ part; and that, when it made 40, it was diminished about one-fourth; when it made less than $18\frac{1}{4}$ turns, its motion was irregular; and when it was loaded so as not to admit its making 18 turns, the wheel was overpowered by its load; Smeaton on Mills, p. 33. For farther information on this subject, we must refer the reader to the original memoirs quoted above, in the first of which Deparcieux proves his point, by reasoning, and in the second, by experiment; or to Brisson's *Traite de Physique*, tom. i, p. 306, edit. 3, where there is a general view of Deparcieux's experiments.

of the water in the buckets; for, when the velocity of the wheel is great, the water, receding from the centre, is thrown out of the buckets, and they are emptied sooner than they would have been, had the wheel moved with less velocity.

Lambert on overshot wheels.

In the Memoirs of the Academy of Berlin, for 1755, M. Lambert has published a dissertation on the theory of overshot mills; but does not seem to be in the least degree acquainted with the improvements, which have been made upon them, in this country. He supposes the buckets to have the form *GF fg*, (Fig. 4, Plate III), so that about one quarter only of the circumference of the wheel is filled with water. Notwithstanding these circumstances, however, the following table, computed from his formulæ, may be of considerable advantage to the millwright.

Plate III, Fig. 4.

Table for Overshot Mills.

Height of the fall, reckoning from the surface of the stream.	Radius of the wheel reckoning from the extremity of the buckets.	Width of the buckets.	Depth of the buckets.	Velocity of the wheel per second.	Time, in which the wheel performs one revolution.	Turns of the mill-stone for one of the wheel.	Force of the water upon the buckets.	The length of *m n*, in Fig. 1, Plate II.	The length of *n o*, in Fig. 1, Plate II.	Quantity of water required per second to turn the wheel.
Feet.	Ft. Dec.	Ft. Dec.	Ft. Dec.	Ft. Dec.	Sec. Dec.		lbs. Avoir.	Ft. Dec.	Ft. Dec.	ubic Ft.
7	2.83	1.00	2.02	5.27	3.38	8.45	636	0.33	1.15	10.55
8	3.22	1.14	1.44	5.63	3.61	9.02	595	0.38	1.32	9.23
9	3.63	1.27	1.07	5.94	3.83	9.57	565	0.42	1.48	8.21
10	4.04	0.43	0.82	6.30	4.04	10.10	531	0.48	1.65	7.38
11	4.45	0.57	0.65	6.60	4.23	10.57	511	0.52	1.81	6.71
12	4.86	0.71	0.52	6.89	4.42	11.05	486	0.57	1.98	6.15
1	2	3	4	5	6	7	8	9	10	11

Borda on overshot wheels.

M. Le Chevalier de Borda, in his excellent memoir on water-wheels,[6] has shewn, that overshot wheels will produce a maximum effect, when their diameter is equal to the greatest height of the fall, when the water enters the buckets on a level with the surface of the reservoir, or canal, and when the velocity of the wheel is infinitely small. But though the greatest possible effect can be produced only when these conditions are observed, yet a small deviation from them, which is absolutely necessary, in practice, does not greatly diminish their performance. If, for example, we suppose the waterfall to be 12 feet, and the diameter of the wheel only 11 feet, so that the water falls through the space of one foot, before it enters the buckets, and, if we suppose also, that 25 degrees of the semicircumference of the wheel are unloaded, while the remaining 155 degrees are filled with water, then, when the wheel has a velocity of four feet per second, the maximum effect is diminished only $\frac{1}{12}$; and if the velocity be augmented to six feet per second, the diminution amounts only to $\frac{1}{10}$ of the greatest possible effect.

In practice, however, a fall of two or three inches is sufficient; so that, if the wheel, in the preceding example, had been made 11 feet 9 inches, the diminution of effect would have been still more inconsiderable.

Relative effect of water wheels.

In comparing the relative effects of water-wheels, the Chevalier de Borda observes, that overshot wheels will raise, through the height of

[6] Mem. de l'Acad. Paris 1767, 4to, p. 286.

the fall, a quantity of water equal to that by which they are driven; that undershot vertical wheels will produce only $\frac{1}{3}$ of this effect; that horizontal wheels will produce a little less than one half of it when the float-boards are plain, and a little more than one half when the float-boards are of a curvilineal form.

Besant's Undershot Wheel.

Besant's undershot wheel.

The water wheel invented by Mr. Besant of Brompton is constructed in the form of a hollow drum, so as to resist the admission of water. The float-boards are fixed obliquely in pairs on the periphery of the wheel, each pair forming an acute angle, open at its vertex. This is represented in Fig. 3, where AB is the wheel, CD its axle, and mn, op, the position of the float-boards. In common undershot wheels, their motion is greatly retarded by the resistance opposed by the tail water to the ascending float-boards; and their velocity is still farther diminished by the resistance of the air. But when the preceding construction is adopted, the resistance of the air and the tail water is greatly diminished by the oblique position of the float-boards.

Plate XIII, Fig. 3.

Account of an Improvement in Flour Mills.

Improvement in flour mills.

In most of the flour mills in Scotland and England, a considerable quantity of manual labour is necessary before the wheat is converted into flour. When the grain is ground and conveyed into the trough from the mill stones, it is afterwards put into bags and raised to the top of the mill house,

to be laid into the cooling boxes or benches, from which it is conveyed into the bolting machine, to be separated from the bran or husk. This manual labour may be saved by adopting an improvement, for which we are indebted to the ingenuity of the American mill-wrights. A large screw is placed horizontally in the trough, which receives the flour from the millstones. The thread or spiral line of the screw is composed of pieces of wood about two inches broad, and three long, fixed into a wooden cylinder 7 or 8 feet in length, which forms the axis of the screw. When the screw is turned round this axis, it forces the meal from one end of the trough to the other, where it falls into another trough, from which it is raised to the top of the mill house by means of elevators, a piece of machinery similar to the chain pump. These elevators consist of a chain of buckets or concave vessels like large teacups, fixed at proper distances upon a leathern band, which goes round two wheels, one of which is placed at the top of the mill house, and the other at the bottom, in the meal trough. When the wheels are put in motion, the band revolves, and the buckets, dipping into the meal trough, convey the flour to the upper storey, where they discharge their contents. The band of buckets is inclosed in two square boxes, in order to keep them clean, and preserve them from injury.

MECHANICS.

ON DR. BARKER'S MILL.

THIS mill, which is sometimes called *Parent's Mill*, has already been described at considerable length in the supplement.[1] It has exercised the ingenuity of Euler and Bernouilli; and its theory seems to be as complicated as its construction is simple. Instead of conveying the water into the top of the vertical pipe *DB*, M. Mathon de la Cour[2] proposes to bend the pipe *A*, which conducts the water from the reservoir, down by the letters *ONGP*, and to introduce the fluid into the horizontal arm *C* at the point *g*. When the water is thus conveyed into the machine, it rushes out at the holes *d* and *e*, with a velocity corresponding to the height of the reservoir, and the trunck *c* will revolve with a retrograde motion. The cause of this is obvious. If the hole *d* were shut up with a cylindrical pin, the pressure upon the circular area of its base would be equal to a column of water whose base is equal to this circular area, and whose length is the height of the water in the reservoir. But the same force is

Improvements upon Barker's mill.

Plate III, Sup. Fig. 1.

[1] See Rozier's Journal de Physique, Jan. and Aug. 1775.

[2] See p. 97 of this volume.

Mode of its operation.

exerted on an equal portion of the tube opposite to the aperture *d*. The pressures, therefore, upon each side of the arm *c* will be equal and opposite, and no motion will ensue. As soon, however, as the hole *d* is opened, the pressure is removed from that part of the tube, and the arm *c* is driven backwards by the unbalanced pressure on the opposite side. Dr. Robison imagines that this unbalanced pressure is equal to the weight of a column of water, having the orifice for its base, and *twice* the depth under the surface of the water in the trunk for its height, upon the supposition that the arm *C* is also impelled by the reaction of the issuing fluid. Upon this supposition, which is extremely plausible, Barker's mill must be a very powerful machine; and when water is used as the impelling power of machinery, it will produce much greater effects by its reaction, than it does either by its impulse or gravity.

The effect is diminished by the velocity.

As soon as the machine begins to move, the horizontal arm withdraws itself from the pressure; the impelling power is consequently diminished, as it depends upon the relative velocity of the arm *C*, and the issuing fluid. Dr. Desaguliers[3] maintains, that when the engine is in motion, the pressure is equal to the weight of a column, which would make the velocity of efflux equal to the relative velocity of the fluid and the machine; and from this he concludes, that it will produce a maximum effect when the velocity of the arm is $\frac{1}{3}$ of the velocity acquired by falling from the surface of the water in the reservoir, in which case it will raise to the same height

[3] Experimental Philosophy, vol. ii, 3d Edit p. 459.

$\frac{8}{27}$ of the water expended, though $\frac{4}{27}$ is the quantity raised by an undershot mill.

The velocity of the machine is no doubt increased by the centrifugal force of the water in the arms; but this effect is completely counteracted by the inertia of the fluid. For, as a new quantity of water is constantly entering the arms, a considerable portion of its velocity must be lost in communicating to this water the circular motion of the arms. This diminution of velocity may be prevented in some measure by enlarging the diameter of the horizontal arms, which will cause the water to move more slowly to the aperture; but when this is to be done, the form recommended by Euler will be most advantageous. In Fig. 4, is represented a section of the machine, with this form. The canal *a* delivers the water into the bason *CDMN*, in the direction of the tangent, and with the same velocity as the machine. The water then descends in spiral excavations formed by partitions between the conoids *CF*, *EM*, and *DE*, *FN*; and when it reaches the bottom *F*, the water flows off in the direction of the tangent, by means of a spout for each excavation.

And by the inertia of the fluid.

Form recommended by Euler.

Plate XIII, App. Fig. 4

It has often occurred to me, that a very powerful hydraulic machine might be constructed, by combining the impulse with the reaction of water. If the spout *a*, for example, instead of delivering the water into the bason *CD*, were to throw it upon a number of curvilineal float-boards, fixed on the circumference *CD*, and so formed as to convey the water easily into the spiral excavations, we should have a machine something like the conical horizontal wheel in Fig. 2, with spiral channels instead of spiral float-boards, and which would in some measure be moved both by the impulse, weight, and reaction of the water.

New kind of water-wheel suggested.

Practical Rules for the Construction of Barker's Mill, given by Mr. Waring.[4]

Practical Rules.

1, Make the arm of the rotatory tube, from the centre of motion to the centre of the aperture, of any convenient length not less than $\frac{1}{3}$ ($\frac{1}{9}$ according to Mr. Gregory,[5] who has corrected some of Waring's numbers) of the perpendicular height of the water's surface above their centres.

2, Multiply the length of the arm in feet by .614, and take the square root of the product for the proper time of a revolution in seconds, and adapt the other parts of the machinery to this velocity; or,

3, If the time of a revolution be given, multiply the square of this time by 1.63 for the proportional length of the arm.

4, Multiply together the breadth, depth, and velocity, per second, of the race, and divide the last product by 18.47 (14.27 according to Mr. Gregory) times the square root of the height, for the area of either aperture.

5, Multiply the area of either aperture by the height of the head of water, and the product by 41$\frac{2}{3}$ (55.775 according to Mr. Gregory) pounds, for the moving force estimated at the centres of the apertures in pounds avoirdupois.

6, The power and velocity at the aperture may be easily reduced to any part of the machinery by the simplest mechanical rules.

---

[4] Transactions of the Americ. Phil. Soc. vol. iii, p. 193.
[5] Mechanics, vol. ii, p. 111.

M. Mathon de la Cour gives us the following dimensions of one of Dr. Barker's mills, which was erected at Bourg Argental, in order to work ventilators for a large room. The length of the horizontal trunk C was 7 feet 8 inches, and its diameter 3 inches; the diameter of the orifices, at d and e, $1\frac{1}{8}$ inches; the height of the reservoir, above the trunk C, is 21 feet; the diameter of the pipe, which conveyed the water into C, from below, was 2 inches at their junction, and was fitted into it by grinding.

Dimensions of one of Barker's mills.

Plate III, Fig. 1, Sup.

When this machine was doing no work, and when the fluid issued only from one aperture, it performed 115 revolutions in a minute. The aperture, therefore, was moving with the velocity of 46 feet per second; whereas, if this aperture were at rest, the water would have issued only with a velocity of $37\frac{1}{8}$ feet per second. Dr. Robison[2] observes, that this great velocity was produced by the prodigious centrifugal force of the water.

Might it not be advantageous to have another horizontal arm crossing C at right angles?[3]

---

[2] Encyclop. Britan. vol. xviii, p. 909, where the reader will find some excellent remarks upon this machine.

[3] Those, who wish to study this important subject with attention, will find the investigations of Euler in the Mem. Acad. Berlin, 1751, and in the Nov. Comment. Petrop. tom. vii, and those of Bernouilli, at the end of his Hydraulics. See also the Exercitationes Hydraulicæ of Professor Segner, who gives Barker's mill as an invention of his own! and the works which have already been quoted. J. A. Euler proposed a machine to be driven by the re-action of the water in the Com. Gotting. 1755.

MECHANICS.

ON THE FORMATION OF THE TEETH OF WHEELS AND THE LEAVES OF PINIONS.

On the formation of the teeth of wheels, &c.

THOUGH nothing is more essential to the perfection of machinery than the proper formation of the teeth of wheels, and those parts of engines, by which their force and velocity are conveyed to other parts; yet no branch of mechanical science has been more overlooked by the speculative and practical mechanics of this country. In vain do we search our systems of experimental philosophy for information on this point. Their authors seem either to reckon it beneath their notice, or to be unacquainted with the labours of De la Hire, Camus, and other foreign academicians, who have written very ingenious dissertations on the teeth of wheels. It is in the memoirs, indeed, of these philosophers, that all our knowledge upon this subject is contained, if

we except a few general remarks, by the learned Mr. Robison.[3]

Uniform motion produced by epicycloidal teeth.

It would be easy to shew, did the nature of this work permit, that when one wheel drives another, it is not driven with an uniform force and velocity, or, in other words, the one wheel will act sometimes with greater, and sometimes with less, force, and the other will move sometimes with a greater, and sometimes with a less velocity, unless the teeth of one or of both the wheels be parts of a curve, generated after the manner of an epicycloid,[4] by the revolution of another curve along the convex or concave side of a circle. It will be sufficient, for our present purpose, to shew, that, when one wheel impels another, by the action of epicycloidal teeth, the moments of these wheels will be equal. Let the wheel *B* Fig. 7, drive the wheel *A*, by the action of the epicycloidal teeth *m n*, *m' n'*, &c. upon the infinitely small pins, or spindles, *a*, *b*, *c*, and let the epicycloids, *m n*, &c. be generated, by the circumference *c b a*, moving over the circumference *m'' m' m*. It is evident, from the formation of the epicycloid, that the arch *a b* is equal to the arch *m m'*, and

Plate I. Fig. 7.

---

[3] Two ingenious memoirs have also been written upon this subject, by A. G. Kaestner, entitled, *De Dentibus Rotarum*, and published in the Comment. Reg. Soc. Gotting. vol. iv, and v, 1781, &c. The celebrated Euler has also treated this subject with great ability, in his memoir *De aptissima Figura Rotarum Dentibus tribuenda*, *Nov. Comment. Petropol.* 1754, 1755, tom. v, p. 299.

[4] Under curves, of this description, are comprehended those which are formed, by evolving the circumferences of circles, for it is demonstrable, that these involutes are epicycloids, the centres of whose generating circles are infinitely distant.

the arch $a\,c$ to $m\,m''$; for, when the part $b\,m'$, of the epicycloid $m'\,n'$, is forming, every point of the arch $a\,b$ is applied to every point of the arch $m\,m'$; and the same may be said of the arch $a\,c$. Since, then, the wheels B and A, that is, the power and the weight, move through equal spaces, in equal times, equal weights acting in opposite directions, at the points a and m, will be in equilibrio: but, as the power of the wheel B must always be greater than the resistance of the wheel A, which is put in motion, this power will, during the whole of the action, have the same relation to the resistance which it overcomes, and the one wheel will impel the other with an uniform force and velocity.

This property of the epicycloid discovered by Roemer.

For the discovery of this property of the epicycloid, which Dr. Robison erroneously ascribes to De la Hire, or Dr. Hook, we are indebted to the Danish astronomer *Olaus Roemer*, the discoverer of the progressive motion of light; and Wolfius, upon whose authority this fact is stated,[7] laments, that the mechanics of his time did not avail themselves of the discovery.

In order to insure an uniformity of pressure and velocity, in the action of one wheel upon another, it is not necessary that the teeth, either of one or both wheels be exactly epicycloids.

---

[7] Ex eodem fonte *Olaus Romerus*, cum Parisiis commoraretur; quamvis non sine subsidio Geometriæ sublimioris, deduxit figuram dentium in rotis epicycloidalem esse debere: id quod post eum quoque ostendit *Philippus de la Hire*: sed quod dolendum hactenus in praxin recepta non est. Wolfii Opera Mathemat. tom. i, p. 684. The same fact is stated by Leibnitz, in the Miscellan. Berolinens. 1710, p. 315.

If the teeth of one of them be either circular, or triangular, with plain sides, or like a triangle, with its sides converging to the wheels' centre, or, indeed, of any other form, this uniformity of force and motion will be attained, provided that the teeth of the other wheel have a figure which is compounded of that of an epicycloid and the figure of the teeth of the first wheel.[8] But, as it is often difficult to describe this compound curve, and sometimes impossible to discover its nature, we shall endeavour to select such a form for the teeth as may be easily described by the practical mechanic, while it ensures an uniformity of pressure and velocity. But, in order to avoid circumlocution and obscurity, we shall call the small wheel, (which is supposed always to be driven by a greater one), the *pinion*, and its teeth the *leaves* of the pinion. The line, which joins the centres of the wheel and pinion, is called the *line of centres*.—Now there are three different ways, in which the teeth of one wheel may act upon the teeth of another; and each of these modes of action requires a different form for the teeth.

Different modes, in which one wheel may act upon another.

I. When the teeth of the wheel begin to act upon the leaves of the pinion, just as they arrive at the line of centres; and when their mutual action is carried on after they have passed this line.

II. When the teeth of the wheel begin to act upon the leaves of the pinion, before they

[8] M. de la Hire has shewn, in a variety of cases, how to find this compound curve.

arrive at the line of centres, and conduct them either to this line or a very little beyond it.

III. When the teeth of the wheel begin to act upon the leaves of the pinion, before they arrive at the line of the centres, and continue to act after they have passed this line.

First mode of action.

I. The first of these modes of action is recommended by Camus and De la Hire, the latter of whom has investigated the form of the teeth solely for this particular case. It is represented, in Fig. 2, where *B* is the centre of the wheel, *A* the centre of the pinion, and *AB* the line of centres. It is evident, from the figure, that the part *b* of the tooth *a b* of the wheel, does not begin to act on the leave *m* of the pinion, till they arrive at the line of centres *AB*; and that all the action is carried on after they have passed this line, and is completed when the leaf *m* comes into the situation *n*.[4] When this mode of action is adopted, the acting faces of the leaves of the pinion should be parts of an *interior epicycloid* generated by a circle, of any diameter, rolling upon the concave superfices of the pinion, or within the circle *a d h*; and the acting faces *a b* of the teeth of the wheel should be portions of an *exterior epicycloid*, formed by the *same* generating circle, rolling upon the convex superfices *o d p* of the wheel.

Plate II, Fig. 2.

Now, it it is demonstrable, that when one circle rolls within another, whose diameter is

[4] The tooth *c*, in the Figure, should have been in contact with the leaf *n*, and on the point of quitting it.

double that of the rolling circle, the line generated, by any point of the latter, will be a *straight line*, tending to the centre of the larger circle. If the generating circle, therefore, mentioned above, should be taken, with its diameter, equal to the radius of the pinion, and be made to roll upon the concave superficies *m b h* of the pinion, it will generate a straight line, tending to the pinion's centre, which will be the form of the acting faces of its leaves, and the teeth of the wheel will, in this case, be exterior epicycloids, formed by a generating circle, whose diameter is equal to the radius of the pinion, rolling upon the convex superfices *o d p* of the wheel. This form of the teeth, viz. when the acting faces of the pinion's leaves are right lines, tending to its centre, is exhibited, in Fig. 3, and is, perhaps, the most advantageous, as it requires less trouble, and may be executed with greater accuracy than if the curvilineal form had been employed. It is recommended, both by De la Hire and Camus, as particularly advantageous in clock and watch work.

A straight line may be generated epicycloidally.

Fig. 3.

The attentive reader will perceive, from Fig. 2, that, in order to prevent the teeth of the wheel from acting upon the leaves of the pinion, before they reach the line of centres *AB*; and that one tooth of the wheel may not quit the leaf of the pinion, till the succeeding tooth begins to act upon the succeeding leaf, there must be a certain proportion between the number of leaves in the pinion, and the number of teeth in the wheel; or between the radius of the pinion, and the radius of the wheel, when the distance of the leaves *AB* is given. But, in machinery, the number of leaves and teeth is always known, from the velocity, which is required at the work-

Fig. 2.

ing point of the machine. It becomes a matter, therefore, of great importance, to determine, with accuracy, the relative radii of the wheel and pinion.[9]

Relative diameters of the wheel and pinion.

For this purpose, let *A*, Fig. 3, be the pinion, having the acting faces of its leaves straight lines, tending to the centre, and *B* the centre of the wheel, *AB* will be the distance of their centres. Then, as the tooth *C* is supposed not to act upon the leaf *Am*, till it arrives at the line *AB*, it ought not to quit *Am*, till the following teeth *F* has reached the line *AB*. But, since the tooth always acts in the direction of a line drawn perpendicular to the face of the leaf *Am*, from the point of contact, the line *CH*, drawn at right angles to the face of the leaf *Am*, will determine the extremity of the tooth *CD*, or the last part of it, which should act upon the leaf *Am*, and will also mark out *CD*, for the depth of the tooth. Now, in order to find *AH*, *HB*, and *CD*, put *a* for the number of teeth in the wheel, *b* for the number of leaves in the pinion, *c* for the distance of the pivots *A* and *B*, and let *x* represent the radius of the wheel, and *y* that of the pinion. Then, since the circumference of the wheel is to the circumference of the pinion, as the number of teeth in the one to the number of leaves in the other, and as the circumferences of circles are proportional to their radii, we shall have $a : b = x : y$, then, by composition, (Eucl. v. 18), $a+b : b = c : y$, (c being equal to $x+y$), and,

[9] A very ingenious Proportion-compass has been invented, by M. le Cerf, watchmaker, at Geneva, for finding the relative diameters of wheels and pinions. It is described at length in the Phil. Trans. v. 68, p. 950.

consequently, the radius of the pinion, viz. $y=\frac{c\,b}{a+b}$; then, by inverting the first analogy, we have $b:a=y:x$, and, consequently, the radius of the wheel, viz. $x=\frac{a\,y}{b}$, y being now a known number.

Now, in the triangle AHC, right angled at C, the side AH is known, and likewise all the angles (HAC being equal to $\frac{360}{b}$) the side AC, therefore, can be easily found by plain trigonometry. Then, in the oblique angled triangle ACB, the angle CAB, equal to HAC, is known, and also the two sides AB, AC, which contain it; the third side, therefore, viz. CB, may be determined; from which DB, equal to HB, already found, being subtracted, there will remain CD for the depth of the teeth. When the action is carried on after the line of centres, it often happens that the teeth will not work in the hollows of the leaves. In order to prevent this, the angle CBH must always be greater than half the angle HBP. The angle HBP is equal to 360 degrees, divided by the number of teeth in the wheel, and CBH is easily found by plain trigonometry. (See p. 228.)

Teeth of lanterns or trundles.

Instead of pinions or small wheels, the millwrights in this country frequently substitute lanterns or trundles, which consist of cylindrical staves, fixed at both ends into two round pieces of board. From the use of trundles, however, Dr. Robison discourages the practical mechanic, when he observes, 'that De la Hire justly condemned the common practice of making the small wheel or pinion in the form of a lantern,' and that, when 'the teeth of the large

'wheel take a deep hold of the cylindrical pins 'of the trundle, the line of action is so disad- 'vantageously placed that the one wheel has 'scarcely any tendency to turn the other.'[5] It is with the greatest deference to such an able philosopher as Dr. Robison, that we presume to contradict this statement, both with respect to the fact which is asserted, and the principle which is maintained. In no part of De la Hire's Dissertation upon this subject does he condemn the use of lanterns. On the contrary, he actually *demonstrates*, that when the teeth of the great wheel are formed in a particular manner, and drive a small wheel whose teeth are cylindrical pins, the pressure and angular velocity of the one wheel will be equal to the pressure and angular velocity of the other; or, in other words, their action will be uniform. To this form of the teeth of the great wheel, when those of the small wheel are cylindrical, we shall now direct the reader's attention; and we earnestly recommend it to the notice of the practical mechanic, because it furnishes us with a method of removing, or at least of greatly diminishing, the friction which arises from the mutual action of the teeth.

Method of drawing a curve parallel to an epicycloid. PLATE II, Fig. 4.

Let *A*, Fig. 4, be the centre of the pinion or small wheel *TCH*, whose teeth are circular like *ICR*, having their centres in the circle *PDE*. Upon *B*, the centre of the large wheel, at the distances *BC*, *BD*, describe the circles *FCK*, *GDO*; and with *PDE*, as a generating circle, form the exterior epicycloid *DNM*, by rolling it upon the convex superficies of the circle *GDO*. The epicycloid *DNM* thus formed,

[5] The same observation is made in Imison's Elements of Science and Art.—Vol. i. p. 91.

would have been the proper form for the teeth of the large wheel GDO, had the circular teeth of the small wheel been infinitely small; but as their diameter must be considerable, the teeth of the wheel should have another form. In order to determine their proper figure, divide the epicycloid DNM into a number of equal parts, 1, 2, 3, 4, &c. as shewn in the figure, and let these divisions be as small as possible. Then, upon the points 1, 2, 3, &c. as centres, with the distance DC, equal to the radius of the circular tooth, describe portions of circles similar to those in the figure; and the curve OPT, which touches these circles, and is parallel to the epicycloid DNM, will be the proper form for the teeth of the large wheel.

In order that the teeth may not act upon each other till they reach the line of centres AB, the curve OP should not touch the circular tooth ICR till the point O has arrived at D. The tooth OP, therefore, will commence its action upon the circular tooth at the point I, where it is cut by the circle DRE. On this account, the part ICR of the cylindrical pin being superfluous, may be cut off, and the teeth of the small wheel will be segments of circles similar to the shaded parts of the figure. But if the spindles remain entire, the vacuities between the teeth should be cut out, and their sides OK directed to the centre of the wheel.

If the teeth of wheels and the leaves of pinions be formed according to the directions already given, they will act upon each other, not only with uniform force, but also with very little friction. The one tooth rolls upon the other, and neither slides nor rubs to such a degree as to retard the wheels, or wear their teeth. But as it is impossible in practice to give that perfect

Very little friction between the teeth when properly shaped.

curvature to the acting faces of the teeth which theory requires, a certain quantity of friction will remain after every precaution has been taken in the formation of the communicating parts. This friction may be removed, or at least greatly diminished, by the following contrivance.

If, instead of fixing the circular teeth, as in Fig. 4, to the wheel *DRE*, they are made to move upon axles or spindles fixed in the circumference of the wheel, all the friction will be taken away, except that which arises from the motion of the cylindrical tooth upon its axis. The advantages which attend this mode of construction are many and obvious. The cylindrical teeth may be formed by a turning lathe with the greatest accuracy; the curve required for the teeth of the large wheel is easily traced; the pressure and motion of the wheels will be uniform; and the teeth are not subject to wear, because whatever friction remains is almost wholly removed by the revolution of the cylindrical spokes about their axis. The reader will also observe, that this improvement may be most easily introduced when the small wheel has the form of a trundle or lantern; and that it may be adopted in cases where lanterns could not be conveniently used.

Cylindrical teeth moving on their axes.

PLATE III, Fig. 3. In Fig. 3, is represented the manner by which cylindrical teeth, moveable upon their axis, may be inserted in the circumference of wheels. *B* is the part of the wheel on which the tooth is to be fixed; *A* is the cylindrical tooth which moves upon its axis *b c* made of iron, whose extremities run in bushes of brass, fixed in the projecting pieces of wood *b*, *c*. This improvement, however, can only be adopted where the machinery is large. For small works, the teeth of the pinion or small wheel should be rectilineal, and those of the large wheel epicycloidal.

II. Having hitherto supposed, that the mutual action of the teeth does not commence till they arrive at the line of centres, let us now attend to the form which must be given them, when the whole of the action is carried on before they reach the line of centres, or when it is completed a very little below this line. This mode of action is not so advantageous as that which we have been considering, and should, if possible, always be avoided. It is represented in Fig. 1, where *A* is the centre of the pinion, *B* that of the wheel, and *AB* the line of centres. It is evident from the figure, that the tooth *C* of the wheel acts upon the leaf *D* of the pinion before they arrive at the line *BA*; that it quits the leaf when they reach this line, and have assumed the position of *E* and *F*; and that the tooth *c* works deeper and deeper between the leaves of the pinion the nearer it comes to the line of centres. From this last circumstance a considerable quantity of friction arises, because the tooth *C* does not, as before, roll upon the leaf *D*, but slides upon it; and from the same cause the pinion soon becomes foul, as the dust which lies upon the acting faces of the leaves is pushed into the hollows between them. One advantage, however, attends this mode of action, for it allows us to make the teeth of the large wheel rectilineal, and thus renders the labour of the mechanic less, and the accuracy of his work greater, than if they had been of a curvilineal form. If the teeth *C*, *E*, therefore, of the wheel *BC* are made rectilineal, having their surfaces directed to the wheel's centre, the acting faces of the leaves *D*, *F*, &c. must be epicycloids formed by a generating circle, whose diameter is equal to the radius *Bo* of the circle *op*, roll-

Second mode of action.

PLATE III, Fig. 1.

ing upon the circumference $m\,n$ of the pinion A. But if the teeth of the wheel and the leaves of the pinion are made curvilineal, as in the figure, the acting faces of the teeth of the wheel must be portions of an interior epicycloid formed by any generating circle rolling within the concave superficies of the circle $o\,p$, and the acting faces of the pinion's leaves must be portions of an exterior epicycloid, produced by rolling the same generating circle upon the convex circumference $m\,n$ of the pinion.

When the teeth of the large wheel are cylindrical spindles, either fixed or moveable upon their axis, an exterior epicycloid must be formed, like $D\,N\,M$, in Fig. 4, by a generating circle whose radius is $A\,C$, rolling upon the convex circumference $F\,C\,K$, $A\,C$ being in this case the diameter of the wheel, and $F\,C\,K$ the circumference of the pinion. By means of this epicycloid a curve $O\,P\,T$ must be formed as before described, which will be the proper curvature for the acting faces of the leaves of the pinion, when the teeth of the wheel are cylindrical, though, when this is the case, this mode of action ought to be avoided.

Plate II, Fig. 4.

The relative diameter of the wheel and pinion, when the number of teeth in each is known, may be found by the same formulæ which were given for the first mode of action, with this difference only, that in this case the radius of the wheel is reckoned from its centre to the extremity of its teeth, and the radius of the pinion from its centre to the bottom of its leaves.

Third mode of action.

III. The third way in which one wheel may drive another, is when the action is partly carried on before the acting teeth arrive at the line of centres, and partly after they have passed this line.

This mode of action, which is represented in

Fig. 2, is a combination of the two first modes, and consequently partakes of the advantages and disadvantages of each. It is evident from the figure, that the portion *e h* of the tooth acts upon the part *b c* of the leaf till they reach the line of centres *A B*, and that the part *e d* of the tooth acts upon the portion *b a* of the leaf after they have passed this line. It follows, therefore, that the acting parts *e h* and *b c* must be formed according to the directions given for the first mode of action, and that the remaining parts *e d*, *b a*, must have that curvature which the second mode of action requires; consequently *e h* should be part of an interior epicycloid formed by any generating circle rolling on the concave circumference *m n* of the wheel, and the corresponding part *b c* of the leaf should be part of an exterior epicycloid formed by the same generating circle rolling upon *b E O*, the convex circumference of the pinion: the remaining part *c d* of the tooth should be a portion of an exterior epicycloid, engendered by any generating circle rolling upon *e L*, the concave superficies of the wheel; and the corresponding part *b a* of the leaf should be part of an interior epicycloid described by the same generating circle, rolling along the concave side *b E O* of the pinion.—As it would be extremely troublesome, however, to give this double curvature to the acting faces of the teeth, it will be proper to use a generating circle, whose diameter is equal to the radius of the wheel *B C*, for describing the interior epicycloid *e h* and the exterior one *b c*, and a generating circle, whose diameter is equal to *A C*, the radius of the pinion, for describing the interior epicycloid *b a*, and the exterior one *e d*. In this case the two interior epicycloids *e h*, *b a*, will be

PLATE III. Fig. 2.

straight lines tending to the centres B and A,[1] and the labour of the mechanic will by this means be greatly abridged.

Relative diameters of the wheel and pinion.

In order to find the relative diameters of the wheel and pinion, when the number of teeth in the one and the number of leaves in the other are given, and when the distance of their centres is also given, and the ratio of ES to CS,[2] let a be the number of teeth in the wheel, b the number of leaves in the pinion, c the distance of the pivots A, B, and let m be to n as ES to CS, then the arch ES, or the angle SAE, will be equal to $\frac{360°}{b}$, and LD, or the angle LBD, will be equal to $\frac{360°}{a}$. But as $ES : CS = m : n$; consequently $LD : LC = m : n$, therefore (Eucl. 6, 16.) $LC \times m = LD \times n$, and $LC = \frac{LD \times n}{m}$ but LD is equal to $\frac{360}{a}$, therefore by substituting this in its stead, we have $LC = \frac{360 \times n}{a\,m}$.

Now, in the triangle APB, AB is known, and also PB, which is the cosine of the angle ABD, PC being perpendicular to DB, AP therefore, which is the radius of the pinion, may be found by plain trigonometry. The reader will observe, that the point P marks out the parts of the tooth D and the leaf SP where they commence their action; and the point I marks out the parts where their mutual action ceases; AP

---

[1] Traite des Epicycloides, par M. de la Hire. Prop. V.

[2] The letter L marks the intersection of the line BL with the arch em, and the letter E the intersection of the arch bO with the upper surface of the leaf m. The letters D and S correspond with L and E respectively, and P with I.

therefore is the proper radius of the pinion, and BI the proper radius of the wheel, the parts of the tooth L without the point I, and of the leaf SP without the point P being superfluous. Now, to find BI, we have $ES : CS = m : n$, consequently (Eucl. vi, 16) $CS \times m = ES \times n$, and $CS = \frac{ES \times n}{m}$; but ES was formerly shewn to be equal to $\frac{360}{b}$; therefore, by substitution, $CS = \frac{360 \times n}{bm}$. Now, the arch ES, or angle EAS, being equal to $\frac{360}{b}$, and CS, or the angle CAS, being equal to $\frac{360 \times n}{bm}$, their difference EC, or the angle EAC, will be equal to $\frac{360}{b} - \frac{360 \times n}{bm}$. By subtracting, we have $\frac{360\,mb - 360\,bn}{b\,b\,m}$, and dividing by b, gives $\frac{360\,m - 360\,n}{bm}$, or $\frac{360^{\circ} \times \overline{m-n}}{bm}$. The angle EAC being thus found, the triangle EAB, or IAB, which is almost equal to it, is known, because AB is given; and likewise AI, which is equal to the cosine of the angle IAB, AC being radius, and AIC being a right angle; consequently IB the radius of the wheel may be found by trigonometry. It was formerly shewn,[1] that AC, the radius of what is called the primitive pinion, was equal to $\frac{cb}{a+b}$, and that BC, the radius of the primitive wheel, was equal to $\frac{AC \times a}{b}$. If, then, we subtract AC or AS from AP, we shall have the quantity SP, which must be added to the radius of the primitive pinion; and if we take the

[1] See page 217.

difference of BC (or BL) and DE, the quantity LE will be found, which must be added to the radius of the primitive wheel. We have all along supposed that the wheel drives the pinion, and have given the proper form of the teeth upon this supposition. But when the pinion drives the wheel, the form which was given to the teeth of the wheel, in the first case, must in this be given to the leaves of the pinion; and the shape which was formerly given to the leaves of the pinion must now be transferred to the teeth of the wheel.

Form of the teeth, according to Dr. Robison.

Another form for the teeth of wheels, different from any which we have mentioned, has been recommended by Dr. Robison. He shews that a perfect uniformity of action may be secured, by making the acting faces of the teeth involutes of the wheel's circumference. Thus, in Plate IV, Fig. 1, let AB be a portion of the wheel on which the tooth is to be fixed, and let Apa be a thread lapped round its circumference, having a loop hole at its extremity a. In this loop hole fix the pin a, and with it describe the curve or *involute* $abcdeh$, by unlapping the thread gradually from the circumference Apm. This curve will be the proper form for the teeth of a wheel, whose diameter is AB. Dr. Robison observes, that as this form admits of several teeth to be acting at the same time, (twice the number that can be admitted in M. de la Hire's method), the pressure is divided among several teeth, and the quantity upon any one of them is so diminished, that those dints and impressions, which they unavoidably make upon each other, are partly prevented. He candidly allows, however, that the teeth thus formed are not altogether free from sliding and friction, but that this slide is so insignificant as

PLATE IV, Fig. 1.

to amount only to $\frac{1}{60}$ of an inch, when a tooth three inches long, fixed on a wheel ten feet in diameter, acts upon the teeth of another wheel whose diameter is two feet.

It may be proper to observe, that this form of the teeth which Dr. Robison recommends is not new. It is only a modification of the general principle of De la Hire, 'that no curve is proper 'for the teeth of wheels, unless it be epicycloidal,' *i. e.* generated after the manner of an epicycloid. A straight line can be generated by an epicycloidal motion; and the involute *a b c*, &c. is actually an *exterior epicycloid*,[4] whose base is *A p m B*, and the centre of whose generating circle is infinitely distant. The involute *a b c d*, &c. may also be produced by an epicycloidal motion; for, since the circumference of a generating circle, whose centre is infinitely distant, must be a straight line, we may form the involute *a b c*, by making a straight ruler roll upon the circumference of the circle to be evolved. In Fig. 1, let *o n* be a straight ruler at whose extremity is fixed the pin *n*, and let the point of the pin be placed upon the point *m* of the circle, then by rolling the straight ruler upon the circular base, so that the point in which it touches the circle may move gradually from *m* towards *B*, the curve *m n* will be generated exactly similar to the involute *a b c*, &c. This, by the by, is perhaps an easier and more accurate method of generating involutes than by unlapping a thread from the circumference of the *evolute* or circle to be evolved.

Mechanical method of describing involutes.

[4] De la Hire calls involutes the last of the exterior epicycloids.

From what has been said in page 217, the reader will perceive, that when the pinion has a small number of leaves, the first mode of action cannot be employed. By computing the angles *H B C*, *H B P*, Plate II, Fig. 3, trigonometrically, it will be found that a pinion of seven leaves cannot be impelled uniformly by a wheel of fifty teeth, when the action is carried on after the line of centres; for even if the leaves had no breadth like a mathematical line, then there would be no room left for the play of the teeth. However great indeed be the number of teeth in a wheel, the space between them would not be sufficiently great to receive a leaf of a reasonable thickness, and to leave at the same time a sufficient space for the play of the teeth. The same may be said of a pinion of 8 leaves driven by a wheel of 57 teeth and upwards, and of a pinion of 9 leaves driven by a wheel of 64[4] teeth and upwards. When a pinion therefore of 7, 8, or 9 leaves are to be impelled by a wheel, the action of the teeth upon the leaves must commence before they have reached the lines of centres, and be continued after they have passed that line. If the pinion has *ten* leaves, it may be moved uniformly by a wheel of 72 teeth, by the first mode of action; but if the vacuity between the teeth is equal to, or greater than the teeth themselves, the leaves of the pinion must be caught by the teeth a little before they reach the line of centre.[5]

Plate II Fig. 3.

---

[4] The number of teeth here specified are those beneath which it would be impossible for the action to be carried on. When the wheel has a greater number, there is no impossibility in the case; but the teeth would be too slender to resist the strains to which they are exposed.

[5] See Camus's Cours de Mathematique, § 550.

Thus have we endeavoured to lay before our readers all the information which we have upon this important subject; and we trust it will be candily received, as it is the only essay on the subject which has appeared in our language.[6] The demonstrations of the propositions have been purposely left out, as being rather foreign to the object of a practical work. To the mechanic, they are of no consequence; and the mathema-

---

[6] In a book entitled, *Imison's Elements of Science and Art*, which professes to be a second edition of *Imison's School of Arts*, there are some practical directions for the formation of the teeth of wheels. but they are so defective in principle that they cannot be trusted. The author seems merely to have heard that the acting faces of the teeth should be epicycloidal, but to have been totally ignorant whether the epicycloids should be exterior or interior, and what should be their bases and generating circles. The directions which this author gives for forming the teeth of a rack, and the lifting cogs or cams of forge hammers, are equally destitute of scientific principle.

*** The preceding note, which was published in the first edition of this work, has called forth a reply from the author of the article in Imison's Elements, on which I had animadverted. This reply was published in a translation of one of Camus's Essays on the teeth of wheels, and was written by a Mr. Thomas Gill in London. This gentleman insists, that the rules which he has given in Imison's elements are correct, because they have been found to answer in practice; though it is demonstrable, and evident to every person who understands the subject, that the generating circles with which he describes his epicycloids, are *twice as large* as they ought to be. The same gentleman has thought proper to say, that the preceding article on the teeth of wheels is defective, in *not* containing that method of forming the teeth in which the acting faces are partly radii, and partly epicycloids; while *this very method* is not only *given*, but *recommended*, to the notice of the practical mechanic! (See page 223, line 11 from bottom). I shall forbear making any animadversions on this new mode of literary assault. I willingly commit the subject to the judgment of every intelligent reader.

tician can either demonstrate them himself, or have recourse to the original dissertations of Camus and De la Hire.

On the Nature of BEVELLED WHEELS, *and the method of giving an epicycloidal form to their Teeth.*

Nature of bevelled wheels.

The principle of bevelled wheels was pointed out by De la Hire, so long ago as the end of the seventeenth century.[7] It consists in one fluted or toothed cone acting upon another, as represented in Figure 8, of Plate XII, where the cone $O\,D$ drives the cone $O\,C$, conveying its motion in the direction $O\,C$. If these cones be cut parallel to their bases as at A and B, and if the two small cones between $A\,B$ and O be removed, the remaining parts $A\,C$ and $B\,D$ may be considered as two bevelled wheels, and $B\,D$ will act upon $A\,C$ in the very same manner, and with the same effect that the whole cone $O\,D$ acted upon the whole cone $O\,C$; and if the section be made nearer the bases of the cones, the same effect will be produced. This is the case in Figure 9, where $C\,D$ and $D\,E$ are but very small portions of the imaginary cones $A\,C\,D$ and $A\,D\,E$.

PLATE XII, Fig. 8.

Fig. 9.

In order to convey motion in any given direction, and determine the relative size and situation of the wheels for this purpose, let $A\,B$, Fig. 10, be the axis of a wheel, and $C\,D$ the given direction in which it is required to convey the motion by means of a wheel fixed upon the axis $A\,B$, and acting upon another wheel fixed on the axis $C\,D$, and let us suppose that the axis $C\,D$ must have four times the velocity of $A\,B$,

Fig. 10.

[7] Traite de Mecanique, prop. 66, published in the Mem. de l'Acad. Paris, &c. depuis 1666, jusqûa 1699, tom. ix.

or must perform four revolutions while AB performs one;—then the number of teeth in the wheel fixed upon AB must be four times greater than the number of teeth in the wheel fixed upon CD, and their radii must have the same proportion. Draw cd parallel to CD at any convenient distance, and draw ab parallel to AB at four times that distance, then the lines im and in drawn perpendicular to AB and CD respectively, will mark the situation and size of the wheels required. In this case the cones are Oni and Omi, and $srni$, $rpmi$, are the portions of them that are employed. The operation here indicated, is evidently nothing more than the common problem of dividing a given angle BOD into two parts, whose sines shall be to one another as the number of revolutions of the one wheel, to the number of revolutions of the other. If $m : n$ as one of these numbers is to the other, the problem solved algebraically will give the following theorem. $2.\,\text{Sin.}\,\frac{BOD}{2} = 2\,\text{Sin.}\,\frac{Bor}{2} \times \frac{m}{m+n}$, which verifies the preceding construction.[8]

On the formation of their teeth.

The formation of the teeth of bevelled wheels is more difficult than one would at first imagine; and no author, so far as I know, has attempted to direct the labours of the mechanic. The teeth of such wheels, indeed, must be formed by the same rules which we have given for other wheels; but since different parts of the same tooth are at different distances from the axis, these parts must have the curvature of their acting surfaces proportioned to that distance. Thus, in Fig. 9, the part of the tooth at i must be

[8] See Gregory's Mechanics, vol. ii, p. 7, and Simpson's Select Exercises, p. 138.

more incurvated than the part at *C*, as is evident from the inspection of Fig. 8, and the epicycloid for the part *i* Fig. 9. must be formed by means of circles whose diameters are *i m* and *F f*, while the epicycloid for the part *r* must be generated by circles, whose diameters are *C n* and *D d*.

Let us suppose a plane to pass through the points *O A B*; the lines *A B*, *A O*, will evidently be in this plane, which may be called the *Plane of Centres*. Now, when the teeth of the wheel *D E*, which is supposed to drive *C D*, the smallest of the two, commence their action on the teeth of *C D*, as soon as they arrive at the plane of centres, and continue their action after they have passed this plane, the curve given to the teeth of *C D* at *C* should be a portion of an interior epicycloid formed by any generating circle rolling on the concave superficies of a circle whose diameter is twice *C n*, which is perpendicular to *C A*, and the curvature of the teeth at *i* should be part of a similar epicycloid, formed upon a circle, whose diameter is twice *i m*. The curvature of the teeth of the wheel *D E* at *D* should be part of an exterior epicycloid formed by the same generating circle rolling upon the concave circumference of a circle whose diameter is twice *D d*, perpendicular to *D A*; and the epicycloid for the teeth at *F* is formed in the same way, only instead of twice *D d*, the diameter of the circle must be twice *F f*. When any other mode of action is adopted, the teeth are to be formed in the same manner that we have pointed out for common wheels, with this difference only, that different epicycloids are necessary for the parts *F* and *D*. It may be sufficient, however, to find the form of the teeth at *F*, as the remaining part of the tooth may be shaped by directing a straight rule from different

points of the epicycloid at F to the centre A, and filing the tooth till every part of its acting surface coincides with the side of the ruler. The reason of this operation will be obvious by attending to the shape of the tooth in Fig. 8. When the small wheel CD impels the large one DE, the epicycloids which were formerly given to CD must be given to DE, and those which were given to DE must be transferred to CD.[1] Fig. 8.

The wheel represented in Fig. 5, Plate XIII, is sometimes called a crown wheel, though it is evident from the figure, that it belongs to that species of wheels which we have just been considering; for the acting surfaces of the teeth both of the wheel MB, and of the pinion EDG, are directed to C, the common vertex of the two cones CMB, CEG. In this case, the rules for bevelled wheels must be adopted, in which AS is to be considered as the radius of the wheel for the profile of the tooth at A, and MN as its radius for the profile of the tooth at M; and the epicycloids thus formed, will be the sections or profiles of the teeth in the direction MP, at right angles to MC, the surface of the cone. When the vertex C of the cone MCG approaches to N till it be in the same plane with the points M, G, some of the curves will be cycloids, and others involutes, as in the case of rackwork mentioned in page 242; for then the cone CEG will revolve upon a plane surface. On crown wheel. Plate XIII, Fig. 5.

[1] A method of bevelling wheels with a simple instrument, invented by Mr. James Kelly of New Lanark cotton-mills, may be seen in the Repertory of Arts, vol. vi, p. 106. This instrument, founded on the equality of vertical angles, is so very simple that it must have occurred to mechanics of common ingenuity.

On the Formation of Exterior and Interior Epicycloids, and on the Disposition of the Teeth on the Wheel's Circumference.

Mechanical method of forming epicycloids.

Nothing can be of greater importance to the practical mechanic, than to have a method of drawing epicycloids with facility and accuracy; the following, we trust, is the most simple mechanical method that has yet been devised.—

Plate IV, Fig. 2.

Take a piece of plain wood *G H*, Fig. 2, and fix upon it another piece of wood *E*, having its circumference *m b* of the same curvature as the circular base upon which the generating circle *A B* is to roll: when the generating circle is large, the shaded segment *B* will be sufficient. In any part of the circumference of this segment, fix a sharp pointed nail *a*, sloping in such a manner that the distance of its point from the centre of the circle may be exactly equal to its radius; and fasten to the board *G H* a piece of thin brass, or copper, or tinplate *a b*, distinguished by the dotted lines. Place the segment *B* in such a position that the point of the nail *a* may be upon the point *b*, and roll the segment towards *G*, so that the nail *a* may rise gradually, and the point of contact between the two circular segments may advance towards *m*; the curve *a b* described upon the brass plate will be an accurate exterior epicycloid. In order to prevent the segments from sliding, their peripheries should be rubbed with rosin or chalk; or a number of small iron points may be fixed in the circumference of the generating segment. Remove, with a file, the part of the brass on the left hand of the epicycloid, and the remaining concave arch or gage *a b* will be a pattern tooth, by means of which all the rest may be easily formed. When an *interior epicycloid* is

wanted, the concave side of its circular base must be used. The method of describing it is represented in Figure 3, where *C D* is the generating circle, *F* the concave circular base, *M N* the piece of wood on which this base is fixed, and *c d* the interior epicycloid formed upon the plate of brass, by rolling the generating circle *C*, or the generating segment *D*, towards the right hand. The *cycloid*, which is useful in forming the teeth of *rack work*, is generated precisely in the same manner, with this difference only, that the base on which the generating circle rolls must be a straight line. Fig. 3.

Although, in general, it is necessary to give the proper curvature only to one side of the teeth, yet it may be proper to form both sides with equal care, that the wheels may be able to move in a retrograde direction. This is particularly necessary when a reciprocating power is employed. In the case of a mill moving by the force of a single-stroke steam engine, the direction of the pressure on the communicating parts of the machinery is changed twice every stroke. During the working stroke, the teeth of the wheels which convey the motion from the beam to the machinery are acting with one side of their teeth, but during the returning stroke the wheels act with the other side of their teeth.[a] Both sides of the teeth should be properly shaped.

In order that the teeth may not embarrass one another before their action commences, and that one tooth may begin to act upon its corresponding leaf of the pinion, before the preceding tooth has ceased to act upon the preceding leaf, the height, breadth, and distance, of the teeth must be properly proportioned. For this pur-

[a] See Dr. Robison's Treatise on *Machinery* in the Supplement to the Encyclopædia Britannica, v. ii, p. 104, § 38.

pose the pitch line or circumference of the wheel
PLATE III, Fig. 2 & 3. which is represented in Figures 2 and 3, by the dotted arches, must be divided into as many equal spaces as the number of teeth which the wheel is to carry. Divide each of these spaces into 16 equal parts; allow 7 of these for the greatest breadth of the tooth, and 9 for the distance between each, or the distance of the teeth may be made equal to their breadth. If the wheel drives a trundle, each space should be divided into 7 equal parts, and 3 of these allotted for the thickness of the tooth, and $3\frac{2}{3}$ for the diameter of the cylindrical stave of the trundle.[3] If each of the spaces already mentioned, or if the distance between the centres of each tooth, be divided into 3 equal parts, the height of the teeth must be equal to 2 of these.[4] These distances and heights, however, vary according to the mode of action which is employed.[5] The teeth should be rounded off at the extremities, and the radius of the wheel made a little larger than that which is deduced from the rules in pages 217 and 224. But when the pinion drives the wheel, a small addition should be made to the radius of the pinion.

On the Formation of Cycloids and Epicycloids by Means of Points, and the Method of drawing Lines parallel to them.

Method of forming epicycloids by means of points. As the preceding mechanical method of forming epicycloidal curves may be regarded by some

[3] Imison allows 3 parts for the thickness of the tooth, and 4 for the diameter of the stave. But it is evident that in this case the staves of the wallower would stick between the teeth of the wheel.

[4] Some make the height of the teeth almost equal to the distance between the centres of each, but this can be determined only by the method formerly stated. See p. 225.

[5] See Wolfii Opera Mathematica, tom. i, pp. 696-7.

as too difficult in practice, and too liable to error, we shall point out a method of describing epicycloids by means of points, and a more accurate way of drawing lines parallel to them than that which is described in the preceding pages, and represented in Figure 4 of Plate II.

Let the radius $A\,B$, Fig. 5, Plate III, of the large wheel be called a, and the radius $B\,C$ of the lesser one, or generating circle, be called b, and let the variable quantity x be equal to $\frac{a}{b} \times z$, z being any number of degrees taken at pleasure, and equal to the variable angle $B\,A\,O$. Then having drawn the chord $B\,O$ we will have $A\,B\,O$, or $A\,O\,B = 90° - \frac{z}{2}$; the chord $B\,O = 2a \times$ sin. $\frac{z}{2}$; and $A\,O\,D = 90° + \frac{x}{2}$. Whence $B\,O\,D = \frac{x+z}{2}$; and $O\,D = 2\,b \times$ sin. $\frac{x}{2}$. The line $O\,D$ being thus determined, we have one point D of the epicycloid $B\,D$. If the angle $B\,A\,O$, or the variable quantity z be gradually diminished, and $O\,D$ determined anew, we shall have other points of the epicycloid between D and B: or if z be increased, other points of the epicycloid beyond D will be determined. Since a very small arch of any curve may be represented by the arch of a circle equicurve to it in the same point, we may describe a small portion of the epicycloid at D with a radius equal to $\frac{a+b}{a+2b} \times 2\,O\,D$. This radius being reckoned from D, on the line $D\,O$, which is perpendicular to the epicycloid at D, will give the centre from which the elementary arc at D may de described. In finding the different points D, d of the epicycloid $B\,D$, we de-

PLATE III. Fig. 5.

termine at the same time the lines $D\,O$, $d\,O$ perpendicular to the epicycloid in the respective points D, d; hence it will be an easy matter to draw a curve parallel to the epicycloid $B\,D$ at any given distance. Thus let M be the given distance, then take the line M in the compasses, and set it from D to F on the perpendicular $D\,F$, and also from d to f, on $d\,f$, and so on for the other points. A number of points F, f, &c. will therefore be determined, through which we can describe the curve $E\,f\,F\,G$, which will be parallel to the epicycloid $B\,D$, and distant from it by the given quantity M.

In order to illustrate this method by an example, let $A\,B$, the radius of the large wheel, be 42.991 inches, and $BC=25.7946=AE\times 0.6$, then $a:b$ as 10 : 6. Let us suppose $z=12°$. Then $x=\frac{10}{6}\times 12$, or $x=20°$; consequently $\frac{z}{2}=60$; $B\,O\,D=16°$. Since $B\,O$ is equal to $2a\times$ sin. $\frac{z}{2}$ we shall have

Logarithm $2\,a=1.9344123$

Log. Sine $\frac{z}{2}$ or $6°=9.0192346$

Therefore $B\,O=8.9876$ $\quad 0.9536469$ Log.

In order to find $O\,D=2\,b\times$ sin. $\frac{z}{2}$ we have

Logarithm $2\,b=1.7125636$

Log. Sine $\frac{z}{2}$ or $10°=9.2396702$

Therefore $OD=8.9584$, $\quad 0.9522338$

The radius of curvature at the point D, consequently, will be $=\frac{16}{11}\times OD$, when $z=12°$,[6] that

[6] The radius of curvature being always $=\frac{a+b}{a+2b}\times 2OD$, it will be equal, in the present example, to $\frac{10+6}{10+12}\times 2OD$, or $\frac{16}{22}\times 2OD$, or $\frac{16}{11}\times OD$.

is, the radius of curvature will be 13.030. If z be successively diminished to 6°, 4°, and 2°, we shall have the results contained in the following table, which are found in the same way as when $z=12°$.

z	x	EBO	BOD	BO	OD	Radius of Curvature.
2°	3° 20′	1°	2° 40′	1.5006	1.5004	2.1824
	6 40	2	5 20	3.0007	2.9996	4.3631
6	10 0	3	8 0	4.5000	4.4962	6.5400
12	12 0	6	16 0	8.9876	8.9584	13.0300

By means of this table, four points of the epicycloid may be found. Make the angle $BAO=12°$, $BOD=16$, and $OD=8.9584$, which will determine the point D; and so on with the rest.

As it would be extremely difficult to project the wheels C and A upon paper, when they are very large, we shall shew how to describe the epicycloid without using the centres C and A. Draw BE perpendicular to the line CA that joins the centres of the wheels, and make the angle EBO equal to one half of z, viz. 6 degrees. Make BO, as before found, equal to 8.9876; the angle $BOD=16°$, and $OD=8.9584$, and the point D will be determined when the line CA is only given in position.

In the Cycloid let the line BO (Fig. 6, Plate III) be equal to $b \times z$, b being the radius of the generating circle c, and z any number of degrees taken at pleasure. Then $DO=2b \times \text{Sine}\frac{z}{2}$, and $DOB=\frac{z}{2}$. From D let fall the perpendicular DK, and let $DK=y$, and $BK=x$; then $Do \times \text{sine}\frac{z}{2}=DK$, or $y=2b \times \text{sine}\frac{z^2}{2}=b \times$ versed sine

PLATE III. Fig. 6.

$z=b \times \overline{1-\cos.\ z}$. Likewise we have $KO=2b \times \cos.\frac{z}{2} \times \sin\frac{z}{2}=b \times$ sine z. Whence BK, or $x=b \times \overline{z-\text{sine } z}$. Wherefore BK and DK being thus found, the point D in the cycloid will be determined; and by diminishing z continually, we shall then have other points of the cycloid between D and B, and by increasing it we shall have points beyond D.

Example. To illustrate this by an example, let $b=1$ and $z=120°=180°-60°$, then since $b=1$ we shall have $y=$ versed sine $120°=2-$ versed sine $60°=1.500$. To find x, which is $=b \times \overline{z-\text{sine } z}$, or, in the present case, $=z-$sine z, since b is equal to 1. The arch z, or 120°, being $\frac{1}{3}$ of the circumference of a circle whose radius is 1, and whose circumference is 3.1415927×2, or 6.2831854, will be equal to 2.0943950, and the sines of 120°, or its supplement 60°, is 0.8660254. Therefore

$$\begin{array}{r} 120°=2.0943951 \\ \text{sine } 120°=0.8660254 \\ \hline x=\ 1.2283697 \end{array}$$

If z be made 5°, x will be $=0.0001108$, and $y=0.0038053$. The numbers x and y being thus determined, we have only to make BK equal to x, and KD to y, in order to find the point D. It may be proper to observe, that the variable number z should be taken pretty small both for the cycloid and epicycloid, as it is only a little portion of these curves that is required for the teeth of wheels; and when several points of the curve are determined, the intervening space may be made arches of a circle equicurve to the epicycloid at the same point.[9]

---

[9] See Kæstner's Memoir *de Dentibus Rotarum*, in the Comment. Soc. Reg. Gotting. 1782, vol. v, pp. 9, 24.

MECHANICS.

ON THE FORMATION OF THE TEETH OF RACK-WORK, THE ARMS OF LEVERS, THE WIPERS OF STAMPERS, AND THE LIFTING COGS OR CAMS OF FORGE HAMMERS.

On the teeth of rackwork.

THE teeth of a wheel may act upon those of a rack, according to the three different ways in which one wheel acts upon another, and each of these modes of action requires a different form for the communicating parts.

From what has been said, in the preceding dissertation, it would be easy to deduce the proper form for the teeth of rackwork, merely by considering the rack as part of a wheel, whose centre is infinitely distant.[8] But, as the epicycloids are, in this case, converted into other curves, which have different names, and are generated in a different manner, it may be proper, for the sake of

[8] Since this article was written, I have seen a paper, by Kæstner, on the same subject, in the *Nov. Commentar. Soc. Reg. Gotting.* 1771, tom. ii, p. 117; but it contains nothing new, excepting a method of describing involutes, by means of points.

the practical mechanic, to add a few observations illustrative of this subject.

Plate IV, Fig. 4. In Fig. 4, let *AB* be the wheel, which is employed to elevate the rack *C*, and let their mutual action not commence till the acting teeth have reached the line of centres *AC*. In this case, *C* becomes, as it were, the pinion or wheel driven, and the acting faces of its teeth must be *interior epicycloids*, formed by any generating circle, rolling within the circumference *pq*; but as *pq* is a straight line, these interior epicycloids will be *cycloids*, or *trochoids*, as they are sometimes called, which are curves generated by a point in the circumference of a circle, rolling upon a straight line, or plane surface. The acting face *op*, therefore, will be part of a *cycloid*, formed by any generating circle, and *mn* the acting face of the teeth of the wheel, must be an *exterior* epicycloid, produced by the same generating circle, rolling on *mr* the convex surface of the wheel. If it is required to make *op* a straight line, as in the figure, then *mn* must be an *involute* of the circle *mr*, formed according to the manner represented in Fig. 1, Plate IV.

Figure 4 represents likewise a wheel depressing the rack *C* when the third mode of action is used, viz. when the action commences above the line of centres, and is carried on below this line. In this case also, *C* becomes the pinion, and *DE* the wheel; *eh*, therefore, must be part of an interior epicycloid, formed by any generating circle, rolling on the concave side *ex* of the wheel, and *bc* must be an exterior epicycloid, produced by the same generating circle, rolling upon the circumference of the rack. The remaining part *cd* of the teeth of the wheel must be an exterior epicycloid, described by any generating circle, mov-

ing upon the convex side *ex*, and *ba* must be an interior epicycloid, engendered by the same generating circle, rolling within the circumference of the rack. But, as the circumference of the rack is, in this case, a straight line, the exterior epicycloid *bc*, and the interior one *ba*, will be cycloids, formed by the same generating circles which are employed in describing the other epicycloids. Since it would be difficult, however, as has already been remarked, to give this compound curvature to the teeth of the wheel and rack, we may use a generating circle, whose diameter is equal to *Dx*, the radius of the whee, for describing the interior epicycloid *eh*, and the exterior one *bc*, and a generating circle, whose diameter is equal to the radius of the rack, for describing the interior epicycloid *ab*, and the exterior one *de; ab* and *eh*, therefore, will be straight lines, and *bc* will be a cycloid, and *de* an involute of the circle *ex*, the radius of the rack being infinitely great.

In the same manner may the form of the teeth of rackwork be determined, when the second mode of action is employed, and when the teeth of the wheel, or rack, are circular or rectilineal. But, if the rack be part of a circle, it must have the same form for its teeth, as that of a wheel of the same diameter with the circle, of which it is a part.

Importance of giving the proper form to wipers.

In machinery, where large weights are to be raised, such as in fulling-mills, mills for pounding ore, &c. or where large pistons are to be elevated by the arms of levers, it is of the greatest consequence, that the power should raise the weight with an uniform force and velocity; and this can be effected only by giving a proper form to the wipers. A certain class of mechanics ge-

nerally excuse themselves for not attending to the proper form of the teeth of wheels, by alleging that the scientific form differs but little from theirs, and that teeth, however badly formed, will, in the course of time, work into the proper shape. This excuse, however, will not apologize for their negligence in the present case. The scientific form of the wipers of stampers and the arms of levers are so widely different from the form which is generally assigned them, as to increase very much the performance of the machine, and preserve its parts from that injury which is always occasioned by the want of an uniform motion.

Now there are two cases in which this uniformity of motion may be required, and each of these demands a different form for the communicating parts. 1, When the lever is to be raised perpendicularly, as the piston of a pump, &c.; 2, When the lever to be raised or depressed moves upon a centre, and rises or falls in the arch of a circle, in the same plane with the wheel, such as the sledge hammer in a forge, and the stampers in a fulling mill; and 3, When the lever rises in the arch of a circle, and moves in a plane at right angles to the plane of the wheel's motion.

Plate IV, Fig. 5. When the weight rises perpendicularly.

1. In Figure 5, let *AB* be an axis driven by a water-wheel, or any other power, at right angles to which is fixed the bar *mm*, on whose extremities the wipers *mn mn* are fastened. The wiper *mn*, acting upon the arm *PE*, raises the piston, or weight, *EF* to the required height. The piston then falls, and is again raised by the lower wiper. We have represented in the figure only one piston; but it often happens that two or three are to be employed, and, in this case, the axis *AB* must carry four or six wipers, which should be so distributed upon its circumference,

that when one piston is about to fall, the other may begin to rise. Now, in order that these pistons may be raised with an uniform motion, the form of the wiper *mn* must be the evolute of a circle, whose diameter is *mm;* or, in other words, it must be an epicycloid, formed by a generating circle, whose centre is infinitely distant, rolling upon the convex circumference of another circle, whose diameter is *mm*. But as a small roller *P* is frequently fixed to the extremity of the arm *E* to diminish the friction of the working parts, we must draw a curve within the above-mentioned involute, and parallel to it, the distance between them being equal to the radius of the roller;[1] and this new curve will be the proper form for the wiper *mn*, when a roller is employed.

The piston *EF* may also be raised or depressed uniformly, by giving a proper curvature to the arm *PE*, and fixing the roller upon the extremities of the bar *mm*. Thus, in Fig. *5*, let *CD* be an axis, moved by any power, in which are fixed the arms *DH*, *MR*, having rollers *H*, *R*, at their extremities, which act upon the curved arm *op*. When the piston *EF* is raised to the proper height, by the action of the roller *H* upon *op*, it then falls, and is again elevated by the arm *M*. In order that its motion may be uniform, the arm *op* must be part of a cycloid, the radius of whose generating circle is equal to the length of the arm *DH*, reckoning from its extremity *H*, or the centre of the roller, to the centre of the axle *DC*. But, when a roller is fixed upon the extremity *H*, we must draw a curve

[1] The method of doing this is shewn, in Plate II, Fig. 4. See pages 218, 219.

parallel to the cycloid, and without it, at the distance of the roller's semidiameter; and this curve will be the proper form for the arm *op*. It is evident, that, when this mode of raising the piston is adopted, the arm *DH* must be bent, as in the figure, otherwise the extremity *p* would prevent the roller *H* from acting upon the arm *op*.

Plate IV, Fig. 6. In Fig. 6, we have another method of raising a weight perpendicularly with a uniform motion. Let *AH* be a wheel moved by any power which is sufficient to raise the weight *MN* by its extremity *O*, from *O* to *e*, in the same time that the wheel moves round one-fourth of its circumference, it is required to fix upon its rim a wing *OBCDEH*, which shall produce this effect with an uniform effort. Divide the quadrant *OH* into any number of equal parts *Om*, *mn*, &c. the more the better, and *oe* in into the same number *ob*, *bc*, *cd*, &c. and through the points *m*, *n*, *p*, *H*, draw the indefinite lines *AB*, *AC*, *AD*, *AE*, and make *AB* equal to *Ab*, *AC* to *Ac*, *AD* to *Ad*, and *AE* to *Ae*; then, through the points *O*, *B*, *C*, *D*, *E*, draw the curve *OBCDE*, which is a portion of the spiral of Archimedes, and will be the proper form for the wiper, or wing, *OHE*.[8] It is evident, that when the point *m* has arrived at *O*, the extremity of the weight will have arrived at *b*; because *AB* is equal to *Ab*; and, for the same reason, when the points *n*, *p*, *H*, have successively arrived at *O*, the extremity of the weight will have arrived at the corresponding points *c*, *d*, *e*. The motion, therefore, will be uniform; because the space described by the weight is proportional to the space described by the moving power, *Ob* being to *Oc* as *Om*

[8] For a different way of forming this spiral, see Wolfii Opera Mathematica, tom. 1, p. 399.

to On. If it be required to raise the weight MN with an accelerated or retarded motion, we have only to divide the line Oe, according to the law of acceleration or retardation, and divide the curve $OBCDE$ as before.

When the weight rises in the arch of a circle.

2. When the lever moves upon a centre, the weight will rise in the arch of a circle, and consequently a new form must be given to the wipers or wings. The celebrated Deparcieux, of the Academy of Sciences of Paris, has given an ingenious and simple method of tracing mechanically the curves which are necessary for this purpose. Though this method was published about fifty years ago in the Memoirs of the Academy, it does not seem to be at all known to the mechanics of this country. We shall therefore lay it before the reader in as abridged and simplified a form as the nature of the subject will permit. Let AB, Fig. 1, be a lever lying horizontally, which it is required to raise uniformly through the arch BC into the position AC, by means of the wheel BFH, furnished with the wing $BNOP$, which acts upon the extremity C of the lever; and let it be required to raise it through BC in the same time that the wheel BFH moves through one half of its circumference; that is, while the point M moves to B, in the direction MFB. Divide the chord CB into any number of equal parts, the more the better, in the points 1, 2, 3, and draw the lines $1a$ $2b$ $3c$ parallel to AB, or a horizontal line passing through the point B, and meeting the arch CB in the points a, b, c. Draw the lines CD, aD, bD, cD, and BD, cutting the circle BFH in the points m, n, o, p.

Plate V, Fig. 1.

Having drawn the diameter BM, divide the semicircle BFM into as many equal parts as the

chord CB, in the points q, s, u. Take Bm and set it from q to r: Take Bn and set it from s to t: Take Bo and set it from u to v; and lastly, set Bp from M to E. Through the points r, t, v, E, draw the indefinite lines DN, DO, DP, DQ, and make DN equal to Dc; DO equal to Db; DP equal to Da; and DQ equal to DC. Then through the points $Q\ P$, O, N, B, draw the spiral B, N, O, P, Q, which will be the proper form for the wing of the wheel when it moves in the direction EMB.

That the spiral BNO will raise the lever AC with an uniform motion, by acting upon its extremity C, will appear from the slightest attention to the construction of the figure. It is evident, that when the point q arrives at B, the point r will be in m, because Bm is equal to qr, and the point N will be at c, because DN is equal to Dc; the extremity of the lever, therefore, will be found in the point c, having moved through Bc. In like manner, when the point s has arrived at B, the point t will be at n, and the point O in b, where the extremity of the lever will now be found; and so on with the rest, till the point M has arrived at B: The point E will then be in p, and the point Q in C; so that the lever will now have the position AC, having moved through the equal heights Bc, cb, ba, aC,[1] in the same time that the power has moved through the equal spaces qB,

[1] The arches Bc, cb, &c. are not equal; but the perpendiculars let fall from the points c, a, b, &c. upon the horizontal lines, passing through a, b, &c. are equal, being proportional to the equal lines $c1$; 1, 2, Eucl, VI, 2. Had it been required to raise the lever through equal arches, instead of equal heights, in equal times, then the arch BC, instead of its chord, would have been divided into equal parts.

s q, *u s*, *M u*. The lever, therefore, has been raised uniformly, the ratio between the velocity of the power, and that of the weight, remaining always the same.

If the wheel *D* turns in a contrary direction, according to the letters *M H B*, we must divide the semicircle *B H E M*, into as many equal parts as the chord *CB*, viz. in the points *e*, *g*, *i*. Then, having set the arch *B m* from *e* to *d*, the arch *B n* from *g* to *f*, and the rest in a similar manner, draw through the points *d*, *f*, *h*, *E*, the indefinite lines *D R*, *D S*, *D T*, *D Q*, make *D R* equal to *D c*; *D S* equal to *D b*; *D T* equal to *D a*, and *D Q* equal to *D C*; and through the points *B*, *R*, *S*, *T*, *Q*, describe the spiral *B R S T Q*, which will be the proper form for the wing, when the wheel turns in the direction *M H B*. For, when the point *e* arrives at *B*, the point *d* will be in *m*, and *R* in *c*, where the extremity of the lever will now be found, having moved through *B c* in the same time that the power, or wheel, has moved through the division *e B*. In the same manner it may be shewn, that the lever will rise through the equal heights *c b*, *b a*, *a C*, in the same time that the power moves through the corresponding spaces *e g*, *g i*, *i M*. The motion of the lever, therefore, and also that of the power, are always uniform. Of all the positions that can be given to the point *B*, the most disadvantageous are those which are nearest the points *F*, *H*; and the most advantageous position is when the chord *BC* is vertical, and passes, when prolonged, through *D*, the

---

[a] In the figure we have taken the point *B* in a disadvantageous position, because the intersections are in this case most distinct.

centre of the circle.* In this particular case the two curves have equal bases, though they differ a little in point of curvature. The farther that the centre *A* is distant, the nearer do these curves resemble each other; and if it were infinitely distant, they would be exactly similar, and would be the spirals of Archimedes, as the extremity *C* would, in this case, rise perpendicularly.

The intelligent reader will easily perceive, that 4, 6, or 8 wings may be placed upon the circumference of the circle, and may be formed by dividing into the same number of equal parts as the chord *BC*, $\frac{1}{4}$, $\frac{1}{6}$, or $\frac{1}{8}$, of the circumference, instead of the semicircle *BFM*.

That the wing *BNO* may not act upon any part of the lever between *A* and *C*, the arm *AC* should be bent; and that the friction may be diminished as much as possible, a roller should be fixed upon its extremity *C*. When a roller is used, however, a curve must always be drawn parallel to the spiral described according to the preceding method, the distance between it and the spiral being everywhere equal to the radius of the roller.

Mistake of mechanics on this subject.

When two or more wings are placed upon the circumference of the wheel, it has been the custom of practical mechanics to make them portions of an ellipse whose semi-transverse axis is equal to *QD*, the greatest distance of the curve from the centre of the circle. But it will appear, from a comparison of an elliptical arch with the spiral *N*, that it will not produce an uniform motion.—If it should be required to raise the lever with an accelerated or retarded motion, we have only to divide the chord *BC*, according to the degree of retardation or acceleration required, and the circle into the same

number of equal parts as before, and then describe the curve by the method already illustrated.

As it is frequently more convenient to raise or depress weights by the extremity of a constant radius, furnished with a roller, instead of wings fixed upon the periphery of a wheel; we shall now proceed to determine the curve which must be given to the arm of the lever, which is to be raised or depressed, in order that this elevation or depression may be effected with an uniform motion.

Plate V, Fig. 2.

Let AB be a lever, which it is required to raise uniformly through the arch BC, into the position AC, by means of the arm or constant radius DE, moving upon D as a centre, in the same time that the extremity E describes the arch EeF. From the point C draw CH at right angles to AB, and divide it into any number of equal parts, suppose three, in the points 1, 2; and through the points 1, 2, draw $1a$, $2b$, parallel to the horizontal line AB, cutting the arch CB in the points a, b, through which draw aA, bA. Upon D as a centre, with the distance DE, describe the arch $EieF$; and upon A as a centre, with the distance AD, describe the arch eOD, cutting the arch $EieF$ in the point e. Divide the arches Eie, and Fse, each into the same number of equal parts as the perpendicular cH, in the points k, i, s, m, and through these points, about the centre A, describe the arches kz, ig, qr, mn. Take zx and set it from k to l, and take gf, and set it from i to h. Take rq also, and set it from s to t, and set nm from o to p, and dc from e to O. Then through the points E, l, h, O, and O, t, p, F, draw the two curves $ElhO$, and $OtpF$, which will be

the proper form that must be given to the arm of the lever. If the handle DE moves from E towards F, the curve EO must be used, but if in the contrary direction, we must employ the curve OF.

It is evident, that when the extremity E of the handle DE, has run through the arch Ek, or rather El, the point l will be in k, and the point z in x, because xz is equal to kl, and the lever will have the position Ab. For the same reason, when the extremity E of the handle has arrived at i, the point h will be in i, and the point g in f, and the lever will be raised to the position Aa. Thus it appears, that the motion of the power and the weight are always proportional. When a roller is fixed at E, a curve parallel to EO, or OF, must be drawn as formerly.

It is upon these principles that the detent levers of clocks, and those connected with the striking part, should be formed. In every machine, indeed, where weights are to be raised or depressed, either by variable or constant levers, its performance depends much on the proper form of the communicating parts.—

Form of wipers, when they move in a plane at right angles to the lever to be raised.

3. Hitherto we have supposed, that the wheel which carries the wipers, or wings, moves in the same plane with the lever or weight to be raised. Circumstances, however, often occur which render it necessary to elevate the lever by means of a wheel moving at right angles to the plane in which the lever moves; and when this method is adopted, a different form must be given to the wipers. As no writer on mechanics, so far as I know, has treated this subject, it becomes the more necessary to supply the defect by a few observations.

Let *ABC*, Fig. 3, be the lever which is to be raised round the axis *AB*, by the action of the wing *mn* of the wheel *D*, upon the roller *C*, fixed at the extremity of the lever; —it is required to find the form which must be given to the wiper *mn*. It is evident, from Fig. 4, where *CB* is a section of the lever and roller, and *BA* the arch through which it is to be raised, that the breadth of the wiper must always be equal to *mn*, or *rB*, the versed sine of the arch *BA*, through which the roller moves, so that the extremity *n* of the wiper may act upon the roller *B* at the commencement of the motion, and that the other extremity *m* may act upon the roller *A*, when the lever arrives at the required position *CA*. It is easy to perceive, however, that, if the acting surface *mn* of the wiper is always parallel to the horizon, or perpendicular tothe radii of the wheel *D*, or the plane in which it moves, it will act disadvantageously, except at the commencement of the motion, when *mn* is parallel to *CB*. For, when *mn* has arrived at the position *op*, the extremity *o* will act upon the roller *A*, but in such an oblique and disadvantageous manner, that it will scarcely have any power to turn it upon its axis, or move the lever round the fulcrum *C*. The friction of the roller upon its axis, therefore, will increase, and the power of the wiper to turn the lever will diminish, in proportion to the length of the arch *BA;* and if *CA* arrives at a vertical position, the power of the wiper will be solely employed in wrenching the lever from its fulcrum.

Plate V, Fig. 3.

Fig. 4.

In order to avoid this inconvenience, we must endeavour to give such a form to the wiper, that its acting surface may always be parallel to the lever, or axis of the roller, having the

position *mn* when the roller is at *B*, and the position *ob* when the roller is at *A*.

Having stated the peculiarities of this construction, let us now attend to the method by which the acting surface of the wiper must be formed. Since the lever *CB* is to be raised perpendicularly through the equal spaces *rc*, *ca*, *aA* in equal times, the acting surface of the wiper must evidently be part of the spiral of Archimedes,[6] the method of describing which is shewn, in Fig. 6 of Plate IV; but the difficulty lies in giving different degrees of inclination to the acting surface, in order that the part in contact with the roller may be parallel to the direction of the lever. Let *AD*, Fig. 6, be the wheel, which is to be furnished with wings, and let *Cb* the perpendicular height, through which the lever is to rise, be equal to *Ar*, in Fig. 4. Divide the quadrant *Db* into any number of equal parts, the more the better, suppose three, in the points *c* and *r*, and describe the spiral of Archimedes *DinC*, as formerly directed. Divide *Ar* (Fig. 4) the sine of the arch *BA*, into the same number of equal parts, in the points *c*, *a*; and draw *af*, *cg* parallel to *CB*, and cutting the circle in the points *d*, *e*, and the tangent *Bb* in the points *f*, *g*; and through the points *C* and *d* draw *Cki*. The line *df* is equal to the difference between radius and the cosine of the arch *dB*; *fi* is equal to the difference between the tangent and the sine of the same arch; *iB* being the tangent, and *fB* equal to the sine of the arch *dB*, or angle *dcB*; *ad* is equal to *af*—*df*, or to the difference be-

Plate V, Fig. 4 & 6.

[6] See page 246.

tween df and the versed sine of the whole arch AB; and ak is equal to $\frac{fi \times da}{df}$ for an account of the similar triangles dfi, dak, we have $df : fi = da : ak$*; and consequently $ak = \frac{fi \times da}{df}$.

Since then the points r, c, a, A (in Fig. 4) correspond respectively with the points D, i, n, C of the spiral, in Fig. 6, take fi and set it from n to m, and ak from n to o; take also gh, and set it from i to h (Fig. 6) set cq from i to k, and make cB, in Fig. 6, equal to pb, in Fig. 4, or the difference between the tangent and sine of the arch AB, and through the points D, k, o, C, and D, h, m, B, draw the curves DoC, DmB, which will be the proper form for the sides ON, MP of the spiral wiper $MONP$ (Fig. 5), the acting surface $MONP$ must then be wrought in such a manner as to consist of a variety of planes, differently inclined to the plane BON of the wiper, the angle of inclination being a right angle at O and M, but increasing gradually till the inclination at NP becomes equal to the angle DCE, or ACB, in Fig. 4.[9] From the construction of Fig. 4, it is evident, that the arches Be, ed, dA are not equal, nor are they aliquot parts of AB. But since the arch AB, and its sine Ar are known, and since the sines of the other arches are known, viz. bc, ba, the arches themselves may be easily found by a table of natural sines.

Plate V, Fig. 5.

* The lines df, fi, ad, ak, may also be found mechanically, by making AC equal to the real length of the lever.

[9] The curves, which must be employed in practice, should be curves drawn parallel to those formed by the preceding method, at the distance of the semidiameter of the roller.

Fig. 5. In Fig. 5, we have a perspective view of a wheel, furnished with two wipers, formed according to the preceding directions. *FC* and *LN* correspond with *bC* and *rA*, in Fig. 6 and 4. The curves *AnmC*, and *ON* correspond with *DkoC*, in Fig. 6, and *MP* with *DhmB*. The diagonal curve *MN* corresponds with the diagonal curve *DinC*, and *OM*, the breadth of the wiper with *mn*, or *rB*, the versed sine of the arch *AB*, in Fig. 4. The breadth *OM*, however, should always be a little greater than the versed sine of the arch through which the lever is to be raised, since *MN* is the path of the roller over the wiper's surface.

Having thus described the different methods of raising weights, whether perpendicularly, or round a centre, with an uniform velocity and force, it would be unnecessary to apply the principles of construction to those machines which are formed for the elevation of weights. The practical mechanic can easily do this for himself. There is one case, however, which deserves peculiar attention, because the wipers, formed according to the preceding rules, will not produce the intended effect. This happens in the case of the large sledge hammer which is employed in forges. In Fig. 7, *BC* is the large hammer moved round *A* as a centre, by means of the wiper *MW* acting upon its extremity *AC*, or upon the roller *R*. The hammer must be tossed up with a sudden motion, so as to strike the elastic oaken spring *E*, which, being compressed, drives back the hammer, with great force, upon the anvil *D*. Now, if spiral wipers, constructed according to the directions already given, are employed, the hammer will indeed be raised equably without the least jolting, but it will rise no

Plate V, Fig. 7. Form of wipers for raising forge hammers.

higher than the wiper lifts it, and will, therefore, fall merely with its own weight. But, if the wipers are constructed in the common way, and the hammer elevated with a motion greatly accelerated, it will rise much higher than the wiper lifts it,—it will impinge against the oaken beam *E*, and be repelled with great effect against the iron on the anvil *D*. In any of the preceding constructions, this accelerated motion may be produced, merely by dividing *BC* according to the law of acceleration, and proceeding as already directed. Plate V, Fig. 1 & 2.

MECHANICS.

ON THE NATURE AND CONSTRUCTION OF WIND-MILLS.

Description of a Wind-mill.

Description of Verrier's wind-mill.

THE limited and imperfect manner in which Mr. Ferguson has treated of wind-mills, in the preceding volume, renders it necessary that the subject should now be prosecuted at greater length. The few observations which he has made, upon these machines, presuppose that the reader is acquainted with their nature and construction; a species of knowledge which is not to be expected in the readers of a popular and elementary work. For the purpose of supplying this defect, and enabling the reader to understand the observations, which may be made on the form and position of the sails, and on the relative advantages of horizonal and vertical wind-mills, we shall give a description of a wind-mill, invented by Mr. James Verrier, containing several improvements on the common construction, for

which the author was liberally rewarded by the Society of Arts.

This machine is represented in Fig. 1, where *AAA* are the three principal posts, 27 feet $7\frac{1}{2}$ inches long, 22 inches broad at their lower extremities, 18 inches at their upper ends, and 17 inches thick. The column *B* is 12 feet $2\frac{1}{2}$ inches long, 19 inches in diameter at its lower extremity, and 16 inches at its upper end; it is fixed in the centre of the mill, passes through the first floor *E*, having its upper extremity secured by the bars *GG*. *EEE* are the girders of the first floor, one of which only is seen, being 8 feet 3 inches long, 11 inches broad, and 9 thick; they are mortised into the posts *AAA* and the column *B*, and are about 8 feet 3 inches distant from the ground floor. *DDD* are three posts 6 feet 4 inches long, 9 inches broad, and 6 inches thick; they are mortised into the girders *EF* of the first and second floor, at the distance of 2 feet 4 inches from the posts *A*, &c. *FFF* are the girders of the second floor, 6 feet long, 11 inches broad, and 9 thick; they are mortised into the posts *A*, &c. and rest upon the upper extremities of the posts *D*, &c. The three bars *GGG* are 3 feet $1\frac{1}{2}$ inches long, 7 inches broad, and 3 thick; they are mortised into the posts *D* and the upper end of the column *B*, 4 feet 3 inches above the floor. *P* is one of the beams which support the extremities of the bray-trees, or brayers; its length is 2 feet 4 inches, its breadth 8 inches, and its thickness 6 inches. *I* is one of the bray-trees, into which the extremity of one of the bridge-trees *K* is mortised. Each bray-tree is 4 feet $9\frac{1}{2}$ inches long, $9\frac{1}{2}$ inches broad, and 7 thick; and each bridge-tree is 4 feet 6 inches long, 9 inches broad, and 7 thick,

Plate VI, Fig. 1.

being furnished with a piece of brass on their upper surface to receive the under pivot of the millstones. *LL* are two iron screw-bolts, which raise or depress the extremities of the bray-trees. *MMM* are the three millstones, and *NNN* the iron spindles, or arbors, on which the turning millstones are fixed. *O* is one of three wheels, or trundles, which are fixed on the upper ends of the spindles *NNN;* they are 16 inches in diameter, and each is furnished with 14 staves. *f* is one of the carriage-rails, on which the upper pivot of the spindle turns, and is 4 feet 2 inches long, 7 inches broad, and 4 thick. It turns on an iron bolt at one end, and the other end slides in a bracket fixed to one of the joists, and forms a mortise, in which a wedge is driven to set the rail and trundle in or out of work; *t* is the horizontal spur-wheel that impels the trundles; it is 5 feet 6 inches diameter, is fixed to the perpendicular shaft *T*, and is furnished with 42 teeth. The perpendicular shaft *T* is 9 feet 1 inch long, and 14 inches in diameter, having an iron spindle at each of its extremities; the under spindle turns in a brass block fixed into the higher end of the column *B;* and the upper spindle moves in a brass plate inserted into the lower surface of the carriage-rail *C*.

The spur-wheel *r* is fixed on the upper end of the shaft *T*, and is turned by the crown-wheel *v* on the windshaft *c*, it is 3 feet 2 inches in diameter, and is furnished with 15 cogs. The carriage-rail *C*, which is fixed on the sliding kerb *Z*, is 17 feet 2 inches long, 1 foot broad, and 9 inches thick. *YYQ* is the fixed kerb, 17 feet 3 inches diameter, 14 inches broad, and 10 thick, and is mortised into the posts *AAA*,

and fastened with screw-bolts. The sliding kerb *Z* is of the same diameter and breadth as the fixed kerb, but its thickness is only $7\frac{1}{2}$ inches; it revolves on 12 friction rollers fixed on the upper surface of the kerb *YYQ*, and has 4 iron half staples *Y*, *Y*, &c. fastened on its outer edge, whose perpendicular arms are 10 inches long, 2 inches broad, and 1 inch thick, and embrace the outer edge of the fixed kerb to prevent the sliding one from being blown off. The capsills *X*, *V*, are 13 feet 9 inches long, 14 inches broad, and 1 foot thick; they are fixed at each end, with strong iron screw bolts, to the sliding kerb, and to the carriage-rail *C*. On the right hand of *w* is seen the extremity of a cross rail, which is fixed into the capsills *X* and *V*, by strong iron bolts: *e* is a bracket 5 feet long, 16 inches broad, and 10 inches thick; it is bushed with a strong brass collar, in which the inferior spindle of the windshaft turns, and is fixed to the cross rail *w*: *b* is another bracket 7 feet long, 4 feet broad, and 10 inches thick; it is fixed into the fore ends of the capsills, and, in order to embrace the collar of the windshaft, it is divided into two parts, which are fixed together with screw bolts. The windshaft *c* is 15 feet long, 2 feet in diameter at the fore end, and 18 inches at the other; its pivot at the back end is 6 inches diameter, and the shaft is perforated to admit an iron rod to pass easily through it. The vertical crown wheel *v* is 6 feet in diameter, and is furnished with 54 cogs, which drive the spur wheel *r*. The bolster *d*, which is 6 feet 3 inches long, 13 inches broad, and half a foot thick, is fastened into the cross rail *w*, directly under the centre of the windshaft, having a brass pulley fixed at its fore end. On the upper surface of

this bolster is a groove, in which the sliding bolt *R* moves, having a brass stud at its fore end. This sliding bolt is not distinctly seen in the figure, but the round top of the brass stud is visible below the letter *h*: the iron rod that passes through the windshaft bears against this brass stud. The sliding bolt is 4 feet 9 inches long, 9 inches broad, and $\frac{1}{3}$ of a foot thick. At its fore end is fixed a line, which passes over the brass pulley in the bolster, and appears at *a* with a weight attached to its extremity, sufficient to make the sails face the wind that is strong enough for the number of stones employed; and when the pressure of the wind is more than sufficient, the sails turn on an edge, and press back the sliding bolt, which prevents them from moving with too great velocity; and, as soon as the wind abates, the sails, by the weight *a*, are pressed up to the wind, till its force is sufficient to give the mill a proper degree of velocity. By this apparatus, the wind is regulated and justly proportioned to the resistance or work to be performed; an uniformity of motion is also obtained, and the mill is less liable to be destroyed by the rapidity of its motion.

That the reader may understand how these effects are produced, we have represented, in Plate VI, Fig. 2, the iron rod, and the arms which bear against the vanes; *ah* is the iron rod which passes through the windshaft *c*, in Fig. 1; *h* is the extremity, which moves in the brass stud that is fixed upon the sliding bolt; *ai*, *ai*, &c. are the cross arms, at right angles to *ah*, whose extremities *i*, *i*, similarly marked in Fig. 1, bear upon the edges of the vanes. The arms *ai* are $6\frac{1}{2}$ feet long, reckoning from the centre *a*, 1 foot

Plate VI, Fig. 2.

Method of varying the angle of the sails' inclination.

broad at the centre, and 5 inches thick; the arms *n*, *n*, &c. that carry the vanes or sails, are 18½ feet long, their greatest breadth is 1 foot, and their thickness 9 inches, gradually diminishing to their extremities, where they are only 3 inches in diameter. The four cardinal sails, *m*, *m*, *m*, *m*, are each 13 feet long, 8 feet broad at their outer ends, and 3 feet at their lower extremities; *p*, *p*, &c. are the four assistant sails, which have the same dimensions as the cardinal ones, to which they are joined by the line *SSSS*. The angle of the sail's inclination, when first opposed to the wind, is 45 degrees, and regularly the same from end to end.

It is evident, from the preceding description of this machine, that the windshaft *c* moves along with the sails; the vertical crown wheel *v* impels the spur wheel *r*, fixed upon the axis *T*, which carries also the spur wheel *t*. This wheel drives the three trundles *H*, one of which only is seen in the figure, which being fixed upon the spindles *N*, &c. communicate motion to the turning mill-stones.

Method of turning the sails to the wind.

That the wind may act with the greatest efficacy upon the sails, the windshaft or principal axis must always have the same direction as the wind. But as this direction is perpetually changing, some apparatus is necessary for bringing the windshaft and sails into their proper position. This is sometimes effected by supporting the machinery on a strong vertical axis, whose pivot moves in a brass socket firmly fixed into the ground, so that the whole machine, by means of a lever, may be made to revolve upon this axis, and be properly adjusted to the direction of the wind. Most wind-mills,

however, are furnished with a moveable roof, which revolves upon friction rollers inserted in the fixed kerb of the mill; and the adjustment is effected by the assistance of a simple lever. As both these methods of adjusting the wind-shaft require the assistance of men, it would be very desirable that the same effect could be produced solely by the action of the wind. This may be done, by fixing a large wooden vane, or weather-cock, at the extremity of a long horizontal arm, which lies in the same vertical plane with the windshaft. By this means, when the surface of the vane, and its distance from the centre of motion are sufficiently great, a very gentle breeze will exert a sufficient force upon the vane to turn the machinery, and will always bring the sails and windshaft to their proper position. This weathercock, it is evident, may be applied, either to machines which have a moveable roof, or which revolve upon a vertical arbor.

Wind-mills numerous in Holland.

Prior to the French revolution, wind-mills were more numerous in Holland and the Netherlands than in any other part of the world, and there they seem to have been brought to a very high state of perfection. This is evident, not only from the experiments of Mr. Smeaton, from which it appears, that sails weathered in the Dutch manner produced nearly a maximum effect, but also from the observations of the celebrated Coulomb. This philosopher examined above 50 wind-mills in the neighbourhood of Lisle, and found that each of them performed nearly the same quantity of work when the wind moved with the velocity of 18 or 20 feet per second, though there were some

trifling differences in the inclination of their windshafts, and in the disposition of their sails. From this fact, Coulomb justly concluded, that the parts of the machine must have been so disposed as to produce nearly a maximum effect.

Form of Dutch wind-mills, according to Coulomb.

In the wind-mills, on which Coulomb's experiments were made, the distance, from the extremity of each sail to the centre of the windshaft, or principal axis, was 33 feet. The sails were rectangular, and their width was a little more than 6 feet, 5 of which were formed with cloth stretched upon a frame, and the remaining foot consisted of a very light board. The line, which joined the board and the cloth, formed, on the side which faced the wind, an angle sensibly concave at the commencement of the sail, which diminished gradually till it vanished at its extremity. Though the surface of the cloth was curved, it may be regarded as composed of right lines perpendicular to the arm, or whip, which carries the frame, the extremities of these lines corresponding with the concave angle formed by the junction of the cloth and the board. Upon this supposition these right lines at the commencement of the sail, which was distant about 6 feet from the centre of the windshaft, formed an angle of 60° with the axis, or windshaft, and the lines, at the extremity of the wing, formed an angle, increasing from 78 to 84°, according as the inclination of the axis of rotation to the horizon increased from 8 to 15°; or, in other words, the greatest angle of weather was 30°, and the least varied from 12 to 6°, as the inclination of the windshaft varied from 8 to

15°.[1] A pretty distinct idea of the surface of wind-mill sails may be conveyed, by conceiving a number of triangles standing perpendicular to the horizon, in which the angle contained between the hypothenuse and the base is constantly diminishing: the hypothenuse of each triangle will then be in the superficies of the vane, and they would form that superficies if their number were infinite.

On the Form and Position of Wind-mill Sails.

Form and position of the sails.

M. Parent seems to have been the first mathematician who considered the subject of wind-mill sails in a scientific manner. The philosophers of his time entertained such erroneous opinions upon this point, as to suppose that the surface of the sails should be equally inclined to the direction of the wind and to the plane of their motion; or, what is the same thing, that the angle of weather should be 45°.[2] But it appears, from the investigations of Parent, that a maximum effect will be produced when the sails are inclined $54\frac{2}{3}°$ to the axis of rotation, or when the angle of weather is $35\frac{1}{3}°$. In obtaining this conclusion, however, M. Parent has assumed data which are inadmissible, and has neglected several circumstances which must materially affect the result of his in-

The inclination assigned by Parent erroneous.

[1] The *weather* of the sails is the angle which the surface of the sails forms with the plane of their motion, and is always equal to the complement of the angle which that surface forms with the axis.

[2] See Wolfii Opera Mathematica, tom. i, p. 680, where this angle is recommended.

vestigations. The angle, or inclination, assigned by Parent, is certainly the most efficacious for giving motion to the sails from a state of rest,[3] and for preventing them from stopping when in motion; but he has not considered that the action of the wind upon a sail at rest is different from its action upon a sail in motion: for since the extremities of the sails move with greater rapidity than the parts nearer the centre, the angle of weather should be greater towards the centre than at the extremity, and should vary with the velocity of each part of the sail.[4] The reason of this is very obvious. It has been demonstrated by Bossut,[5] and sufficiently established by experience, that when any fluid acts upon a plain surface, the force of impulsion is always exerted most advantageously when the impelled surface is in a state of rest, and that this force diminishes as the velocity of the surface increases.

---

[3] This may be demonstrated in the following manner.—Let x be the cosine of the angle sought; then, since the sine, cosine, and radius of any arch form a right angled triangle, the square of the sine will be equal to the square of the cosine subtracted from the square of the radius, that is, $1-x^2$ will be the square of the sine when the radius is unity. But the effect of the wind, on an oblique sail, is, in the compound ratio of the square of the sine of its obliquity, and the breadth of the sail projected on a plane perpendicular to the direction of the wind. Now, this breadth is exactly x, the cosine of the sail's inclination; therefore $x \times \overline{1-x^2}$, or $x-x^3$ will represent the effect of the wind upon the sail. And, as this is to be a maximum, let us take its fluxion, which will be $\dot{x}-3x^2\dot{x}=0$. Dividing by $\dot{x}$ we have $3x^2=1$, or $x=\sqrt{\frac{1}{3}}=\frac{1}{1.7320508076}=.5773520$, which is the cosine of 54° 44′ 13″.

[4] See vol. i, p. 97.

[5] Traite d'Hydrodynamique, § 772.

Now, let us suppose, with Parent, that the most advantageous angle of weather for the sails of wind-mills is $35\frac{1}{2}$ degrees for that part of the sail which is nearest the centre of rotation, and that the sail has everywhere this angle of weather; then, since the extremity of the sail moves with the greatest velocity, it will, in a manner, withdraw itself from the action of the wind; or, to speak more properly, it will not receive the impulse of the wind so advantageously as those parts of the sail which have a less velocity. In order, therefore, to make up for this diminution of force, we must make the wind act more perpendicularly upon the sail, by diminishing its obliquity, that is, we must increase its inclination to the axis or the direction of the wind; or, what is the same thing, we must diminish its angle of weather. But, since the velocity of every part of the sail is proportional to its distance from the centre of motion, every elementary portion of it must have a different angle of weather diminishing from the centre to the extremity of the sail. The law or rate of diminution, however, is still to be discovered, and we are fortunately in possession of a theorem of Euler's, afterwards given by M'Laurin, which determines this law of variation.[6] Let a represent the velocity of the wind, and c the velocity of any given part of the sail, then the effort of the wind upon that part of the sail will be greatest when the tangent of the angle of the wind's incidence, or of the sail's inclination to the axis, is to radius as $\sqrt{2+\frac{9cc}{4aa}}+\frac{3c}{2a}$ to 1.

Euler's theorem.

[6] See Maclaurin's Fluxions, art. 910—914.

In order to apply this theorem, let us suppose that the radius or whip ms of the sail $\alpha\beta\delta i$, is divided into six equal parts, that the point n is equidistant from m and s, and is the point of the sail which has the same velocity as the wind; then, in the preceding theorem, we will have $c=a$, when the sail is loaded to a maximum; and therefore the tangent of the angle, which the surface of the sail at n makes with the axis, when $a=1$ will be $\sqrt{2+\frac{9}{4}}+\frac{3}{2}=3.561=$ tangent of 71°19′, which gives 15° 41′ for the angle of weather at the point n. Since, at $\frac{1}{2}$ of the radius $c=a$, and since c is proportional to the distance of the corresponding part of the sail from the centre we will have, at $\frac{1}{6}$ of the radius sm, $c=\frac{a}{3}$, at $\frac{2}{6}$ of the radius, $c=\frac{2a}{3}$; at $\frac{4}{6}$, $c=\frac{4a}{3}$; at $\frac{5}{6}$; $c=\frac{5a}{3}$; and at the extremity of the radius, $c=2a$. By substituting these different values of c, instead of c in the theorem, and by making $a=1$, the following table will be obtained, which exhibits the angles of inclination and weather which must be given to different parts of the sails.

Plate VI, Fig. 1. Explanation and application of this theorem.

Table shewing the rate at which the inclination varies.

Parts of the radius from the centre of motion at s.	Velocity of the sail at these distances—or values of c.	Angle made with the axis.		Angle of weather.	
		Deg.	Min.	Deg.	Min.
$\frac{1}{6}$	$\frac{a}{3}$	63	26	26	34
$\frac{2}{6}$	$\frac{2a}{3}$	69	54	20	6
$\frac{3}{6}$ or $\frac{1}{2}$	a	74	19	15	4
$\frac{4}{6}$ or $\frac{2}{3}$	$\frac{4a}{3}$	77	20	12	40
$\frac{5}{6}$	$\frac{5a}{3}$	79	27	10	33
1	$2a$	81	0	9	0

Having thus pointed out an important error in Parent's theory, and shewn how to find the law of variation in the angle of weather, we have farther to observe, that, in order to simplify the calculus, Parent supposed the velocity of the wind to be infinite when compared with the velocity of the sail, and that its impulsion upon the sail was in the compound ratio of the square of its velocity and the square of the sine of incidence. The first of these suppositions is evidently inaccurate, and was shewn to be so by Daniel Bernouilli, in his Hydrodynamique. With regard to the force of impulsion on the sails, the proposition is perfectly true in theory, and has been demonstrated

by Pitot,[1] and other philosophers; but it unquestionably appears, from the experiments presented to the French Academy, in 1763, by M. le Chevalier de Borda, and from those made, in 1776, by M. d'Alembert, the Marquis Condorcet, and the Abbe Bossut,[2] that this proposition does not hold in practice. The first part of the proposition, indeed, that the force of impulsion is proportional to the square of the velocity of the surface that it is impelled, is true in practice; but, when the angles of incidence are small, the latter part of the proposition must be abandoned, as it would afford very false results. In cases, however, where the angles of incidence are between 50 and 90 degrees, we may regard the impulsion as proportional to the square of the velocity multiplied by the square of the sine of incidence; but we must remember, that the force thus determined by the theory will be a little less than that which would be found by experiment, and that the difference increases as the angle of incidence recedes from 90°.

Force of impulsion on inclined surfaces.

Such being the circumstances which Parent has overlooked in his investigations, we need not be surprised to find, from the experiments of Smeaton, that when the angle which he recommends was adopted, the sails produced a smaller effect than when they were weathered in the common manner, or according to the Dutch construction.[3]

---

[1] Mem. de l'Acad. Paris, 1729, p. 540.

[2] Nouvelles Experiences sur la resistance des fluides, par M. M. d'Alembert, le Marquis de Condorcet, et l'Abbe Bossut, chap. v, § 35.

[3] Mons. Belidor has fallen into the same error as Parent, and observes, that the workmen at Paris make the angle of weather,

Euler's observations on wind-mills.

The theory of wind-mills has been treated at great length by M. Euler, the most profound and celebrated mathematician of his time. He has shewn, that the angle assigned by Parent is too small for a sail in motion, and that the angle of weather should vary with the velocity of the different parts of the sails; but, like Parent, he has supposed that the force of impulsion upon surfaces, with different obliquities, is proportional to the square of the sines of their inclination. As the angles of incidence, however, are sufficiently great, this circumstance will have but a trifling effect upon his conclusions. After Euler has shewn, in general, how to determine the force of impulsion upon the sails, whatever be their figure and disposition, and whatever be the celerity of their motion; he then investigates, by the method *de maximis et minimis*, what should be the inclination of the sails to the axis, and the velocity of their extremities, in order to produce a maximum effect; and he finds, that this inclination and velocity are variable, and are inversely proportional to the momentum of friction in the machine. That the reader may fully understand this important result, we may remark, that, in theory, the greatest effect will be produced when the velocity of the sails is infinitely great, and when their surfaces are perpendicular to the wind's direction; that is, when the angle of weather is nothing. But both these suppositions are excluded in practice; for though the sails receive the greatest possible impetus from the wind,

---

weather 18°, and thereby lose $\frac{3}{7}$ of the effect; whereas, this is nearly the most efficacious angle that can be adopted. See Architecture Hydraulique, par Belidor, tom. 2, B. iii, pp. 33—41.

when they are inclined 90° to the axis, yet this force has not the smallest tendency to put them in motion; and it is not difficult to perceive, that the friction of the machine, and the resistance of the air to the thickness of the sails, must always limit the velocity of their motion. In this case, theory does not accord with practice; but they may be easily reconciled, by making the angle of inclination 89° instead of 90, and supposing the sails to perform a finite, but a very great number of revolutions in a second, an hundred for example. Then the sails, having still a very disadvantageous position, will receive but a small impetus from the wind, which may be called *one* pound. But this defect in the impelling power is made up by the great velocity of the sails; and since the effect is always equal to the product of the weight and the velocity, we will have $1 \times 100 = 100$ for the effect of the machine. Now, let us take friction into the account, and suppose it to be so great as to diminish the rapidity of the sails, from 100 to 50 turns in a second; then, in order that the machine may produce an effect equal to 100, as formerly, we must change the angle of the sail's inclination, till it receives from the wind an impetus equal to two pound for $2 \times 50 = 100$. If the friction be still farther increased, the celerity of the machine will experience a proportional diminution, and the angle of inclination must undergo such a change, that the force of impulsion received from the wind may make up for the velocity that is lost by an increase of friction. From these observations it plainly appears, that the celerity of the sails, and their inclination to the axis, depend upon the momentum of friction; and as this is generally a constant quantity in machines, and can easily be

determined experimentally, the position of the sails, the velocity of their motion, and the effect of the machine, may be found from the following table, which is calculated from the formulæ of Euler, and adapted to different degrees of friction.

In this table, F denotes the force of the wind upon all the sails; d is the radius of the sail, or the distance of its extremity from the centre of the axis or windshaft; v is the velocity of the wind; and s the velocity of the sail's extremity, which is equal to the numbers contained in the fourth column.

Table containing the Angle of Inclination and Weather of Wind-mill Sails, the Velocity of their Extremities, and the Effect of the Machine, for any Degree of Friction.

Momentum of friction.	Angle of the sail's inclination to the axis.	Angle of weather.	Velocity of the sails at their extremities.	Effect of the machine.	Effect of the machine differently expressed.
0.235702 Fd	45°	45°	0.000000 v	0.000000 Fv	0.000000 F_s
0.175837 Fd	50	40	0.127686 v	0.004718 Fv	0.036950 F_s
0.122871 Fd	55	35	0.281334 v	0.017968 Fv	0.063869 F_s
0.079653 Fd	60	30	0.469882 v	0.037427 Fv	0.079653 F_s
0.047001 Fd	65	25	0.711154 v	0.060147 Fv	0.084576 F_s
0.024370 Fd	70	20	1.042160 v	0.083159 Fv	0.079795 F_s
0.010362 Fd	75	15	1.550395 v	0.103842 Fv	0.066978 F_s
0.003084 Fd	80	10	2.499421 v	0.120105 Fv	0.048053 F_s
0.000386 Fd	85	5	5.208606	0.130454 Fv	0.025046 F_s
0.000000 Fd	90	0	Infinite.	0.134001 Fv	0.000000 F_s
1	2	3	4	5	6

Explanation of the table.

The preceding table has been applied, by Euler, solely to that species of wind-mills in which the sails are sectors of an ellipse, and which intercept the whole cylinder of wind. This

construction was recommended also by Parent; but later and more accurate experiments have evinced, that when the whole area is filled up with sail, the wind does not produce its greatest effect, from the want of proper interstices to escape. On this account a small number of sails are generally used, and these are either rectangular, or a little enlarged at their extremities. It will be proper, therefore, to shew how the table can be applied to this description of sails, for the application is much more difficult than in the other case.

It is evident, from the first column of the table, that before we can use it, we must find the value of F, or the force of the wind upon all the sails. But as this force depends not merely upon the quantity of surface, and the velocity of the wind, which are always given, but also upon the angle of their inclination, which is unknown, some method of determining it, independently of this angle, must be adopted. Euler has shewn how to do this, in the case where the whole area is filled with elliptical sectors; but there is no direct method of determining the value of F in the case of rectangular sails, when the angle of inclination is unknown. We must find it therefore by approximation; that is, we must take any probable angle of inclination, 70° for example, and find the value of F suited to this angle, and thence the co-efficient of Fd, in the first column. With this co-efficient enter the table, and take out the corresponding angle of inclination, which will be either less or greater than 70. With this new angle of inclination find a more accurate value of F, and consequently a new co-efficient of Fd. If this co-efficient does not differ very much from that formerly found,

it may be regarded as true, and employed for taking out of the table a more accurate angle of inclination, along with the velocity of the sails, and the effect of the machine. We shall now illustrate both these methods by an example, after having shewn how to determine by experiment the momentum of friction, and the velocity of the wind.

To find the Momentum of Friction.

On the momentum of friction.

In a calm day, when the wind-mill is unloaded, or performing no work, bring two opposite sails into a horizontal position; and, having attached different weights to the extremities of their radius, find how many pounds are sufficient not only for impressing the smallest motion on the sails, but for continuing them in that state; and the number of pounds multiplied into the length of the radius, will be the momentum of friction. When this experiment is made, it will always be found that a greater weight is necessary for moving the sails than for continuing them in motion; and, in order that the quantity of friction may be accurately estimated, the wind-mill should be put in motion immediately before the experiment is made; for the friction always increases with the time in which the communicating parts have remained in contact.

To find the Velocity of the Wind.

To find the wind's velocity.

Various instruments, denominated anemometers, or anemoscopes, have been invented for

measuring the force and velocity of the wind, the best of which are those which were constructed by Mr. Pickering[1] and Dr. Lind.[2] The velocity of the wind has been deduced also from the motion of the clouds, and the change effected by the wind upon the motion of sound.[3] The second of these methods is manifestly inaccurate, and the first takes for granted what is palpably erroneous, that the velocity of the wind is the same in the higher regions of the atmosphere, as at the surface of the earth. The ingenious Professor Leslie having found, in the course of his experiments on heat, that the refrigerant, or cooling, power of a current of air is exactly proportional to its velocity, derives, from this principle the construction of a new and

---

[1] Philosophical Transactions, No. 473.

[2] Id. vol. lxv, p. 353.

[3] Brisson, *Traite de Physique*, vol. ii, p. 150, § 1015.—For the description of another anemometer, see Wolfii Opera Math. tom. i, p. 773. The anemometer invented by Bouguer is described in his *Traite du Navire*, p. 369; Onsen Bray's anemometer in the Mem. Acad. Paris, 1734; and another by Zeiher, which is a combination of Bouguer's instrument, with the apparatus employed by Smeaton, is described in the Nov. Com. Petrop. 1766, vol. x, p. 302.

I have seen an ingenious anemometer, invented by the Rev. Mr. Jameſon of St. Mungo, and founded on the same principle as the quadrant, described by Bossut, for finding the velocity of running water. A plane surface, suspended in a vertical direction, is exposed to the action of the wind, and the angle of its elevation, to the tangent of which the force of the wind is always proportional, is pointed out by an index carried round by a wheel and pinion. By means of a ſmall click which falls into the teeth of one of the wheels, the plain surface, or pendulum, is detained in the position to which it is raised, and the greatest velocity of the wind may be determined in the absence of the observer.

Leslie's anemometer.

simple anemometer. 'It is in reality nothing 'more,' says he, 'than a thermometer, only 'with its bulb larger than usual. Holding it in 'the open still air, the temperature is marked: 'it is then warmed by the application of the 'hand, and the time is noted which it takes to 'sink back to the middle point. This I shall 'term the fundamental measure of cooling. The 'same observation is made on exposing the bulb 'to the impresson of the wind, and I shall call 'the time required for the bisection of the inter- 'val of temperatures, the occasional measure of 'cooling. After these preliminaries, we have 'the following easy rule:—*Divide the funda- 'mental by the occasional measure of cooling, 'and the excess of the quotient above unit, being 'multiplied by* $4\frac{1}{2}$, *will express the velocity of 'the wind in miles per hour.* The bulb of the 'thermometer ought to be more than half an 'inch in diameter, and may, for the sake of 'portability, be filled with alcohol tinged, as 'usual, with archil. To simplify the observation, 'a sliding scale of equal parts may be applied to 'the tube. When the bulb has acquired the 'due temperature, the zero of the slide is set 'opposite to the limit of the coloured liquor in 'the stem; and, after having been heated, it 'again stands at 20° in its descent, the time 'which it thence takes until it sinks to 10° is 'measured by a stop watch. Extemporaneous 'calculation may be avoided, by having a table 'engraved upon the scale for the series of occa- 'sional intervals of cooling.'[4]

[4] Enquiry into the Nature and Propagation of Heat, p. 284.

The most simple method of determining the velocity of the wind, is that which Coulomb employed in his experiments on wind-mills, and which requires neither the aid of instruments nor the trouble of calculation.[s] Two persons were placed on a small elevation, at the distance of 150 feet from one another, in the direction of the wind; and, while the one observed, the other measured the time which a small and light feather employed in moving through the space. The distance between the two persons, divided by the number of seconds, gave the velocity of the wind per second. Having thus shewn how to find the momentum of friction, and the velocity of the wind, we shall now explain the use of the table. Coulomb's method.

Supposing the radius of the sails to be 20 feet, the velocity of the wind 10 feet per second, and that it requires a force of 10 pounds acting at the extremity of the radius to overcome the friction of the machine,—it is required to find the angle of weather, the velocity of the sails, and the effect of the machine. Explanation of the table.

Let d, the radius of the sails, be $=20$ feet, then the momentum of friction will be $10\times 20 = 200$ pounds. Let n, the number of sails, be $=12$, while a represents the breadth of the sails at their extremities, and b the breadth into which they are projected, or the breadth which they would occupy if reduced into a plane perpendicular to the wind. Then, since the whole cylinder of wind is supposed to be intercepted, the effect produced upon all the oblique sails will be equal

[s] See Mem. de l'Acad. Paris, 1781, p. 70.

to the effect that would be produced upon a perpendicular surface, equal to the whole area of the polygon into which the oblique triangular sails are projected. The value of b, therefore, may be found by plane trigonometry, the length of the sail and the angle of the polygon being given, or by the following theorem: $b = 2d \times \text{tang.} \frac{180}{n}$, d being radius, and n the number of sails. In the present case then, we shall have $b = 2 \times 20 \times \text{tang.} \frac{180'}{n}$, or $b = 40 \times \text{tang.} 15°$, $= 10.717968$ feet. Now, since the area of any triangle is equal to its altitude multiplied by half its base, the area of a polygon will be equal to the altitude of one of the triangles which compose it, or to the radius of the inscribed circle, multiplied by half the number of its sides. The area of the polygon, therefore, into which the sails are projected, or the quantity of perpendicular surface impelled by the wind, will be $\frac{1}{2} ndb$, and, consequently, the force of impulsion F, upon this surface, will be $\frac{1}{2} ndbvv$, where vv is the square of the wind's velocity, to which the force of impulsion is always proportional. In the present case, then, the force F, which impels the sails, will be $6 \times 20 \times 10.717968 \times vv$; and if vv be the altitude which is due to the velocity of the wind, or the height through which a heavy body must fall in order to acquire that velocity, the force of impulsion F will be equal to the weight of a mass of air, whose volume is $1286.15616 \times vv$ cubic feet, or to $14\frac{1}{5}$ vv cubic feet of water; for water is about 800 times more dense than air; that is to 100 vv pounds avoirdupois, $62\frac{1}{5}$ of which are

equal to a cubic foot of water. But, in order that the machine may move, the momentum of friction 200 must be less than $0.235702 \times Fd$, or $0.235702 \times 100\,vv \times 20$; for when it is exactly this, the wind cannot move the machine, as appears from the first line of the table; or, what is the same thing, the height due to the velocity of the wind, viz. vv must be greater than 0.424, or $\frac{3}{7}$ of a foot, which corresponds to a velocity of 5.222, or $5\frac{2}{9}$. Unless, therefore, the celerity of the wind exceeds $5\frac{2}{9}$ feet per second, it will not be able to move the machine. These things being premised, let us now proceed to determine the construction and effect of the machine, upon the supposition that the momentum of friction is 200 pounds, and the velocity of the wind 10 feet per second. Now, vv, the height due to this velocity is $1\frac{3}{5}$ feet;[1] therefore the force of impulsion F is $= 100\,vv$ pounds, or $100 \times \frac{3}{5}$, or $=160$ pounds avoirdupois; and $Fd = 160 \times 20 = 3200$. But the momentum of friction, viz. Fd, multiplied into its co-efficent, should be equal 200 pounds; therefore, the co-efficient will be equal to $\frac{200}{Fd} = \frac{200}{3200} = 0.062500$, and the momentum of friction will be $0.062500\,Fd$. With this number enter the first column of the table, and you will find the angle of inclination corresponding to it to be about 63°; the

[1] The height answering to any velocity, and the velocity due to any height, may be found by the following theorems, in which v is the velocity, and h the height due to it; $v = 2\sqrt{16.087 \times h}$, hence $h = \frac{2vv}{129}$. See pp. 170, 171.

velocity of the sail's extremity $= \frac{1}{5} v$, or 6 feet per second; and the effect of the machine $= 0.05\ Fv = 0.05 \times 160\text{lb} \times 10 = 8\text{lb} \times 10$ feet, or 8 pounds raised through 10 feet in a second, which is equal to 1000 pounds raised through 288 feet in an hour. But the force of a man, according to Euler, is equal to 1000 pounds raised through 180 feet in an hour; therefore, the power of the machine, with a wind moving at the rate of 10 feet per second, is not equal to the power of two men.[a]

Let us now suppose that the wind-mill is driven by means of four rectangular sails, 18 feet in length and 4 in breadth, and that the momentum of friction and the radius of the sails are the same as before. Then the area of each sail will be 18×4, and the whole surface that is acted upon by the wind, will be $18 \times 4 \times 4 = 288$ square feet. But before we can determine the force which the wind exerts upon this surface, we must know its inclination to the wind; let us suppose this to be 70°, then the impetus of the wind upon the sails, or F, will be $= 288 \times \text{Sin.}70^2 \times vv$, in which v is the wind's velocity, or $F = 254\ vv$ cubic feet of air. If vv be the height due to the wind's velocity, di-

---

[a] Bernouilli makes the force of a man equal to 1000 pounds raised through 216 feet in an hour, Recueil des Prix, tom. viii; Coulomb makes it equal to 1000 pounds raised through 192 feet in an hour, Mem. de l'Acad. Paris, 1781, p. 74; and M. Schulze makes it 1000 pounds raised through 260 feet in an hour, Mem. de l'Acad. Berlin, 1783, p. 333. A very interesting discussion on the force of men, by Lambert, will be found in the Mem. de l'Acad. Berlin, 1776.

viding this quantity by 800, we will have $F=\frac{127}{400}vv$ cubic feet of water, and multiplying this by $62\frac{1}{2}$ we will have $F=19.8\ vv$ pounds avoirdupois. Now, let the velocity of the wind be 30 feet per second, the height vv due to this velocity will be 14 feet nearly; and, consequently $F=19.8\times14$, $=276$ pounds avoirdupois. Fd will therefore be $=5540$; and, since the whole momentum of friction is 200, the co-efficient of Fd will be $=\frac{200}{5540}=0.036101$, and the momentum of friction, expressed as the table requires, will be $=0.036101\ Fd$. Having entered the table with this number, the proper angle of inclination will be found to be $67\frac{1}{2}$ degrees. With this angle, instead of 70°, repeat the foregoing calculation, and after finding a new co-efficient to Fd, enter the table with it a second time, and you will have the proper angle of inclination, differing but little from the former, and likewise the velocity of the sails, and the effect of the machine.[3]

By comparing with the preceding theory the performance of the wind-mills examined by Coulomb and Lulofs,[4] it will be found that their power is almost double of that which is deduced from theory. This remarkable difference arises

---

[3] Those who wish to inquire farther into the theory of wind-mills, will find some excellent observations in D'Alembert's Traite de l'Equilibre et du Mouvement des Fluides, 1770, p. 396, § 368; or in his *Opuscules*, tom. v, p. 148, &c. and also by Lambert, in the Mem. de l'Acad. Berlin, 1775, p. 92.

[4] See pages 287, 288.

from a defect in the common hypothesis, which represents the force of impulsion as proportional to the square of the wind's velocity, and the square of the sine of the angle of incidence. When the wind impinges upon the sail, the air behind it is rarefied; this rarefaction increases with the velocity of the wind, and therefore the impulsion must be much greater than what is deduced from the common hypothesis. Euler supposes it to be twice as great; and, upon this supposition, has treated the subject more accurately in a subsequent memoir,[3] which, however, is too profound to be of any service to the practical mechanic.

Results of Smeaton's experiments.

These theoretical deductions, however interesting they may be, must yield in point of practical utility to the observations of our countryman Mr. Smeaton. From a variety of well conducted experiments, he found, that the common practice of inclining plane sails, from 72° to 75°, to the axis, was much more efficacious than the angle assigned by Parent, the effect being as 45 to 31. When the sails were weathered in the Dutch manner, that is, when their surfaces were concave to the wind, and when the angle of inclination increased towards their extremities, they produced a greater effect than when they were weathered either in the common way, or according to Maclaurin's theorem.[4] But when the sails were enlarged at their extremities, as represented at $\alpha\beta$, so that $\alpha\beta$ was one third of the radius ms, and αm to

Fig. 1.

[3] Recherches plus exactes sur l'effet des moulins à vent, Mem. de l'Acad. Berlin, 1766, vol. xii, p. 164.

[4] See page 262.

$m\beta$, as 5 to 3, their power was greatest of all, though the surface acted upon by the wind remained the same.[5] If the sails be farther enlarged, the effect is not increased in proportion to the surface; and, besides, when the quantity of cloth is great, the machine is much exposed to injury by sudden squalls of wind. In these experiments of Smeaton, the angle of weather varied with the distance from the axis; and he found, from several trials, that the most efficacious angles were those contained in the following table:

Parts of the radius *ms*, which is divided into 6 parts.	Angle with the axis.	Angle of weather.
1	72	18
2	71	19
3	72	18 middle
4	74	16
5	$77\frac{1}{2}$	$12\frac{1}{2}$
6	83	7

Supposing the radius *ms* of the sail, to be 30 feet, then the sail will commence at $\frac{1}{6}$ *ms*, or 5 feet from the axis, where the angle of inclination will be 72°. At $\frac{2}{6}$ *ms*, or 10 feet from the axis, the angle will be 71°, and so on.

[5] In the sails used in Portugal, the broad part is placed at the end of the arm. They are much more swoln than those of common wind-mills, and may be set to draw, in a manner similar to the stay sails of a ship.

On the Effect of Wind-mill Sails.

Effect of wind-mill sails,

The following maxims, deduced by Mr. Smeaton from his experiments, contain the best information which we have upon the effect of wind-mill sails, if we except a few experiments made by Coulomb.

According to Smeaton.

Maxim 1. The velocity of wind-mill sails, whether unloaded or loaded, so as to produce a maximum effect, is nearly as the velocity of the wind, their shape and position being the same.

Maxim 2. The load at the maximum is nearly, but somewhat less than, as the square of the velocity of the wind, the shape and position of the sails being the same.

Maxim 3. The effects of the same sails at a maximum, are nearly, but somewhat less than, as the cubes of the velocity of the wind.

Maxim 4. The load of the same sails, at the maximum, is nearly as the squares, and their effect as the cubes of their number of turns in a given time.

Maxim 5. When sails are loaded, so as to produce a maximum at a given velocity, and the velocity of the wind increases, the load continuing the same; 1st, The increase of effect, when the increase of the velocity of the wind is small, will be nearly as the squares of those velocities; 2dly, When the velocity of the wind is double, the effects will be nearly as 10 to $27\frac{1}{2}$; but, 3dly, When the velocities compared are more than double of that where the given load produces a maximum, the effects increase nearly in the simple ratio of velocity of the wind.

Maxim 6. In sails where the figure and position are similar, and the velocity of the wind the same, the number of turns, in a given time, will be reciprocally as the radius or length of the sail.

Maxim 7. The load, at a maximum, which sails of a similar figure and position will overcome, at a given distance from the centre of motion, will be as the cube of the radius.

Maxim 8. The effects of sails of similar figure and position are as the square of the radius.

Maxim 9. The velocity of the extremities of Dutch sails, as well as of the enlarged sails, in all their usual positions when unloaded, or even loaded to a maximum, are considerably quicker than the velocity of the wind.[6]

According to Coulomb.

M. Coulomb made a number of experiments on wind-mills that were employed to raise stampers for the purpose of bruising seed. He found that wind-mills having the dimensions formerly stated,[7] produced an effect equivalent to 1000 pounds raised through the space of 218 feet in a minute. The quantity of force, which was lost by the action of the wipers upon the stampers, was equal to 1000 pounds raised through $16\frac{1}{2}$ feet in a minute; and the friction was equivalent to 1000 pounds raised through $18\frac{1}{2}$ feet in a mi-

---

[6] Mr. Smeaton found, when the radius was 30 feet, that for every three turns of the Dutch sails in their common position, (when the angle of weather at the extremity is nothing), the wind-mill moves at the rate of two miles an hour; for every five turns in a minute of the Dutch sails, in their best position, the wind moves four miles an hour; and for every six turns in a minute of the enlarged sails, in their best position, the wind will move five miles an hour.

[7] See page 266.

nute. The total quantity of action, therefore, exerted by the wind in moving the machine, was equal to 1000 pounds elevated to the height of 253 feet in a minute, the velocity of the wind being 20 feet per second.

It appears, too, from Coulomb's experiments, that when the wind moved at the rate of 13 feet per second, the sails made 8 turns in a minute; when the velocity of the wind was 20 feet per second, the sails performed 13 turns in a minute; and when its velocity was 28 feet in a second, the sails made 17 turns in a minute.[8] By taking the medium of these results, it will be found, that the number of turns made by the sails in a minute, is to the number of feet which the wind moves in a second, as 1 to 1.6. Hence, when the velocity of the sails is given, that of the wind may be easily determined.

M. Lulofs of Leyden examined a Dutch wind-mill, which was employed to drain marshes, and found that when the wind moved at the rate of 30 feet per second, it was capable of raising 1500 cubic feet of water, 4 feet high, in a minute. The wind-mill had four rectangular sails, each being 43 feet long, and $95\frac{1}{2}$ feet broad; and the mean angle of weather was 17 degrees.

On Horizontal Wind-mills.

Horizontal wind-mills.

A variety of opinions have been entertained respecting the relative advantages of horizontal and vertical wind-mills. Mr. Smeaton, with great justice, gives a decided preference to the latter; but, when he asserts that horizontal wind-mills

[8] Mem. de l'Acad. Paris, 1781, p. 81.

have only $\frac{1}{8}$ or $\frac{1}{10}$ of the power of vertical ones, he certainly forms too low an estimate of their power. Mr. Beatson, on the contrary, who has received a patent for the construction of a new horizontal wind-mill, seems to be prejudiced in their favour, and greatly exaggerates their comparative value. From an impartial investigation, it will probably appear, that the truth lies between these two opposite opinions; but before entering on this discussion, we must first consider the nature and form of horizontal wind-mills.

In Fig. 3 of Plate VI, *CK* is the perpendicular axis, or windshaft, which moves upon pivots. Four cross bars *CA*, *CD*, *IB*, *FG*, are fixed to this arbor, which carry the frames *APIB*, *DEFG*. The sails *AI*, *EG*, are stretched upon these frames, and are carried round the axis *CK*, by the perpendicular impulse of the wind. Upon the axis *CK* a toothed wheel is fixed, which gives motion to the particular machinery that is employed. In the figure only two sails are represented; but there are always other two placed at right angles to these. Now, let the sails be exposed to the wind, and it will be evident that no motion will ensue; for the force of the wind, upon the sail *AI*, is counteracted by an equal and opposite force, upon the sail *EG*. In order, then, that the wind may communicate motion to the machine, the force upon the returning sail *EG* must either be removed by screening it from the wind, or diminished by making it present a less surface when returning against the wind. The first of these methods is adopted in Tartary, and in some provinces of Spain; but is ob-

Plate VI, Fig. 3. App.

Common method of bringing back the sails against the wind.

jected to by Mr. Beatson, from the inconvenience and expence of the machinery and attendance requisite for turning the screens into their proper positions. Notwithstanding this objection, however, I am disposed to think that this is the best method of diminishing the action of the wind upon the returning sails, for the moveable screen may easily be made to follow the direction of the wind, and assume its proper position, by means of a large wooden weather-cock, without the aid either of men or machinery. It is true, indeed, that the resistance opposed to the returning sails is not completely removed; but it is at least as much diminished as it can be by any method hitherto proposed. Besides, when this plan is resorted to, there is no occasion for any moveable flaps and hinges, which must add greatly to the expence of every other method.

Beatson's method.

The mode of bringing the sails back against the wind, which Mr. Beatson invented, is, perhaps, the simplest and best of the kind. He makes each sail *AI* to consist of six or eight flaps, or vanes, *AP b* 1, *b* 1 *c* 2, &c. moving upon hinges, represented by the dark lines *AP*, *b* 1, *c* 2, &c. so that the lower side *b* 1, of the first flap overlaps the hinge, or highest side, of the second flap, and so on. When the wind, therefore, acts upon the sail *AI*, each flap will press upon the hinge of the one immediately below it, and the whole surface of the sail will be exposed to its action. But when the sail *AI* returns against the wind, the flaps will revolve upon their hinges, and present only their edges to the wind, as is represented at *EG*, so that the resistance occasioned by the return of

the sail must be greatly diminished, and the motion will be continued, by the superiority of force exerted upon the sails, in the position *AI*. In computing the force of the wind upon the sail *AI*, and the resistance opposed to it by the edges of the flaps in *EG*, Mr. Beatson finds, that, when the pressure upon the former is 1872 pounds, the resistance opposed by the latter is only about 36 pounds, or $\frac{1}{52}$ part of the whole force; but he neglects the action of the wind upon the arms *CA*, &c. and the frames which carry the sails, because they expose the same surface, in the position *AI*, as in the position *EG*. This omission, however, has a tendency to mislead us in the present case, as we shall now see, for we ought to compare the whole force exerted upon the arms, as well as the sail, with the whole resistance which these arms and the edges of the flaps oppose to the motion of the wind-mill. By inspecting Fig. 3, it will appear, that if the force, upon the edges of the flaps, which Mr. Beatson supposed to be 12 in number, amounts to 36 pounds, the force spent upon the bars *CD*, *DG*, *GF*, *FE*, &c. cannot be less than 60 pounds. Now, since these bars are acted upon with an equal force, when the sails have the position *AI*, 1872+60 =1932 will be the force exerted upon the sail *AI*, and its appendages, while the opposite force, upon the bars and edges of the flaps, when returning against the wind will be 36+60=96 pounds, which is nearly $\frac{1}{20}$ of 1932, instead of $\frac{1}{52}$ as computed by Mr. Beatson. Hence we may see the advantages which will probably arise from using a screen for the returning sail, instead of moveable flaps, as it will

Resistance of the returning sails.

Fig. 3.

preserve not only the sails, but the arms and the frame which support it, from the action of the wind.[6]

Comparison between vertical and horizontal wind-mills.

We shall now conclude this article with a few remarks on the comparative power of horizontal and vertical wind-mills. It was already stated, that Mr. Smeaton rather under-rated the former, while he maintained that they have only $\frac{1}{8}$ or $\frac{1}{10}$ the power of the latter. He observes, that when the vanes of a horizontal and vertical mill are of the same dimensions, the power of the latter is four times that of the former; because, in the first case, only one sail is acted upon at once; while, in the second case, all the four receive the impulse of the wind. This, however, is not strictly true, since the vertical sails are all oblique to the direction of the wind. Let us suppose that the area of each sail is 100 square feet; then the power of a horizontal sail will be 100, as only one sail is acted upon, and as its surface is perpendicular to the wind, and the power of a vertical sail may be called $100 \times \text{sine}^2 70° = 88$ nearly, ($70°$ being the common angle of inclination;) but since there are four vertical sails, the power of them all will be $4 \times 88 = 352$; so that the power of the horizontal sail is to that of the four vertical ones, as 1. to 3.52, and not as 1 to 4 accord-

[6] The sails of horizontal wind-mills are sometimes fixed, like float-boards, on the circumference of a large drum or cylinder. These sails move upon hinges so as to stand at right angles to the drum, when they are to receive the impulse of the wind; and when they return against it, they fold down upon its circumference. See Repertory of Arts, vol. vi.

ing to Mr. Smeaton. But Mr. Smeaton also observes, that if we consider the farther disadvantage which arises from the difficulty of getting the sails back against the wind, we need not wonder if horizontal wind-mills have only about $\frac{1}{8}$ or $\frac{1}{10}$ the power of the common sort. We have already seen, that the resistance occasioned by the return of the sails, amounts to $\frac{1}{20}$ of the whole force which they receive; by subtracting $\frac{1}{10}$, therefore, from $\frac{1}{3.52}$ we will find that the power of horizontal wind-mills is only $\frac{1.81}{4.46}$, or little more than $\frac{1}{4}$ less than that of vertical ones. This calculation proceeds upon a supposition, that the whole force exerted upon vertical sails is employed in turning them round the axis of motion; whereas, a considerable part of this force is lost in pressing the pivot of the axis, or windshaft, against its gudgeon. Mr. Smeaton has overlooked this circumstance, otherwise he could never have maintained that the power of four vertical sails was quadruple the power of one horizontal sail, the dimensions of each being the same. Taking this circumstance into the account, we cannot be far wrong in saying, that, in theory at least, if not in practice, the power of a horizontal wind-mill, is about $\frac{1}{3}$ or $\frac{1}{4}$ of the power of a vertical one, when the quantity of surface and the form of the sails is the same, and when every part of the horizontal sails have the same distance from the axis of motion as the corresponding parts of the vertical sails. But if the horizontal sails have the position *AI*, *EG*, instead of the position *CA d m*, *CD o n*, their power will be greatly increased, though the quantity of surface is the same; because the part *CP 3 m* being Fig. 3.

transferred to *BI 3 d*, has much more power to turn the sails. I would recommend it also to the mechanic, to furnish horizontal wind-mills with *six* or *eight sails;* for, as it happens in the analogous case of water-mills, the wind bends round their extremties, and impinges upon those parts of the sail immediately behind, which are not expoſed to the direct action of the wind. Having these methods, therefore, of increasing the power of horizontal sails, we would encourage every attempt to improve their construction, as not only laudable in itself, but calculated to be of essential utility in a commercial country.

MECHANICS.

ON WHEEL CARRIAGES.

MR. FERGUSON, in his fourth lecture, has treated the subject of wheel-carriages with great perspicuity, and has communicated much practical information of considerable importance. Many of the prejudices, however, which he has there encountered, and several others which have escaped his notice, still continue to prevail in this country; and as some of these have been countenanced even by ingenious men, we are laid, under a more urgent necessity of attempting to develope the source of their errors, and of regulating the practice of the mechanic by the deductions of theory. The very assistance which theory has, in this case, furnished to the artist, has been rendered not only useless, but injurious, by an erroneous application; and we may safely affirm, that there is no species of machinery where less science is displayed than in the construction and position of carriage-wheels. The few imperfect hints, which we are able to convey upon this subject, regard the formation and position of the wheels, the line of traction, Wheel carriages.

and the method of disposing the load which is to be drawn. To some of these we solicit the reader's attention, as being entirely new, and apparently leading to consequences of high importance.

On the Formation of Carriage Wheels.

Wheels act as mechanical powers.

When the wheels of carriages either move upon a level surface, or overcome obstacles which impede their progress, they act as mechanical powers, and may be reduced to levers of the first kind. In order to elucidate this remark, which is of great importance in the present discussion, let A be the centre, and BCN the circumference of a wheel 6 feet in diameter, and let the impelling power P, which is attached to the extremity of a rope ADP, passing over the pulley D, act in the horizontal direction AD. Then, if the wheel is not affected by friction, it will be put in motion upon the level surface MB, when the power P is infinitely small. For since the whole weight of the wheel rests on the ground at the point B, which is the fulcrum of the lever AB, the distance of the weight from the centre of motion will be nothing, and therefore the mechanical energy of the smallest power P, acting at the point A, with a length of lever AB, will be infinitely great when compared with the resistance of the weight to be raised; and this will be the case however small be the lever AB, and however great be the weight of the wheel. —But as the wheels of carriages are constantly meeting with impediments, let C be an obstacle 6 inches high, which the wheel is to surmount. Then the spoke AC will represent the lever, C

Plate II, Fig. 5. App.

its fulcrum, *AD* the direction of the power; and if the wheel weighs 100 pounds, we may represent it by a weight *W* fixed to the wheel's centre *A*, or to the extremity of the lever *CA*, and acting in the perpendicular direction *AB*, in opposition to the power *P*. Now, the mechanical energy of the weight *W* to pull the lever round its fulcrum in the direction *AE*, is represented by *CE*, while the mechanical energy of an equal weight *P* to pull it in the opposite direction *AF*, is represented by *CF*; an equilibrium, therefore, will be produced, if the power *P* is to the weight *W* as *CE* to *CF*, or as the sine is to the cosine of an angle, whose versed sine is equal to the height of the obstacle to be surmounted; for *EB*, the height of the mound *C*, is the versed sine of the angle *BAC*, and *CE* is the sine, and *CF* the cosine of the same angle. In the present case, where *EB* is 6 inches, and *AB* 3 feet, *EB*, the versed sine, will be 1666, &c. when *AB* is 1000; and, consequently, the angle *BAC* will be 33° 33′, and *CE* will be to *EF* as 52 to 83, or as 66 to 100. A weight *P*, therefore, of 66 pounds, acting in a horizontal direction, will balance a wheel 6 feet diameter, and 100 pounds in weight, upon an obstacle 6 inches high; and a small additional power will enable it to surmount that obstacle. But if the direction *AD* of the power be inclined to the horizon, so that the point *D* may rise towards *H*, the line *FC*, which represents the mechanical energy of *P*, will gradually increase, till *DA* has reached the position *HA*, perpendicular to *AC*, where its mechanical energy, which is now a maximum, is represented by *AC* the radius of the wheel; and since *EC* is to *CA* as 53 to 100, a little more than 53 pounds will be

sufficient for enabling the wheel to overcome the obstacle.

Proceeding in this way, it will be found, that the power of wheels to surmount eminences increases with their diameter, and is directly proportional to it, when their weight remains the same, and when the direction of the power is perpendicular to the lever which acts against the obstacle. Hence we see the great advantages which are to be derived from large wheels, and the disadvantages which attend small ones. There are some circumstances, however, which confine us within certain limits in the use of large wheels. When the radius *AB* of the wheel is greater than *DM* the height of the pulley, or of that part of the horse to which the rope or pole *DA* is attached, the direction of the power, or the line of traction, *AD* will be oblique to the horizon, as *Ad*, and the mechanical energy of the power will be only *Ae*, whereas it was represented by *AE* when the line of traction was in the horizontal line *DA*. Whenever the radius of the wheel, therefore, exceeds *four feet and a half*, the height of that part of the horse, to which the traces should be attached,[1] the line of traction *AD* will incline to the horizon, and, by declining from the perpendicular *AH*, its mechanical effort will be diminished; and, since the load rests upon an inclined plane, the trams, or poles, of the cart will rub against the flanks of the horse, even in level roads, and

Advantages of large wheels.

[1] According to M. Couplet, the distance of this part of the horse from the ground is generally *three feet and a half*, (Mem. de l'Acad. Paris, 1703, 8vo, p. 75). In horses of a common size, however, it is seldom below *four feet and a half*.

still more severely in descending ground. Notwithstanding this diminution of force, however, arising from the unavoidable obliquity of the impelling power, wheels exceeding four and a half feet radius have still the advantage of smaller ones; but their power to overcome resistances does not increase so fast as before. Hitherto we have supposed the weight of the large and small wheels to be the same; but it is evident, that, when we augment their diameter, we add greatly to their weight; and, by thus increasing the load, we sensibly diminish their power.

From these remarks, we see the superiority of great wheels to small ones, and the particular circumstances which suggest the propriety of making the wheels of carriages less than $4\frac{1}{2}$ feet radius. Even this size is too great, as we shall afterwards shew, when speaking of the line of traction; and we may safely assert, that they ought never to exceed 6 feet in diameter, and should never be less than $3\frac{1}{2}$ feet. When the nature of the machine will permit, large wheels should always be preferred, and small ones should never be adopted, unless we are compelled to employ them by some unavoidable circumstances in the construction.[a] This maxim, which has

[a] For the advantage of those who wish to study this subject with greater attention, and with the view also of recommending the use of large wheels, we shall subjoin the following references to the works of eminent men, who have held the same opinion upon this point; Mersennus' Geom. p. 459; Herigon, Mecan. prob. xvi, Schol.; Wallis' Mecan. c. vii, prob. 3, Schol. § 15; Phil. Trans. vol. xv, p. 856; Camus' Traite des Forces Mouvantes, prop. xxviii, xxx; and Deparcieux sur le Tirage des Chevaux, Mem. de l'Acad. Paris, 1760, p. 263, 4to.

The fore-wheels of carriages too small.

been inculcated by every person who has written on the subject, seems to have been strangely neglected by the practical mechanics of this country. The fore-wheels of our carriages are still unaccountably small, and we have seen carts moving upon wheels scarcely *fourteen* inches in diameter. The workman, indeed, will tell us, that, in the one case, the wheels are made small for the conveniency of turning, and, in the other, for facilitating the loading of the cart; but how trifling are these advantages when compared with that diminution of the horses' power, which necessarily results from the use of small wheels. A convenient place for turning with large fore wheels, which is not frequently required, may be procured, by going to the end of a street; and a few additional turns of a windlass will be sufficient to raise the heaviest load into carts which are mounted upon high wheels. It has been objected against large fore-wheels, that the horses, when going down a declivity, cannot so easily prevent the carriages from running downwards; but this very objection, trifling as it is, is a plain confession that large fore-wheels are advantageous, both in horizontal and inclined planes, otherwise their tendency downwards would not be greater than that of small ones.[3]

---

[3] From some experiments on wheel carriages, Mr. Walker conceives that the greatest advantage was obtained when the hind wheels were 5 feet 6 inches in diameter, and the fore ones 4 feet 8 inches, whereas the large wheels are, in general, only 4 feet 8 inches, and the small ones 3 feet 8 inches.—System of Familiar Philosophy, vol. i, p. 130.

Having thus ascertained the superiority of large wheels, we are now to determine on the shape which ought to be assigned them. Every person, who is not influenced by preconceived notions, would affirm, without hesitation, that, if the wheels are to consist of solid wood, they should be portions of a cylinder; and if they are to be composed of naves, spokes, and fellies, that the rim of the wheel ought to be cylindrical, and the spokes perpendicular to the naves. But some men, desirous of being inventors, have renounced this simple shape, and adopted the more complicated form of Fig. 6, where the rim *BsrA* is conical, and the spokes inclined to the naves.[4] Philosophers, too, have found a reason for this change, and it has been adopted in every country, more from the authority of names than the force of argument.[5] It is with the greatest diffidence, however, that we presume to contradict a practice which has been defended by the most celebrated mechanics; but we trust that the reader's indulgence will be proportioned to the solidity of the reasons upon which this difference of sentiment is founded.

On the form of the wheels.

Cylindrical wheels.

Plate II, Fig. 6. App.

Conical wheels.

The form represented in Fig. 6, then, is liable to two objections, namely, the inclination of the spokes, and the conical figure of the

Advantages and disadvantages of concave dishing wheels.

[4] This inclination is about 1 inch out of 11, or *A* is generally 3 inches when the diameter of the wheel is $5\frac{1}{2}$ feet.

[5] I have seen some carriage wheels, in which one half of the spokes were inclined about one fourth more than the other half, every alternate spoke being equally inclined to the axis. The reasons for such a construction I have not been able to discover.

rim. When the spokes are inclined to the nave, the wheels are said to be concave, or dishing, and they are recommended by Mr. Ferguson, and every other writer on mechanics, from the numerous advantages which are said to attend them. By extending the base of the carriage, they prevent it from being easily overturned, they hinder the fellies from rubbing against the load or the sides of the cart, and when one wheel falls into a rut; and, therefore, supports more than one half of the load, the spokes are brought into a perpendicular position, which renders them more capable of supporting this additional weight. Now, it is evident, that the second of these advantages is very trifling, and may be obtained when it is wanted, by interposing a piece of board between the wheel and the load. The other two advantages exist only in very bad roads; and if they are necessary, which we very much question, in a country like this, where the roads are so excellently made, and so regularly repaired, they can easily be procured by making the axle-tree a few inches longer, and increasing the strength of the spokes. But it is allowed, on all hands, that perpendicular spokes are preferable on level ground. The inclination of the spokes, therefore, which renders concave wheels advantageous in rugged and unequal roads, renders them disadvantageous when the roads are in good order; and where the good roads are more numerous than the bad ones, as they certainly are in this country, the disadvantages of concave wheels must overbalance their advantages. It is true, indeed, that in concave wheels, the spokes are in their strongest position when they are exposed to the severest strains; that is, when one wheel is in a deep rut, and

Inclination of the spokes disadvantageous in general.

sustains more than one half of the load; but it is equally true, that in level ground, where the spokes are in their weakest position, a less severe strain, by continuing for a much longer time, may be equally, if not more, detrimental to the wheel.[s]

Upon these observations, we might rest the opinion which we have been maintaining, and appeal for its truth to the judgment of every intelligent and unbiassed mind; but we shall go a step farther, and endeavour to shew, that concave dishing wheels are more expensive, more injurious to the roads, more liable to be broken by accidents, and less durable, in general, than those wheels in which the spokes are perpendicular to the naves. By inspecting Fig. 6, it will appear, that the whole of the pressure, which the wheel *AB* sustains, is exerted along the inclined spoke *ps*, and therefore acts obliquely upon the level ground *nD*, whether the rims be conical or cylindrical. This oblique action must necessarily injure the roads, by loosening the stones more between *B* and *D* than between *B* and *n*; and if the load were sufficiently great, the stones would start up between *s* and *D*. The texture of the roads, indeed, is sufficiently firm to prevent this from

Concave dishing wheels more injurious to the roads.

Plate 14. Fig. 6.

[s] Mr. Anstice, in his excellent treatise on wheel carriages, recommends concave wheels; but candidly allows, that 'some disadvantages attend this contrivance; for the 'carriage thus takes up more room upon the road, which 'makes it more unmanageable; and when it moves upon 'plain ground, the spokes not only do not bear perpendicularly, by which means their strength is lessened, but 'the friction upon the nave and axle is made unequal, and 'the more so the more they are dished.'

talking place; but, in consequence of the oblique pressure, the stones between *s* and *D* will, at least, be loosened, and, by admitting the rain, the whole of the road will be materially damaged. But when the spokes are perpendicular to the nave, as *pn*, and when the rims *mA*, *nB* are cylindrical, or parallel to the ground, the weight sustained by the wheel will act perpendicularly upon the road, and however much that weight is increased, its action can have no tendency to derange the materials of which it is composed; but is rather calculated to consolidate them, and render the road more firm and durable.

And more expensive.

It was observed, that concave wheels are more expensive than plain ones. This additional expence arises from the greater quantity of wood and workmanship which the former require; for, in order that dishing wheels may be of the same perpendicular height as plane ones, the spokes of the former must exceed in length those of the latter, as much as the hypothenuse *oA* of the triangle *oAm* exceeds the side *om*; and therefore the weight and the resistance of such wheels must be proportionally great. The inclined spokes, too, cannot be formed nor inserted with such facility as perpendicular ones. The extremity of the spoke which is fixed into the nave is inserted at right angles to it, in the direction *op*, and if the rims are cylindrical, the other extremity of the spoke should be inserted in a similar manner, while the intermediate portion has an inclined position. There are, therefore, two flexures or bendings in the spokes of concave wheels, which require them to be formed out of a larger piece of wood than if they had no such

Plate II, Fig. 6.

flexures, and render them liable to be broken by any sudden strain at the points of flexure.

In the comparison which we have now been stating, between the merits of concave and plane wheels, we have taken for granted what has been uniformly stated by the advocates of the former, that when one of the wheels falls into a rut or surmounts an eminence, the lowest sustains much more than one half of the load. Now, though it be true that the lowest wheel supports more than one half of the load, yet we deny that it bears so much as has generally been supposed,[6] and we shall prove the assertion, by pointing out a method of ascertaining the additional weight which is transferred to one wheel by any given elevation of the other. Let *AMOC* represent a cart loaded with coals or lime, or any other material which fills it to the top, and let *AB* be a horizontal line on the surface of a level road. Then, if the wheel *A* remains fixed, and the wheel *C* raised to any height, its lower extremity *C* will describe the arch *BO* round the centre *A*, while the centre of gravity *D* of the whole machine and load will move in the arch *NM* round the same centre. Now, let us suppose that *BC* is an eminence which the wheel *C* has to surmount, and that it has arrived at the top of it; it is required to find what proportion of the load is sustained by each wheel. Bisect the horizontal line *AB* in *e*, and from *e* draw *ed* at right angles to *AB*, and meet-

Plate II, Fig. 7.

Proportion of the load borne by each wheel when one of them is surmounting an eminence.

[6] Mr. Ferguson observes, (vol. i, p. 116), that the wheel, which falls into the rut, bears *much more* of the weight than the other; and, a little afterwards, that it bears *most of* the weight of the load.

ing the arch *NM* in the point *d*, join *AC*, *A d*, *AD*, and from the point *D* let fall the perpendicular *DE*. The point *d* will be the centre of gravity of the load when the points *C* and *B* coincide; that is, when the wheels are resting on the horizontal plane *AB*. For since, in this case, each wheel bears an equal part of the weight, the line of direction, or a vertical line passing through the centre of gravity, will cut the base *AB*, so that *Ae* will be to *eB* as the weight upon the wheel *A* to the weight upon *C*; and, therefore, *ed* will be the line of direction, and the point *d*, where it cuts the circle *NM*, in which the centre of gravity moves, will be the centre of gravity of the load in a horizontal position. Now as *D* is the centre of gravity when the cart is in its inclined position, the perpendicular *DE* will be the line of direction, and the weight sustained by the wheel *A* will be to that sustained by *C* as *EB* to *EA*, or *Ee* will represent the additional weight transferred upon *A*, when *AB* represents the whole of the load. But *Ee* can be easily determined for any value of *BC*, the height of the obstacle. For, while the point *C* moves from *B* to *C*, the centre of gravity rises from *d* to *D*, so that *Dd* and *BC* are similar arches, and *AB*, *Ad*, *BC*, are known, *AB* being the distance between the wheels, and *Ad* being equal to the square root of the sum of the squares of *Ae*, the half of that distance, and *de* the height of the centre of gravity (Eucl. 1, 47), and *BC* being the height of the eminence. But since *de*, the sine of the arch *dN*, is known, *dN* is known, and also *DN*, the sum of the two arches, *Dd*, *dN*. The cosines *AE*, *Ae*, of the arches *DN*, *dN*, are therefore known, and consequently *Ee*, their difference may be determin-

ed; or, otherwise, *Ee* is the difference of the versed sines *EN*, *eN*, of the same arches. Let us now take a particular value of *BC*, or rather of *Co*, the perpendicular height of the eminence, and call it 12 inches; for even in the worst roads there are few eminences which are greater than this. Let *AB*, the distance between the wheels, be 6 feet, and *de*, the height of the centre of gravity, 4 feet, then *Co* will be $\frac{1}{6}$ of the radius *AB*; and making *AB*=1000000, *CO* will be 166666, which, being the natural sine of the arch *BC*, gives 9° 35′ for the arch *BC*, and for the similar arch *Dd*. Now, since *Ae* is 3 feet, and *de* 4 feet, the sum of their squares will be 25, and its square root 5 will be the length of the hypothenuse *Ad*, or the radius of the circle *NDM*. Then, making *Ad* radius, or 1000000, *de*, the sine of the arch *dN*, will be $\frac{4}{5}$ of it, or 800000; and therefore the arch *dN* will be 53° 8′, and the arch *DN*, 62° 43′. But *AE*, the cosine of the arch *DN*, is = 458391 = or $\frac{46}{100}$, nearly, of *AD*=5 feet, and is therefore equal to 2 feet 8 inches and 6 tenths; consequently *Ee*=*Ae*—*AE* will be 8 inches and 4 tenths, which is nearly $\frac{1}{9}$ of *AB*. We may therefore conclude, that the additional weight sustained by the wheel *A*, while the other wheel is rising over an obstacle 12 inches in perpendicular height, is $\frac{1}{9}$ only of the whole load; or that $\frac{2}{9}$ of the pressure upon the wheel *C* is transferred to the wheel *A*, while surmounting an eminence 12 inches high. If one of the wheels falls into a rut 12 inches deep, the same conclusion will result; and we may affirm, that as the ruts and eminences which are generally to be met with even in bad roads, are for the most part much less than 12 inches in depth or height, such a

small proportion of the load will be transferred to the lowest wheel, that there is no necessity for inclining the spokes in order to sustain the additional weight. When the cart is loaded with stones, or any heavy substance, the centre of gravity will be lower than *d*, so that a less proportion of the weight will be transferred to one wheel by the elevation of the other; and when it is loaded with hay, or any light material, the lowest wheel will sustain a greater proportion of the load.

Concave wheels easily injured.

We shall now dismiss the subject of concave wheels with one observation more, and we beg the reader's attention to it, because it appears to be decisive of the question. The obstacles which carriages have to encounter, are almost never spherical protuberances, which permit the elevated wheel to resume by degrees its horizontal position. They are generally of such a nature, that the wheel is instantaneously precipitated from their top to the level ground. Now the momentum with which the wheel strikes the ground is very great, arising from a successive accumulation of force. The velocity of the wheel *C* is considerable when it reaches the top of the eminence, and while it is tumbling into the horizontal line *AB*, the centre of gravity is falling through the arch *Dd*, and the wheel *C* is receiving gradually that proportion of the load which was transferred to *A*, till, having recovered the whole, it impinges against the ground with great velocity and force. But in concave wheels, the spoke which then strikes the ground is in its weakest position, and therefore much more liable to be broken by the impetus of the fall, than the spokes of the lowest wheel by the mere transference of additional weight. Whereas if the

Fig. 7.

spokes be perpendicular to the nave, they receive this sudden shock in their strongest position, and are in no danger of giving way to the strain.

In the preceding observations, we have supposed the rims of the wheels to be cylindrical, as *AC*, *BD*. In concave wheels, however, the rims are uniformly made of a conical form, as *Ar*, *Bs*, which not only increases the disadvantages that we have ascribed to them, but adds many more to the number. Mr. Cumming, in a late treatise on wheel carriages, solely devoted to the consideration of this single point, has shewn, with great ability, the disadvantages of conical rims, and the propriety of making them cylindrical; but we are of opinion that he has ascribed to conical rims several disadvantages which arise chiefly from an inclination of the spokes. He insists much upon the injury done to the roads by the use of conical rims; yet, though we are convinced that they are more injurious to pavements and highways than cylindrical rims, we are equally convinced, that this injury is occasioned chiefly by the oblique pressure of the inclined spokes. The defects of conical rims are so numerous and palpable, that it is wonderful how they should have been so long overlooked. Every cone that is put in motion upon a plane surface, will revolve round its vertex, and if force is employed to confine it to a straight line, the smaller parts of the cone will be dragged along the ground, and the friction greatly increased. Now when a cart moves upon conical wheels, one part of the cone rolls while the other is dragged along, and though confined to a rectilineal direction by external force, their natural tendency to revolve round

PLATE II, Fig. 6.

Conical rims disadvantageous.

their vertex occasions a great and continued friction upon the linch pin, the shoulder of the axletree, and the sides of deep ruts.

The shape of the wheels being thus determined, we must now attend to some particular parts of their construction. The iron plates of which the rims are composed should never be less than 3 inches in breadth, as narrower rims sink deep into the ground, and therefore injure the roads and fatigue the horses. Mr. Walker, indeed, attempts to throw ridicule upon the act of parliament which enjoined the use of broad wheels, but he does not assign any sufficient reason for his opinion, and ought to have known, that several excellent and well devised experiments were lately instituted by Boulard and Margueron,[7] which evinced, in the most satisfactory manner, the great utility of broad wheels. Upon this subject an observation occurs to us which has not been generally attended to, and which appears to remove all the objections which can be urged against broad rims. When any load is supported upon two points, each point supports one half of the weight; if the points are increased to four, each will sustain one fourth of the load, and so on, the pressure upon each point of support diminishing as the number of points increases. If a weight, therefore, is supported by a broad surface, the points of support are infinite in number, and each of them will bear an infinitely small portion of the load; and, in the same way, every finite portion of this surface

Utility of broad wheels.

[7] The memoir which contains an account of these experiments, was presented to the Academy of Lyons, and is published in the Journal de Physique, tom. xix, p. 424.

will sustain a part of the weight inversely proportional to the number of similar portions which the surface contains. Let us now suppose that a cart, carrying a load of 16 hundred weight, is supported upon wheels whose rims are 4 inches in breadth, and that one of the wheels passes over 4 stones, each of them an inch broad, and equally high, and capable of being pulverized only by a pressure of 400 weight. Then, as each wheel sustains one half of the load, and as the wheel which passes over the stones has 4 points of support, each stone will bear a weight of 200 weight, and therefore will not be broken. But if the same cart, with rims only 2 inches in breadth, should pass the same way, it will cover only 2 of the stones; and the wheel having now only two points of support, each stone will be pressed with a weight of 400 weight, and will therefore be reduced to powder. Hence we may infer, that narrow wheels are, in another point of view, injurious to the roads, by pulverizing the materials of which they are composed.

Practical remarks.

As the rims of wheels wear soonest at their edges, they should be made thinner in the middle, and ought to be fastened to the fellies with nails of such a kind, that their heads may not rise above the surface of the rim. In some military waggons, we have seen the heads of these nails rising an inch above the rims, which not only destroys the pavements of streets, but opposes a continual resistance to the motion of the wheel. If these nails were 8 in number, the wheel would experience the same resistance as if it had to surmount 8 obstacles, 1 inch high, during every revolution. The fellies on which the rims are fixed should, in carriages, be $3\frac{1}{4}$ inches deep, and in waggons 4 inches. The naves

should be thickest at the place where the spokes are inserted, and the holes in which the spokes are placed should not be bored quite through, as the grease upon the axle-tree would insinuate itself between the spoke and the nave, and prevent that close adhesion which is necessary to the strength of the wheel.

On the Position of the Wheels.

Position of the wheels.

It must naturally occur to every person reflecting upon this subject, that the axle-trees should be straight, and the wheels perfectly parallel, so that they may not be wider at their highest than at their lowest point, whether they are of a conical or a cylindrical form. In this country, however, the wheels are always made concave, and the ends of the axle-trees are *universally* bent downwards, in order to make them spread at the top and approach nearer below. In some carriages which we have examined, where the wheels were only 4 feet 6 inches in diameter, the distance of the wheels at top was fully 6 feet, and their distance below only 4 feet 8 inches. By this foolish practice, the very advantages which may be derived from the concavity of the wheels are completely taken away, while many of the disadvantages remain; more room is taken up in the coach-house, and the carriage is more liable to be overturned, by the contraction of its base.

Disadvantages of bent axle-trees.

With some mechanics it is a practice to bend the ends of the axle-trees forwards, and thus make the wheels wider behind than before. This blunder has been strenuously defended by Mr. Henry Beighton, who maintains that wheels in this position are more favourable for turning,

since, when the wheels are parallel, the outermost would press against the linch-pin, and the innermost would rub against the shoulder of the axle-tree. In rectilineal motions, however, these converging wheels engender a great deal of friction, both on the axle and the ground, and must therefore be more disadvantageous than parallel ones. This, indeed, is allowed by Mr. Beighton; but he seems to found his opinion upon this principle, that as the roads are seldom straight lines, the wheels should be more adapted for curvilineal than for rectilineal motion. In what part of the world Mr. Beighton has examined the roads we cannot say; but of this we are sure, that there are no such flexures in the roads of Scotland.

On the Line of Traction, and the Method by which Horses exert their Strength.

Line of traction.

M. Camus, a gentleman of Lorrain, was the first person who treated on the line of traction.[8] He attempted to shew that it should be a horizontal line, or rather that it should always be parallel to the ground on which the carriage is moving, both because the horse can exert his greatest strength in this direction, and because the line of draught being perpendicular to the vertical spoke of the wheel, acts with the largest possible lever. M. Couplet,[9] however, considering that the roads are never perfectly level,

---

[8] Traite des Forces Mouvantes, p. 387.

[9] Reflexions, sur le tirage des charrettes, Mem. de l'Acad. Paris, 1733, 8vo, pp. 75, 86.

and that the wheels are constantly surmounting small eminences, even in the best roads, recommends the line of traction to be oblique to the horizon. By this means the line of draught *HA*, (which is by far too much inclined in the figure), will in general be perpendicular to the lever *AC* which mounts the eminence, and will therefore act with the longest lever when there is the greatest necessity for it. We ought to consider also, that when a horse pulls hard against any load, he always brings his breast nearer the ground, and therefore it follows, that if a horizontal line of traction is preferable to all others, the direction of the traces should be inclined to the horizon when the horse is at rest, in order that it may be horizontal when he lowers his breast and exerts his utmost force.

PLATE II, Fig. 5.

How horses exert their strength.

The particular manner, however, in which living agents exert their strength against great loads, seems to have been unknown both to Camus and Couplet, and to many succeeding writers upon this subject. It is to M. Deparcieux, an excellent philosopher and ingenious mechanic, that we are indebted for the only accurate information with which we are furnished; and we are sorry to see, that philosophers who flourished after him have overlooked his important instructions. In his Memoir on the draught of horses,[1] he has shewn, in the most satisfactory manner, that animals draw by their weight, and not by the force of their muscles. In four-footed animals, the hinder feet is the fulcrum of the lever by which their weight acts against the load, and

[1] Sur le Tirage des Chevaux, published in the Mem. de l'Acad. Paris, 1760, 4to, p. 263, 8vo, p. 275.

when the animal pulls hard, it depresses its chest, and thus increases the lever of its weight, and diminishes the lever by which the load resists its efforts. Thus, let *P* be the load, *DA* the line of traction, and let us suppose *FC* to be the hinder leg of the horse, *AF* part of its body, *A* its chest or centre of gravity, and *CE* the level road. Then *AFC* will represent the crooked lever by which the horse acts, which is equivalent to the straight one *AC*. But when the horse's weight acts downwards at *A*,[a] round *C* as a centre, so as to drag forward the rope *AD*, and raise the load *P*, *CE* will represent the power of the lever in this position, or the lever of the horse's weight, and *CF* the lever by which it is resisted by the load, or the lever of resistance. Now, if the horse lowers its centre of gravity *A*, which it always does when it pulls hard, it is evident that *CE*, the lever of its weight, will be increased, while *CF*, the lever of its resistance, will be diminished, for the line of traction *AD* will approach nearer to *CE*. Hence we see the great benefit which may be derived from large horses, for the lever *AC* necessarily increases with their size, and their power is always proportioned to the length of this lever, their weight remaining the same. Large horses, therefore, and other animals, will draw more than small ones, even though they have less muscular force, and are unable to carry such a heavy burden. The force of the muscles tends only to

PLATE II. Fig. 5.

[a] It may be imagined that the fore feet of the horse prevent it from acting in this manner; but Deparcieux has shewn by experiment that the fore feet bear a much less part of the horse's weight when he draws than when he is at rest.

make the horse carry continually forward his centre of gravity; or, in other words, the weight of the animal produces the draught, and the play and force of its muscles serve to continue it.[3]

Position of the line of traction.

From these remarks, then, we may deduce the proper position of the line of traction. When the line of traction is horizontal, as *AD*, the lever of resistance is *CF*; but if this line is oblique to the horizon, as *Ad*, the lever of resistance is diminished to *Cf*, while the lever of the horse's weight remains the same.—Hence it appears, that inclined traces are much more advantageous than horizontal ones, as they uniformly diminish the resistance to be overcome. Deparcieux, however, has investigated experimentally the most favourable angle of inclination, and found, that when the angle *DAF*, made by the trace *Ad*, and a horizontal line is 14 or 15 degrees, the horses pulled with the greatest facility and force. This value of the angle of draught will require the height of the spring-tree bar, to which the traces are attached in four-wheeled carriages, to be *one half* of the height of that part of the horse's breast to which the fore end of the traces is connected.[4]

Notwithstanding the great utility of inclined

---

[3] When I first compared Deparcieux's theory with the manner in which horses appear to exert their strength, I was inclined to suspect its accuracy; but a circumstance occurred which removed every doubt from my mind. I observed a horse making continual efforts to raise a heavy load over an eminence. After many fruitless attempts, it raised its fore feet completely from the ground, pressed down its head and chest, and instantly surmounted the obstacle.

[4] This height is about 4 feet 6 inches, and therefore the height of the spring-tree bar should be only 2 feet 3 inches, whereas it is generally 3 feet.

traces, it will not be easy to derive complete advantage from them in two-wheeled carriages without diminishing the size of the wheels. In all four-wheeled carriages, however, they may be easily employed; and in many other cases where wheels are not concerned, great advantage may be derived from the discovery of Deparcieux.

On the Position of the Centre of Gravity, and the manner of Disposing the Load.

Position of the centre of gravity.

From Mr. Ferguson's observations on the centre of gravity,[5] it must be evident, that if the axle-tree of a two-wheeled carriage passes through the centre of gravity of the load, the carriage will be in equilibrio in every position in which it can be placed with respect to the axle-tree, and in going up and down hill, the whole load will be sustained by the wheels, and will have no tendency either to press the horse to the ground or to raise him from it. But if the centre of gravity is far above the axletree, as it must necessarily be according to the present construction of wheel carriages, a great part of the load will be thrown on the back of the horses from the wheels, when going down a steep road, and thus tend to accelerate the motion of the carriage, which the animal is striving to prevent; while in ascending steep roads a part of the load will be thrown behind the wheels, and tend to raise the horse from the ground, when there is the greatest necessity for some weight on his back, to enable him to fix his feet on the earth, and

[5] Vol. i, page 17.

overcome the great resistance which is occasioned by the steepness of the road. On the contrary, if the centre of gravity is below the axle, the horse will be pressed to the ground in going up hill, and lifted from it when going down. In all these cases, therefore, where the centre of gravity is either in the axletree, or directly above or below it, the horse will bear no part of the load in level ground: In some situations the animal will be lifted from the ground when there is the greatest necessity for his being pressed to it, and he will sometimes bear a great proportion of the load when he should rather be relieved from it.

The only way of remedying these evils is to assign such a position to the centre of gravity, that the horse may bear some portion of the load when he must exert great force against it; that is, in level ground, and when he is ascending steep roads;—for no animal can pull with its greatest effort, unless it is pressed to the ground. Now, this may, in some measure, be effected in the following manner. Let *BCN*, be the wheel of a cart, *AD* one of the shafts, *D* that part of it where the cart is suspended on the back of the horse, and *A* the axletree; then, if the centre of gravity of the load is placed at *m*, a point equidistant from the two wheels, but below the line *DA*, and before the axletree, the horse will bear a certain weight on level ground, a greater weight when he is going up hill and has more occasion for it, and a less weight when he is going down hill and does not require to be pressed to the ground. All this will be evident from the figure, when we recollect, that if the shaft *DA* is horizontal, the centre of gravity will press more upon the

Plate II, Fig. 5. App.

point of suspension D the nearer it comes to it; or, the pressure upon D, or the horse's back, will be proportional to the distance of the centre of gravity from A. If m, therefore, be the centre of gravity, bA will represent its pressure upon D, when the shaft DA is horizontal. When the cart is ascending a steep road, AH will be the position of the shaft, the centre of gravity will be raised to a, and aA will be the pressure upon D. But if the cart is going down hill, AC will be the position of the shaft, the centre of gravity will be depressed to n, and cA will represent the pressure upon the horse's back. The weight sustained by the horse, therefore, is properly regulated, by placing the centre of gravity at m. We have still, however, to determine the proper length of ba and bm, the distance of the centre of gravity from the axle, and from the horizontal line DA; but these depend upon the nature and inclination of the roads, upon the length of the shaft DA, which varies with the size of the horse, on the magnitude of the load, and on other variable circumstances, it would be impossible to fix their value. If the load along with the cart weighs 400 pounds, if the distance DA be 8 feet, and if the horse should bear 50 pounds of the weight, then bA ought to be 1 foot, which being $\frac{1}{8}$ of DA, will make the pressure upon D exactly 50 pounds. If the road slopes 4 inches in 1 foot, bm must be 4 inches, or the angle bAm should be equal to the inclination of the road, for then the point m will rise to a when ascending such a road, and will press, with its greatest force, on the back of the horse.

When carts are not constructed in this manner, we may, in some degree, obtain the same Method of disposing the load.

end, by judiciously disposing the load. Let us suppose that the centre of gravity is at *O*, when the cart is loaded with homogeneous materials, such as sand, lime, &c. then, if the load is to consist of heterogeneous substances, or bodies of different weights, we should place the heaviest at the bottom and nearest the front, which will not only lower the point *O*, but will bring it forward, and nearer the proper position *m*. Part of the load, too, might be suspended below the fore part of the carriage in dry weather, and the centre of gravity would approach still nearer the point *m*. When the point *m* is thus depressed, the weight on the horse is not only judiciously regulated, but the cart will be prevented from overturning, and in rugged roads the weight sustained by each wheel will be in a great degree equalized.

In loading four-wheeled carriages, great care should be taken not to throw much of the load upon the fore wheels, as they would otherwise be forced deep into the ground, and require great force to pull them forward. In some modern carriages this is very little attended to. The coachman's seat is sometimes enlarged so as to hold two persons, and all the baggage is generally placed in the front directly above the fore-wheels. By this means, the greatest part of the load is upon the small wheels, and the draught becomes doubly severe for the poor animals, who must thus unnecessarily suffer for the ignorance and folly of man.

MECHANICS.

ON THE THRASHING MACHINE.

In a country like this, where agriculture has arrived at such a high state of perfection, the utility of thrashing machines cannot easily be called in quesion. The universal prevalence of these engines is a strong proof that they are advantageous to the farmer; and, however much some men may inveigh against the adoption of every kind of machinery that has for its object the abridgement of manual labour, yet we are convinced, that no evil consequences can possibly accrue from their introduction; and that such insinuations have a tendency to inflame the minds of the vulgar, and retard the progress of science. As a proof of this, we might mention the fate of the celebrated Arkwright, the inventor of the fly-shuttle, whom the fury of an English rabble banished from his native country.

Utility of machines for abridging labour.

The thrashing machine was invented in Scotland, in 1758, after five years labour, by Mr. Michael Stirling, a farmer in Perthshire. The honour of this invention has been claimed by Mr. Andrew Meikle, an ingenious mill-wright in East Lothian, who obtained a patent for one

History of the thrashing machine.

of these machines, about the year 1785; and in this country his claims have been generally admitted. Mr. Meikle, however, was merely an improver of the thrashing machine, and I am assured by a gentleman of the most unquestionable authority, who, from his local situation, had access to the best information, that Mr. Meikle had seen Mr. Stirling's thrashing machine before he erected any of his own, and that he merely altered and improved it. About 26 years prior to the date of Mr. Stirling's invention, a thrashing machine was constructed in Edinburgh, by Mr. Michael Menzies, which operated by the elevation and depression of a number of flails, by means of the motion of a crank; and, in 1767, the model of a thrashing mill, invented by Mr. Evers of Yorkshire, was laid before the Society of arts in London, who rewarded the inventor with a premium of 60 pounds. This machine, which was driven by wind, consisted of a number of stampers, that beat out the grain when laid upon a moveable thrashing floor, and was actually used on a large scale in Yorkshire, where it received the approbation of several intelligent gentlemen of the county.[1] All these machines, however, and others of a similar kind, with which the public are perpetually harassed, are completely defective in principle, and are greatly inferior to the worst of those now in use, which operate by the revolution of a thrashing scutch furnished with beaters,—the exclusive invention of our countryman Mr. Stirling.

---

[1] Bailey's Drawings of Machines laid before the Society of Arts, vol. i, pp. 54-59.

On Thrashing Machines driven by Water.

In Fig. 1, Plate VII, AB is an undershot water wheel, which drives the machinery. On its axis is fixed the spur-wheel CD, furnished with 150 teeth, which impel the pinion b, containing 25 teeth. On the axis H of the pinion b is placed another wheel E, carrying 72 teeth, which take into the 15 leaves of the pinion c. The axle xx of the *thrashing scutch*, represented more distinctly in Fig. 2, by yxy, is fastened upon the same axis with the pinion c, and is therefore carried round with the same velocity. The thrashing scutch, a section of which may be seen in Fig. 3, is generally furnished with four, and sometimes with a greater number of *beaters*, yy, whose surfaces, o, o, are covered with iron rounded off at the edges, in order to prevent them from cutting the straw. When these beaters strike upwards, the scutch must be contained in a hollow cylinder of wood mn, so that the tops y, y, o, o, of the beaters may be above it; in which case, the scutch is called the *thrashing drum*. But when the beaters strike downwards, there is no occasion for covering it with boards. Plate VII, Fig. 1. Thrashing machines driven by water. Fig. 3.

The gudgeon of the axis H carries a wheel i of 22 teeth, which acts upon the wheel h with 18 teeth; on the axis he is fixed another wheel e with 17 teeth, that drives the crown wheel d, furnished with three rows of teeth, 13, 17, and 21, which, by means of the spindle R, gives motion to one of the feeding rollers, not visible in Fig. 1, but represented distinctly by RR in Fig. 2. On the axis of the upper feeding roller RR is placed a small pinion, which drives the

under feeding roller by acting upon another pinion, with the same number of teeth, fixed upon its spindle. The two feeding rollers, which are generally $3\frac{1}{2}$ inches in diameter, are fluted, or cut into small leaves like pinions, so that the leaves of the one may take into the leaves of the other; and their gudgeons move in mortises of such a nature, that the upper roller may rise in its frame, and the under one remove from the beaters, when too much corn is admitted between them. In order that the velocity of the rollers may be increased and diminished at pleasure, according to the nature of the corn to be thrashed, the wheel *e* is made to shift on its axis so as to act upon any of the three rows of teeth in the crown wheel *d*, which enable us to communicate three different degrees of velocity to the rollers.

As the machinery which drives the straw-shaker interferes, in Fig. 1, with that which gives motion to the fluted rollers, it will be seen
Fig. 2. in Fig. 2, which is a plan of the machine where the corresponding parts are marked by similar letters. The wheels *b*, *E*, *c*, in Fig. 1, are not represented in this figure, but *H* is the extremity of the axle on which *E* and *b* are fixed. The small wheel *i* of 22 teeth, fixed upon the extremity of the gudgeon *i H* gives motion to *m*, a wheel of 17 teeth, which, by the intervention of the spindle *m n* and wheel *n* of 24 teeth, drives *o*, a wheel carrying 34 teeth.[a] On the same

[a] The dimensions of the thrashing machines here described are chiefly taken from Gray's Experienced Millwright, a book of great utility in a manufacturing country. It consists chiefly of plans, sections, and elevations, of different machines, which the author himself has either erected, or whose construction he has immediately superintended. We are afraid, however, that Mr. Gray has

axis with *o* is fixed the straw-shaker *KK*, on whose cross arms are fastened the rakes z *r*, furnished with a number of iron, or wooden, teeth, which carry off the straw, while the grain falls down into the fanners. The axis of these fanners *p q*, Fig. 1, is put in motion by the belt *p p* passing over the two rollers *p*, *p*. A section of the straw-shaker is shewn in Fig. 4, where *K* is its axle, z, z, its arms, and *r*, *r*, &c. the teeth fastened at the extremity of these arms.

Velocity of its different parts.

That the reader may have a distinct idea of the thrashing machine, we have calculated the following table, which exhibits the number of teeth in the wheels, and the velocity of its different parts. It is scarcely necessary to premise, that when one wheel drives another, the number of turns, or parts of a turn, performed by the wheel which is driven, is represented by a fraction, whose numerator is the number of teeth in the wheel that gives the motion, and whose denominator is the number of teeth in the wheel which receives it. Thus, a wheel with 25 teeth, driven by another with 150, will perform $\frac{150}{25}$, or six revolutions for one revolution of the impelling wheel; and a wheel with 16 teeth, driven by a pinion with 8 teeth, will make $\frac{8}{16}$, or $\frac{1}{2}$ of a turn for one revolution of the pinion. When two or more wheels are upon the same axis, they all perform the same number of revolutions, however different be their magnitude

---

not rendered these machines sufficiently intelligible to the uninstructed mechanic, from the great brevity of his descriptions; and, we hope, if his work reaches a second edition, as we trust it will, that he will take advantage of this friendly hint.

and the number of teeth; though the velocities of their circumferences may be widely different.

In the following table, we have calculated merely the number of turns made by each wheel for one turn of the water wheel; but when the number of revolutions performed by the water wheel in a second is known, we have only to multiply the quantities in the third column by this number, in order to find the number of turns which each wheel makes in the same time.

Names of the wheels.	Number of teeth in each wheel.	Number of turns for one of the water-wheel.
Plate VII, Fig. 1 & 2.	Teeth.	Turns. Dec.
CD	150	1.000
b	25	6.000
E	72	6.000
c	15	28.800
Thrashing-scutch,	0	28.000
i	22	6.000
h	18	7.333
e	17	7.333
Fluted Rollers *d*	13	9.534
Fluted Rollers *d*	17	7.333
Fluted Rollers *d*	21	5.940
m	17	7.764
n	24	7.764
o	34	5.479
Straw-shaker.	0	5.479

The working parts of the thrashing machine being thus described, the manner of its operation will be easily understood. The sheaves of corn Fig. 2 are spread upon an inclined board *O*, called the feeding board, and introduced between the flut-

ed rollers, a section of which is distincly visible at *i i*, in Figure 3. The corn is held fast by these rollers, which are only about three quarters of an inch from the beaters, while the thrashing drum, or scutch, revolving with immense rapidity and force, separates the grain from the straw, by the repeated strokes of the beaters. Part of the grain falls through the heck or searce *i r*, into a large hopper, which conducts it to the fanners, and some of it is carried along with the straw into the other heck *r p*, where it falls into the hopper, while the straw is cleared away by the rakes z of the straw-shaker, and thrown out at the opening *n p* into the lower part of the barn. Plate VIII, Fig. 3.

In some thrashing machines driven by water, the motion is conveyed to the thrashing scutch, by means of a long perpendicular axis. The lower extremity of the axis is furnished with a pinion, which is driven by a spur-wheel, with teeth perpendicular to its plane, placed upon the axis of the water wheel. A large horizontal wheel is fixed on the top of this long axle, which acts upon a pinion fastened upon the axis of the thrashing-drum.

On Thrashing Machines driven by Horses.

Wherever a sufficient quantity of water can be procured, it should always be employed as the impelling power of thrashing machines. There are many situations, however, in which it cannot be obtained; and as the erection of steam-engines and wind-mills would be too expensive for the generality of farmers, they are under the necessity of having recourse to animal power. In Plate VIII, Fig. 1, is represented a Thrashing machines driven by horses. Plate VIII, Fig. 1.

thrashing machine, which may be driven by four or six horses. To the vertical axis *M* six strong bars are fixed, called the horse polls, four of which, *P*, *R*, *S*, *L*, are visible in the figure, and to the extremity of each of these poles two pieces of wood, like *o p*, are attached, to which the horses are yoked when the machine is to be used. Upon the top of the six poles is placed the large bevelled wheel *AB*, containing 270 teeth, which drives the pinion *BC* of 40 teeth; on the axle *N* is also fixed the wheel *DD*, which carries 84 teeth, and drives the pinion *b* of 24 teeth, placed upon the axle *b k*. Upon the same axis the wheel *EE* revolves, carrying 66 teeth, which drive the pinion *c* of 15 teeth, and consequently the thrashing-drum *xx*, which is fixed upon the same axle. The feeding rollers are driven by the intervention of the four bevelled wheels *i*, *h*, *e*, *d*, the latter of which is fastened on the axis of the upper feeding roller. The wheel *i*, upon the gudgeon *i b*, contains 25 teeth, the wheel *h* 24 teeth, *e* 22 teeth, and *d* 21 teeth; but when the fluted rollers require a greater velocity, *e* is taken from its iron axle, and a greater or less wheel substituted in its room. The short axle *b k* is furnished with a pulley *p*, which, by means of the leathern belt *p p*, gives motion to the fanners placed below the thrashing scutch and straw-shaker.

Fig. 2. Fig. 2 represents a plan of the wheels, thrashing-drum, and straw-shaker, where the corresponding parts, in Fig. 1, are marked with similar letters. The small wheels *g* and *k*, however, which convey motion to the straw-shaker, are not seen in Fig. 1. The largest one *g* is fixed on the axis *N*, and carries 38 teeth. It drives *k*, which contains 14 teeth, and is placed upon the axis of the straw-shaker *KK*.

An elevation of the working parts of the machine is delineated in Fig. 3, where the corresponding parts in the plan and section have the same letters affixed to them. The sheaves of corn are spread on the feeding board *o*, drawn in by the rollers *i*, *i*, and thrashed by the beaters *o*, *o*, which strike downward. Part of the corn falls through the heck *i r*, and some part of it is carried along with the straw into the larger heck *r p*, where it falls into the hopper below, while the straw is thrown out at the opening *n p*. The drum and straw-shaker are surrounded with a covering of wood *i m n*. The following table exhibits, at one view, the number of teeth in the wheels, and the different velocities with which they move. Fig. 3.

Names of the wheels.	Number of teeth in each wheel.	Number of turns for one of the wheel.
Plate VIII, Fig. 1, 3, 4.	Teeth.	Turns. Dec.
AB	270	1.000
BC	40	6.750
DD	84	6.750
b	24	23.625
EE	66	23.625
c	15	103.950
Thrashing-scutch.	0	103.950
g	38	6.750
k	14	18.293
Straw-shaker.	0	18.293
i	25	23.625
h	24	24.617
e	22	26.857
d	21	28.199
Feeding Rollers.	0	28.199

Driven by horses and water.

In situations where there is an occasional supply of water, thrashing machines are sometimes constructed so as to be driven either by horses or water. In this case, the water-wheel has the position *LH*, Fig. 1, and is furnished with a large wheel *GH* consisting of segments of cast iron firmly fixed to the arms of the water-wheel. The wheel *GH* drives *FG*, and thus communicates motion to the horizontal shaft *N*, and the rest of the machinery. When there is no water for impelling the mill, the water-wheel *LH* is either lowered in its frame, or one of the segments is taken from the wheel *GH*, in order to keep it clear of the wheel *FG*; and when there is a sufficient discharge of water *CB* is either raised above *AB*, or *AB* is deprived of a few teeth, which can be screwed and unscrewed at pleasure. Sometimes, when there is a small supply of water, its energy may be combined with the exertion of one or two horses.

Driven by wind or steam.

If the thrashing machine is to be driven by wind, the motion is conveyed to the axle *N*, by the small wheel *mC*, fixed at the bottom of the vertical axis *n*, which is moved by the wheel upon the windshaft. If the mill is to be moved by steam, the large fly must be fixed on the axis *N*, parallel to the horizon.

Fig. 4.

Fig. 4 represents a thrashing machine of a very simple construction, which may be driven by two or three horses. The large wheel and pinion, corresponding with *AB* and *BC*, in Fig. 1, are not delineated in the figure, but the former contains 166, and the latter 19, teeth. On the shaft *N* is fastened the wheel *DD*, which carries 80 teeth, and drives the pinion *c* of 9 teeth, and consequently the thrashing-drum, which is fixed on its axis. The straw-shaker is turned by means of the leathern belt *h i* pass-

ing over the pulleys *h* and *i*, the fluted rollers by the belt *k m*, and the fanners by the rope *d e*.

I have seen a thrashing mill of this simple construction belonging to Hercules Ross, Esq. of Rossie, which was driven by six horses. The large wheel, corresponding with *AB*, had 144 teeth, and the pinion, corresponding with *BC*, had 14 teeth. The wheel *DD* had 80 teeth, and the pinion *c* 8. The straw-shaker and fluted rollers were driven by belts, and the fanners by a rope passing over a groove in the large wheel *DD*. The thrashing-drum revolved 103 times for every turn of the horses; whereas the drum in the machine, represented in Fig. 4, performed only 79 revolutions in the same time. In the first case, however, the horse walk was of such a size that the horses performed only 3 turns in a minute; while, in the latter, the horses are supposed to make 4 revolutions in a minute. The velocity, therefore, of the former will be $4\times79=316$, and the velocity of the latter $3\times103=309$. PLATE VIII. Fig. 1.

When thrashing mills began to be generally adopted in this country, they were constructed according to the plan represented in Fig. 5. The wheel *AB* has 276 cogs, *b* 14, the crown wheel *c* 84, *d* 16. The thrashing-drum is fixed on the axis *m d*, and the fanners, straw-shaker, and fluted rollers, are moved by leathern belts. Fig. 5.

A thrashing machine for small farms, which can be wrought by a single horse, has long been a desideratum in mechanics, and every attempt to construct one on a small scale seems to have completely failed. While examining the causes of this failure, I have thought of some methods by which they may be partially. A small thrashing machine a desideratum in mechanics.

removed, and of a machine which might be impelled by one horse, or by two or three men working at a winch. The description of this simple engine I expected to have communicated in this article; but a desire to improve it as much as possible, has induced me to defer its publication to some future opportunity.

On the Power of Thrashing Machines.

Power of thrashing machines.

The quantity of corn which a machine will thrash in a given time, depends so much upon the judicious formation and position of its parts, that one machine will often perform double the work of another, though constructed upon the same principles, and driven by the same impelling power. Misled by this circumstance, those who have given an account of the power of their thrashing mills, have published merely the number of bolls which they can thrash in a given time, without mentioning the quantity of impelling power, or the number of horses employed to drive them.

Mr. Fenwick, whose labours in practical mechanics we have already mentioned with commendation, has furnished us with some important information upon this point. He found, from a variety of experiments, that a power capable of raising a weight of 1000 pounds, with a velocity of 15 feet per minute, will thrash two bolls of wheat in an hour; and that a power sufficient to raise the same weight, with a velocity of 22 feet per minute, will thrash three bolls of the same grain in an hour. From these facts, Mr. Fenwick has com-

puted the following table, which is applicable to machines that are driven either by water or horses.

Table of the Power of Thrashing Machines.

Gallons of water per minute, ale measure, discharged on an overshot wheel 10 feet in diameter.	Gallons of water per minute, ale measure, discharged on an overshot wheel 15 feet in diameter.	Gallons of water per minute, ale measure, discharged on an overshot wheel 20 feet in diameter.	Number of horses working 9½ hours.	Bolls of wheat thrashed in an hour.	Bolls thrashed in 9½ hours actual working, or in a day.
230	160	130	1	2	19
390	296	205	2	3	28½
528	380	272	3	5	47½
660	470	340	4	7	66½
790	565	400	5	9	85½
970	680	500	6	10	95
1	2	3	4	5	6

The four first columns of the preceding table contain different quantities of impelling power, and the two last exhibit the number of bolls of wheat in Winchester measure, which such powers are capable of thrashing in an hour, or in a day. Six horses, for example, are capable of thrashing 10 bolls of wheat in an hour, or 95 in the space of 9½ hours, or a working day; and 680 gallons of water discharged during a minute into the buckets of an overshot water wheel 15 feet in diameter, will thrash the same quantity of grain.

MECHANICS.

ON THE NATURE OF FRICTION, AND THE METHOD OF DIMINISHING ITS EFFECTS IN MACHINERY.

Importance of considering the nature and effects of friction

THE resistance which friction generates in the communicating parts of machinery is so powerful, and the consequent defalcation from the impelling power is so great, that a knowledge of its nature and effects must be of the highest importance to the philosopher and the practical mechanic. The theory of mechanics must continue imperfect till the nature and effects of friction are thoroughly developed, and their performance must be comparatively small, and the expence of their erection and preservation comparatively great, till some effectual method is discovered for diminishing that retardation of the machine's velocity, and that decay of its materials which arise from the attrition of the connecting parts. The knowledge, however, which has been acquired concerning this abstruse subject has not been commensurate with the labours of

philosophers, and the progress of other branches of mechanical science; and those contrivances which ingenious men have discovered for diminishing the resistance of friction, have either been overlooked by practical inquirers, or rejected by those vulgar prejudices which prompt the mechanics of the present day to persist in the most palpable errors, and neglect such maxims of construction as are authorized both by theory and experience. It may be proper, therefore, in a work like this, to give a summary view of the opinions of different philosophers upon the nature of friction, and the means which may be adopted for diminishing its effects.

M. Amontons was the first philosopher who favoured us with any thing like correct information upon this subject. He found that the resistance opposed to the motion of a body upon a horizontal surface was exactly proportional to its weight, and was equal to *one third* of it, or more generally to one third of the force with which it was pressed against the surface over which it moved. He discovered also that this resistance did not increase with an increase of the rubbing superficies, nor with the velocity of its motion.[1]

The experiments of M. Bulfinger authorized conclusions similar to those of Amontons, with this difference only, that the resistance of friction was equal only to *one fourth* of the force with which the rubbing surfaces were pressed together.[2]

---

[1] Mem. de l'Acad. Paris, 1699, p. 206. Amonton's experiments were confirmed by Bossut and Belidor. See Architect. Hydraulique, vol. 1, chap. ii, p. 70.

[2] Comment. Petropol. tom. ii, p. 40.

This subject was also considered by Parent, who supposed that friction is occasioned by small spherical eminences in one surface being dragged out of corresponding spherical cavities in the other, and proposed to determine its quantity by finding the force which would move a sphere standing upon three equal spheres. This force was found to be to the weight of the sphere as 7 to 20, or nearly one third of the sphere's weight.[3] In investigating the phenomena of friction, M. Parent placed the body upon an inclined plane, and augmented or diminished the angle of inclination till the body had a tendency to move; and the angle at which the motion commenced, he called the angle of equilibrium. The weight of the body, therefore, will be to its friction upon the inclined plane, as radius to the sine of the angle of equilibrium, and its weight will be to the friction on a horizontal plane, as radius to the tangent of the angle of equilibrium.[4]

The celebrated Euler seems to have adopted the hypothesis of Bulfinger respecting the ratio of friction to the force of pression; and in two curious dissertations which he has published upon this subject,[5] has suggested many important observations, which have been of great use to future enquirers. He observes, that when a body is in motion, the effect of friction will be only one half of what it is when the body has

---

[3] Recherches de Mathematique et Physique, 1713, tom. ii, p. 462.

[4] Mem. de l'Acad. Paris, 1704, p. 174.

[5] The first is entitled, *Sur le frottement des Corps solides*, and the other, *Sur la diminution de la resistance du frottement*, published in the Mem. de l'Acad. Berlin, ann. 1748, pp. 122, 133.

begun to move; and he shews that if the angle of an inclined plane be gradually increased, till the body which is placed upon it begins to descend, the friction of the body at the very commencement of its motion will be to its weight or pressure upon the plane, as the sine of the plane's elevation is to its cosine, or as the tangent of the same angle is to radius, or as the height of the plane is to its length. But when the body is in motion the friction is diminished, and may be found by the following equation $F = \text{Tan. } a - \frac{m}{15625\ nn \cos.\ a}$, in which F is the quantity of friction, the weight or pressure of the body being $= 1$; a the angle of the plane's inclination, m the length of the plane in 1000th parts of a rhinland foot, and n the time of the body's descent. Respecting the cause of friction, Euler is nearly of the same opinion with Parent: the only difference is, that instead of regarding the eminences and corresponding depressions as spherical, he supposes them to be angular, and imagines the friction to arise from the body's ascending a perpetual succession of inclined planes.

Mr. Ferguson found that the quantity of friction was always proportional to the weight of the rubbing body, and not to the quantity of surface, and that it increased with an increase of velocity, but was not proportional to the augmentation of celerity. He found also that the friction of smooth soft wood, moving upon smooth soft wood, was equal to $\frac{1}{3}$ of the weight; of rough wood upon rough wood $\frac{1}{2}$ of the weight; of soft wood upon hard, or hard upon soft, $\frac{1}{5}$ of the weight; of polished steel upon polished steel or pewter $\frac{1}{4}$ of the weight; of polished steel up-

on copper $\frac{1}{5}$, and of polished steel upon brass $\frac{1}{6}$, of the weight.[6]

The Abbé Nollet[7] and Bossut[8] have distinguished friction into two kinds; that which arises from one surface being dragged over another, and that which is occasioned by one body rolling upon another. The resistance which is generated by the first of these kinds of friction is always greater than that which is produced by the second; and it appears evidently from the experiments of Muschenbroek, Schoeber, and Meister, that when a body is carried along with an uniformly accelerated motion, and retarded by the first kind of friction, the spaces are still proportional to the squares of the times, but when the motion is affected by the second kind of friction, this proportionality between the spaces and the times of their description does not obtain.

Result of Vince's experiments.

The subject of friction has more lately occupied the attention of the ingenious Mr. Vince of Cambridge. He found that the friction of hard bodies in motion is an uniformly retarding force, and that the quantity of friction, considered as equivalent to a weight drawing the body backwards, is equal to $M\frac{\overline{M \times W} \times S}{r\,t^2}$ where M is the moving force expressed by its weight, W the weight of the body upon the horizontal plane, S the space through which the moving force or weight descends in the time t and $r = 16.087$ feet, the force of gravity. Mr. Vince also found

---

[6] Tables and Tracts, edit. 2d, p. 289.

[7] Nollet, Lecons de Physique, tom. iii, p. 231, ed. 1770.

[8] Traite Elementaire de Mecanique, par Bossut, § 306-7.

that the quantity of friction increases in a less ratio than the quantity of matter or weight of the body, and that the friction of a body does not continue the same when it has different surfaces applied to the plane on which it moves, but that the smallest surfaces will have the least friction.[9]

Notwithstanding these various attempts to unfold the nature and effects of friction, it was reserved for the celebrated Coulomb to surmount the difficulties which are inseparable from such an investigation, and to give an accurate and satisfactory view of this complicated part of mechanical philosophy. By employing large bodies and ponderous weights, and conducting his experiments on a large scale, he has corrected several errors which necessarily arose from the limited experiments of preceding writers; he has brought to light many new and striking phenomena, and confirmed others which were hitherto but partially established. As it would be foreign to the nature of this work to follow Monsieur Coulomb through his numerous and varied experiments, we shall only present the reader with the new and interesting results which they authorize.[1]

Experiments of Coulomb.

1. The friction of homogeneous bodies, or bodies of the same kind moving upon one another, is generally supposed to be greater than that of

Friction of homogeneous bodies not always

[9] Philosophical Transactions, v. lxxv, p. 167.

[1] A full account of Coulomb's experiments may be seen in the *Journal de Physique* for September and October 1785, vol. xxvii, pp. 206 & 282, &c. An excellent summary of them may also be found in Van Swinden's Positiones Physicæ. They were originally published in the *Mémoires des Savans Etrangers, tom.* x, p. 163; and obtained the double prize offered by the Academy in 1779 and 1782.

greater than that of heterogeneous bodies.

heterogeneous bodies;[2] but Coulomb has shewn that there are exceptions to this rule. He found, for example, that the friction of oak upon oak was equal to $\frac{1}{2.34}$ of the force of pression; the friction of pine against pine was $\frac{1}{1.78}$, and of oak against pine $\frac{1}{1.5}$. The friction of oak against copper was $\frac{1}{3.5}$, and that of oak against iron nearly the same.[3]

Friction greatest according to the course of the fibres.

2. It was generally supposed, that in the case of wood, the friction is greatest when the bodies are dragged contrary to the course of their fibres;[4] but Coulomb has shewn that the friction is, in this case, sometimes the smallest. When the bodies moved in the direction of their fibres the friction was $\frac{1}{2.34}$ of the force with which they were pressed together; but when the motion was contrary to the course of the fibres, the friction was only $\frac{1}{3.76}$.

Friction increases with the time of contact.

3. The longer the rubbing surfaces remain in contact, the greater is their friction.[5]—When wood was moved upon wood, according to the direction of the fibres, the friction was increased by keeping the surfaces in contact for a few seconds; and when the time was prolonged to a minute, the friction seemed to have reached its utmost limit. But when the motion was per-

---

[2] This was the opinion of Muschenbroek, Krafft, Camus, and Bossut.

[3] From a series of experiments on heavy machinery where the force of pression was about 33 cwt. Mr. Southern of Birmingham concludes, that in favourable cases, the friction does not exceed $\frac{1}{40}$ of the force of pression. It is to be wished that this curious result were confirmed by other writers.

[4] Muschenbroek, Introductio ad Philosoph. Nat. § 513.

[5] This is mentioned by Bossut, Traite de Mecanique, § 310; but Coulomb has the merit of having established the fact.

formed contrary to the course of the fibres, a greater time was necessary before the friction arrived at its maximum. When wood was moved upon metal, the friction did not attain its maximum till the surfaces continued in contact for 5 or 6 days; and it is very remarkable, that when wooden surfaces were anointed with tallow, the time requisite for producing the greatest quantity of friction was increased. The increase of friction which is generated by prolonging the time of contact is so great, that a body weighing 1650 pounds was moved with a force of 64 pounds when first laid upon its corresponding surface. After having remained in contact for the space of 3 seconds, it required 160 pounds to put it in motion, and when the time was prolonged to 6 days, it could scarcely be moved with a force of 622 pounds. When the surfaces of metallic bodies were moved upon one another, the time of producing a maximum of friction was not changed by the interposition of olive oil; it was increased, however, by employing swines grease as an unguent, and was prolonged to 5 or 6 days by besmearing the surfaces with tallow.

4. Friction is in general proportional to the force with which the rubbing surfaces are pressed together; and is, for the most part, equal to between $\frac{1}{2}$ and $\frac{1}{4}$ of that force.[6]—In order to prove the first part of this proposition, Coulomb employed a large piece of wood, whose surface

Friction proportional to the force of pression.

[6] Friction being $\frac{1}{3}$ of the force of pression, it may be shewn, that a power which moves a body along a horizontal plane, acts to the greatest advantage when the line of direction makes an angle of 18° 26′ with the plane. This proposition is neatly demonstrated in Mr. Gregory's Mechanics, vol. ii, p. 17.

contained 3 square feet, and loaded it successively with 74 pounds, 874 pounds, and 2474 pounds. In these cases the friction was successively $\frac{1}{2.46}$, $\frac{1}{2.16}$, $\frac{1}{2.21}$, of the force of pression; and when a less surface and other weights were used, the friction was $\frac{1}{2.36}$, $\frac{1}{2.42}$, $\frac{1}{2.40}$. Similar results were obtained in all Coulomb's experiments, even when metallic surfaces were employed. The second part of the proposition has also been established by Coulomb. He found that the greatest friction is engendered when oak moves upon pine, and that it amounts to $\frac{1}{1.78}$ of the force of pression; on the contrary, when iron moves upon brass, the least friction is produced, and it amounts to $\frac{1}{9}$ of the force of pression.

Friction not proportional to the rubbing surfaces.

5. Friction is in general not increased by augmenting the rubbing surfaces.[7]—When a superficies of 3 feet square was employed, the friction, with different weights, was $\frac{1}{2.28}$ at a medium; but when a smaller surface was used, the friction, instead of being greater, as might have been expected, was only $\frac{1}{2.39}$.

Friction sometimes diminished by increasing the velocity.

6. Friction for the most part is not augmented by an increase of velocity. In some cases, however, it is diminished by an augmentation of celerity.[8]—M. Coulomb found, that when

---

[7] Muschenbroek and Nollet entertained the opposite opinion. The experiments of Krafft coincide with those of Coulomb. See Commen. Petropol. tom. xii, p. 266, § 19, 20, &c.

[8] The latter part of this proposition is confirmed by a circumstance which occurred in the course of M. Lambert's experiments on undershot mills, but which he imputes to a very different cause. He found that the resistance which is generated by the friction of the communicating parts of a corn mill, combined with that which arises from the grain between the mill-stones, always diminished when the velocity was increased. M. Lambert did not hesitate

wood moved upon wood in the direction of the fibres, the friction was a constant quantity, however much the velocity was varied; but that when the surfaces were very small, in respect to the force with which they were pressed, *the friction was diminished by augmenting the rapidity:* the friction, on the contrary, was increased when the surfaces were very large when compared with the force of pression. When the wood was moved contrary to the direction of its fibres, the friction in every case remained the same. If wood is moved upon metals, the friction is greatly increased by an increase of velocity; and when metals move upon wood besmeared with tallow, the friction is still augmented by adding to the velocity. When metals move upon metals, the friction is always a constant quantity; but when heterogeneous substances are employed which are not bedaubed with tallow, the friction is so increased with the velocity, as to form an arithmetical progression when the velocities form a geometrical one.

Friction of loaded cylinders.

7. The friction of loaded cylinders rolling upon a horizontal plane, is in the direct ratio of their weights, and the inverse ratio of their diameters.—In Coulomb's experiments, the friction of cylinders of guaiacum wood, which were two inches in diameter, and were loaded with 1000 pounds, was 18 pounds or $\frac{1}{56}$ of the force of

---

hesitate to assert, that the part of this compound resistance which was produced by the friction of the machinery continued invariably the same, and ascribed, without any reason, the diminution which accompanied an increase of velocity to a diminution of the grain's resistance between the mill-stones; whereas it was probably a diminution of the friction of the connecting parts, occasioned by the augmentation of their velocity.

pression. In cylinders of elm, the friction was greater by $\frac{2}{5}$, and was scarcely diminished by the interposition of tallow.

Friction of the axes of pulleys.

From a variety of experiments on the friction of the axes of pullies, Coulomb obtained the following results.—When an iron axle moved in a brass bush or bed, the friction was $\frac{1}{6}$ of the pression; but when the bush was besmeared with very clean tallow, the friction was only $\frac{1}{11}$; when swines grease was interposed, the friction amounted to $\frac{1}{8.5}$; and when olive oil was employed as an unguent, the friction was never less than $\frac{1}{8}$ or $\frac{1}{7.5}$. When the axis was of green oak, and the bush of guaiacum wood, the friction was $\frac{1}{26}$ when tallow was interposed; but when the tallow was removed so that a small quantity of grease only covered the surface, the friction was increased to $\frac{1}{17}$. When the bush was made of elm, the friction was in similar circumstances $\frac{1}{33}$ and $\frac{1}{20}$, which is the least of all. If the axis be made of box, and the bush of guaiacum wood, the friction will be $\frac{1}{23}$ and $\frac{1}{14}$, circumstances being the same as before. If the axle be of boxwood, and the bush of elm, the friction will be $\frac{1}{29}$ and $\frac{1}{20}$; and if the axle be of iron, and the bush of elm, the friction will be $\frac{1}{20}$ of the force of pression.

Having thus given a brief, though we trust a comprehensive view of the interesting results of Coulomb's experiments, we shall conclude this part of the subject, by presenting the reader with some excellent and original observations on the cause of friction, by Mr. John Leslie, Professor of Mathematics in the university of Edinburgh.[7]

---

[7] See his ingenious and profound work on the Nature and propagation of heat, chap. xv, p. 299, &c.

'If the two surfaces which rub against each other are rough and uneven, there is a necessary waste of force, occasioned by the grinding and abrasion of their prominences. But friction subsists after the contiguous surfaces are worked down as regular and smooth as possible. In fact, the most elaborate polish can operate no other change than to diminish the size of the natural asperities. The surface of a body, being moulded by its internal structure, must evidently be furrowed, or toothed, or serrated. Friction is, therefore, commonly explained on the principle of the inclined plane, from the effort required to make the incumbent weight mount over a succession of eminences. But this explication, however currently repeated, is quite insufficient. The mass which is drawn along is not continually ascending; it must alternately rise and fall; for each superficial prominence will have a corresponding cavity; and since the boundary of contact is supposed to be horizontal, the total elevations will be equalled by their collateral depressions. Consequently, if the lateral force might suffer a perpetual diminution in lifting up the weight, it would, the next moment, receive an equal increase by letting it down again; and those opposite effects, destroying each other, could have no influence whatever on the general motion.' Leslie on friction.

'Adhesion seems still less capable of accounting for the origin of friction. A perpendicular force acting on a solid can evidently have no effect to impede its progress; and though this lateral force, owing to the unavoidable inequalities of contact, may be subject to a certain irregular obliquity, the balance of

'chances must, on the whole, have the same 'tendency to accelerate, as to retard, the mo- 'tion. If the conterminous surfaces were, there- 'fore, to remain absolutely passive, no friction 'could ever arise. Its existence demonstrates 'an unceasing mutual change of figure, the 'opposite planes, during the passage, continual- 'ly seeking to accommodate themselves to all 'the minute and accidental varieties of contact. 'The one surface, being pressed against the 'other, becomes, as it were, compactly indent- 'ed, by protruding some points and retracting 'others. This adaptation is not accomplished 'instantaneously, but requires very different 'periods to attain its *maximum*, according to the 'nature and relation of the substances concern- 'ed. In some cases, a few seconds are suf- 'ficient, in others, the full effect is not pro- 'duced till after the lapse of several days. 'While the incumbent mass is drawn along, at 'every stage of its advance, it changes its ex- 'ternal configuration, and approaches more or 'less towards a strict contiguity with the under 'surface. Hence the effort required to put it 'first in motion, and hence too, the decreased 'measure of friction, which, if not deranged 'by adventitious causes, attends generally an 'augmented rapidity. This appears clearly 'established by the curious experiments of 'Coulomb, the most original and valuable which 'have been made on that interesting subject. 'Friction consists in the force expended to 'raise continually the surface of pressure by 'an oblique action. The upper surface travels 'over a perpetual system of inclined planes; 'but that system is ever changing, with alter- 'nate inversion. In this act, the incumbent

'weight makes incessant, yet unavailing efforts 'to ascend: for the moment it has gained the 'summits of the superficial prominences, these 'sink down beneath it, and the adjoining cavi-'ties start up into elevations, presenting a new 'series of obstacles which are again to be sur-'mounted; and thus the labours of Sisiphus are 'realized in the phenomena of friction.

'The degree of friction must evidently de-'pend on the angles of the natural protuber-'ances, which are determined by the element-'ary structure or the mutual relation of the 'two approximate substances. The effect of 'polishing is only to abridge those asperities 'and increase their number, without altering 'in any respect their curvature or inflections. 'The constant or successive acclivity produced 'by the ever varying adaptation of the conti-'guous surfaces, remains, therefore, the same, 'and consequently the expence of force will 'still amount to the same proportion of the 'pressure. The intervention of a coat of oil, 'soap, or tallow, by readily accommodating 'itself to the variations of contact, must tend 'to equalize it, and therefore must lessen the 'angles, or soften the contour, of the succes-'sively emerging prominences, and thus dimi-'nish likewise the friction which thence re-'sults.'

Method of diminishing the effects of friction.

Having thus considered the origin, the nature, and the effects, of friction, we shall now attend to the method of lessening the resistance which it opposes to machinery. The most efficacious mode of accomplishing this, is to convert that species of friction which arises from one body being dragged over another, into that which is occasioned by one body rolling upon

another. As this will always diminish the resistance, it may be easily effected by applying wheels or rollers to the sockets or bushes which sustain the gudgeons of large wheels, and the axles of wheel carriages. Casatus[8] seems to have been the first who recommended this apparatus. It was afterwards mentioned by Sturmius[9] and Wolfius;[1] but was not used in practice till Sully[2] applied it to clocks in the year 1716, and Mondran[3] to cranes in 1725. Notwithstanding these solitary attempts to introduce friction wheels, they seem to have attracted but little attention till the celebrated Euler examined and explained, with his usual accuracy, their nature and advantages.[4] The diameter of the gudgeons and pivots should be made as small as the weight of the wheel and the impelling force will permit. The gudgeons should rest upon two wheels as large as circumstances will allow, having their axes as near each other as possible, but no thicker than what is absolutely necessary to sustain the superincumbent weight. When these precautions are properly attended to, the resistance which arises from the friction of the gudgeons, &c. will be extremely trifling.[5]

Friction wheels.

---

[8] Mechan. lib. ii, cap. i. p. 130.
[9] Miscellan. Berolinens. tom. i, p. 306.
[1] Opera Mathematica, tom. ii, p. 684.
[2] Machines approuvées, tom. No. 177.
[3] Id. No. 254.
[4] Mem. de l'Acad. Berlin 1748, p. 133.
[5] Mr. Walker, a lecturer on Experimental Philosophy, has boldly pronounced friction wheels to be 'expensive 'nonsense,' (System of Famil. Philos. v. i.) This gentleman should have recollected that they were recommended by Euler and many distinguished philosophers; and, though

Friction diminished by a judicious application of the impelling power.

The effects of friction may likewise in some measure be removed by a judicious application of the impelling power, and by proportioning the size of the friction wheels to the pressure which they severally sustain. If we suppose, for example, that the weight of a wheel, whose iron gudgeons move in bushes of brass, is 100 pounds; then the friction arising from both its gudgeons will be equivalent to 25 pounds. If we suppose also that a force equal to 40 pounds is employed to impel the wheel, and acts in the direction of gravity, as in the case of overshot wheels, the pressure of the gudgeons upon their supports will thus be 140 pounds and the friction 35 pounds. But if the force of 40 pounds could be applied in such a manner as to act in direct opposition to the wheel's weight, the pressure of the gudgeons upon their supports would be 100—40, or 60 pounds, and the friction only 15 pounds. It is impossible indeed to make the moving force act in direct opposition to the gravity of the wheel, in the case of water-mills; and it is often impracticable for the engineer to apply the impelling power but in a given way; but there are many cases in which the moving force may be so exerted, as at least in such a manner to increase the friction which arises from the wheel's weight.

---

though this is by no means a sufficient reason for their adoption, yet we humbly conceive that the errors of the learned should always be opposed with respectful diffidence. We are of opinion, however, and we presume that every person who understands the subject will agree with us, that friction wheels, if properly executed, are of immense service, and that nothing but the ignorance or narrowness of the proprietors of machinery could have prevented them from being more generally adopted.

When the moving force is not exerted in a perpendicular direction, but obliquely as in undershot wheels, the gudgeon will press with greater force on one part of the socket than on any other part. This point will evidently be on the side of the bush opposite to that where the power is applied, and its distance from the lowest point of the socket, which is supposed circular and concentric with the gudgeon, being called x we will have Tang. $x = \frac{H}{V}$, that is, the tangent of the arch contained between the point of greatest pressure and the lowest point of the bush, is equal to the sum of all the horizontal forces, divided by the sum of all the vertical forces and the weight of the wheel, H representing the former, and V the latter quantities. The point of greatest pressure being thus determined, the gudgeon must be supported at that part by the largest friction wheel, in order to equalize the friction upon their axles.

The application of these general principles to particular cases is so simple as not to require any illustration. To aid the conceptions, however, of the practical mechanic, we may mention two cases in which friction wheels have been successfully employed.

Mr. Gottlieb, the constructor of a new crane, has received a patent for what he calls an anti-attrition axle-tree, the beneficial effects of which he has ascertained by a variety of trials. It consists of a steel roller about 4 or 6 inches long, which turns within a groove cut in the inferior part of the axle. When wheel-carriages are at rest, Mr. Gottlieb has given the friction wheel its proper position; but it is evident that the point of greatest pressure will change when they

are put in motion, and will be nearer the front of the carriage. This point, however, will vary with the weight of the load; but it is sufficiently obvious that the friction roller should be at a little distance from the lowest point of the axle-tree.

Mr. Gammett of Bristol has applied friction rollers in a different manner, which does not, like the preceding method, weaken the axle-tree. Instead of fixing them in the iron part of the axle, he leaves a space between the nave and the axis to be filled with equal rollers almost touching each other. The axis of these rollers are inserted in a circular ring at each end of the nave, and these rings, and consequently the rollers, are kept separate and parallel, by means of small bolts passing between the rollers from one side of the nave to the other.

In wheel-carriages constructed in the common manner with conical rims, there is a great degree of resistance occasioned by the friction of the linch pins on the external part of the nave, which the ingenious mechanic may easily remove by a judicious application of the preceding principles.

As it appears from the experiments of Ferguson and Coulomb, that the least friction is generated when polished iron moves upon brass, the gudgeons and pivots of wheels, and the axles of friction rollers, should all be made of polished iron, and the bushes in which these gudgeons move, and the friction wheels should be formed of polished brass.[6]

When every mechanical contrivance has been adopted for diminishing the obstruction which

Friction diminished by unguents.

[6] M. de La Hire recommends the sockets or bushes to be made square and not concave.

arises from the attrition of the communicating parts, it may be still farther removed by the judicious application of unguents. The most proper for this purpose are swines grease and tallow, when the surfaces are made of wood, and oil when they are of metal. When the force with which the surfaces are pressed together is very great, tallow will diminish the friction more than swines grease. When the wooden surfaces are very small, unguents will lessen their friction a little, but it will be greatly diminished if wood moves upon metal greased with tallow. If the velocities, however, are increased, or the unguent not often enough renewed, in both these cases, but particularly in the last, the unguent will be more injurious than useful. The best mode of applying it, is to cover the rubbing surfaces with as thin a stratum as possible, for the friction will then be a constant quantity, and will not be increased by an augmentation of velocity.

By the power of black lead.

In small works of wood, the interposition of the powder of black lead has been found very useful in relieving the motion. The ropes of pulleys should be rubbed with tallow, and whenever the screw is used, the square threads should be preferred.

MECHANICS.

ON THE NATURE AND OPERATION OF FLY WHEELS.

A FLY in mechanics is a heavy wheel or cylinder which moves rapidly upon its axis, and is applied to machines for the purpose of rendering uniform a desultory or reciprocating motion, arising either from the nature of the machinery, from an inequality in the resistance to be overcome, or from an irregular application of the impelling power. When the first mover is inanimate, as wind, water, and steam, an inequality of force obviously arises from a variation in the velocity of the wind, from an increase of water occasioned by sudden rains, or from an augmentation or diminution of the steam in the boiler, produced by a variation in the heat of the furnace; and accordingly various methods have been adopted for regulating the action of these variable powers. The same inequality of force obtains when machines are moved by horses or men. Every animal exerts its greatest strength when first set to work. After pulling for some time its strength will be impaired, and when the resistance is great, it will take frequent, though short relaxation, and then commence its labour with renovated vigour.

Fly wheels.

Causes of inequal motion in machines.

These intervals of rest and vigorous exertion must always produce a variation in the velocity of the machine, which ought particularly to be avoided, as being detrimental to the communicating parts as well as the performance of the machine, and injurious to the animal which is employed to drive it. But if a fly, consisting either of cross bars, or a massy circular rim, be connected with the machinery, all these inconveniencies will be removed. As every fly wheel must revolve with great rapidity, the momentum of its circumference must be very considerable, and will consequently resist every attempt either to accelerate or retard its motion. When the machine, therefore, has been put in motion, the fly wheel will be whirling with an uniform celerity, and with a force capable of continuing that celerity when there is any relaxation in the impelling power. After a short rest the animal renews his efforts, but the machine is now moving with its former velocity, and these fresh efforts will have a tendency to increase the velocity: the fly, however, now acts as a resisting power, receives the greatest part of the superfluous motion, and causes the machinery to preserve its original celerity. In this way the fly secures to the engine an uniform motion, whether the animal takes occasional relaxation or exerts his force with redoubled ardour.

These inequalities remedied by a fly.

We have already observed, that a desultory or variable motion frequently arises from an inequality in the resistance, or work to be performed. This is particularly manifest in thrashing-mills, on a small scale, which are driven by water. When the corn is laid inequally on the feeding board, so that too much is taken in by the fluted rollers, this increase of resistance in-

Exemplified in a thrashing machine.

stantly affects the machinery, and communicates a desultory or irregular motion even to the water wheel or first mover. This variation in the velocity of the impelling power may be distinctly perceived by the ear in a calm evening, when the machine is at work. The best method of correcting these irregularities is to employ a fly wheel, which will regulate the motion of the machine, when the resistance is either augmented or diminished. In machines built upon a large scale there is no necessity for the interposition of a fly, as the *inertia* of the machinery supplies its place, and resists every change of motion that may be generated by an inequal admission of the corn.

Irregularities arise from the nature of the machinery.

A variation in the velocity of engines arises also from the nature of the machinery. Let us suppose that a weight of 1000 pounds is to be raised from the bottom of a well 50 feet deep, by means of a bucket attached to an iron chain which winds round a barrel or cylinder; and that every foot in length of this chain weighs 2 pounds: it is evident that the resistance to be overcome in the first moment is 1000 pounds, added to 50 pounds, the weight of the chain; and that this resistance diminishes gradually, as the chain coils round the cylinder, till it becomes only 1000 pounds, when the chain is completely wound up. The resistance therefore decreases from 1050 to 1000 pounds; and, if the impelling power is inanimate, the velocity of the bucket will gradually increase; but if an animal is employed, it will generally proportion its action to the resisting load, and must therefore pull with a greater or less force, according as the bucket is near the bottom or top of the well. In this case, however, the assistance of a fly may be

dispensed with, because the resistance diminishes uniformly, and may be rendered constant, by making the barrel conical, so that the chain may wind upon the part nearest the vertex at the commencement of the motion, the diameter of the barrel gradually increasing as the weight diminishes. In this way the variable resistance will be equalized much better than by the application of a fly-wheel; for the fly, having no power of its own, must necessarily waste the impelling power.

Having thus pointed out the chief causes of a variation in the velocity of machines, and the method of rendering it uniform by the invention of fly-wheels, the utility, and, in some instances, the necessity of this piece of mechanism, may be more obviously illustrated by shewing the propriety of its application in particular cases.

Advantages of fly wheels exemplified in the pile engine.

In the description which has been given of Vauloue's pile engine,[1] the reader must have remarked a striking instance of the utility of fly-wheels. The ram Q, is raised between the guides $b\,b$, by means of horses acting against the levers $S\,S$; but as soon as the ram is elevated to the top of the guides, and discharged from the follower G, the resistance against which the horses have been exerting their force, is suddenly removed, and they would instantaneously tumble down, were it not for the fly O. This fly is connected with the drum B, by means of the trundle X: and as it is moving with a very great force, it opposes a sufficient resistance to the action of the horses, till the ram is again taken up by the follower.

PLATE IX, Fig. 1.

[1] See Vol. i, p. 118.

When machinery is driven by a single stroke steam engine, there is such an inequality in the impelling power, that, for 2 or 3 seconds, it does not act at all. During this interval of inactivity, the machinery would necessarily stop, were it not impelled by a massy fly-wheel of a great diameter, revolving with rapidity, till the moving power again resumes its energy. In the single stroke steam engine.

If the moving power is a man acting with a handle or winch, it is subject to great inequalities. The greatest force is exerted when the man pulls the handle upwards from the height of his knee, and he acts with the least force when the handle, being in a vertical position, is thrust from him in a horizontal direction. The force is again increased when the handle is pushed downwards by the man's weight, and it is diminished, when the handle, being at its lowest point, is pulled towards him horizontally. But when a fly is properly connected with the machinery, these irregular exertions are equalized, the velocity becomes uniform, and the load is raised with an equable and steady motion. In the common winch.

In many cases, where the impelling force is alternately augmented or diminished, the performance of the machine may be increased by rendering the resistance unequal, and accommodating it to the inequalities of the moving power. Dr. Robison observes, that 'there are 'some beautiful specimens of this kind of ad-'justment in the mechanism of animal bodies.'

Besides the utility of fly-wheels or regulators of machinery, they have been employed for accumulating or collecting power. If motion is communicated to a fly-wheel by means of a small force, and if this force is continued till the Fly-wheels accummulators of powers.

wheel has acquired a great velocity, such a quantity of motion will be accumulated in its circumference as to overcome resistances, and produce effects, which could never have been accomplished by the original force. So great is this accumulation of power, that a force equivalent to 20 pounds, applied for the space of 37 seconds to the circumference of a cylinder, 20 feet diameter, which weighs 4713 pounds, would, at the distance of one foot from the centre, give an impulse to a musket ball equal to what it receives from a full charge of gunpowder. In the space of 6 minutes and 10 seconds, the same effect would be produced, if the cylinder was driven by a man who constantly exerted a force of 20 pounds at a winch 1 foot long.[a]

Exemplified in the sling.

This accumulation of power is finely exemplified in the sling. When the thong which contains the stone is swung round the head of the slinger, the force of the hand is continually accumulating in the revolving stone, till it is discharged with a degree of rapidity which it could never have received from the force of the hand alone. When a stone is projected from the hand itself, there is even then a certain degree of force accumulated, though the stone only moves through the arch of a circle. If we fix the stone in an opening at the extremity of a piece of wood 2 feet long, and discharge it in the usual way, there will be more force accumulated than with the hand alone, for the stone describes a larger arch in the same time, and must therefore be projected with greater force.

---

[a] This has been demonstrated by Mr. Atwood. See his Treatise on Rectilineal and Rotatory Motion.

When coins or medals are struck, a very considerable accumulation of power is necessary, and this is effected by means of a fly. The force is first accumulated in weights fixed in the end of the fly; this force is communicated to two levers, by which it is farther condensed: and from these levers it is transmitted to a screw by which it suffers a second condensation. The stamp is then impressed on the coin or medal by means of this force, which was first accumulated by the fly, and afterwards augmented by the intervention of two mechanical powers.[3]

Importance of placing the fly-wheels properly.

Notwithstanding the great advantages of fly-wheels, both as regulators of machines, and collectors of power, their utility wholly depends upon the position which is assigned them, relative to the impelled and working points of the engine. For this purpose no particular rules can be laid down, as their position depends altogether on the nature of the machinery. We may observe, however, in general, that when fly-wheels are employed to regulate machinery, they should be near the impelling power; and, when used to accumulate force in the working point, they should not be far distant from it. In hand-mills for grinding corn, the fly is for the most part very injudiciously fixed on the axis to which the winch is attached; whereas, it should always be fastened to the upper mill-stone, so as to revolve with the same rapidity. In the first position, indeed, it must equalize the varying ef-

[3] In the article on the Steam Engine, the reader will see an account of a new kind of fly, called the conical pendulum, which Messrs. Watt and Boulton have very ingeniously employed for regulating the admission of steam into the cylinder.

forts of the power which moves the winch; but when it is attached to the turning mill-stone, it not only does this, but contributes very effectually to the grinding of the corn.

Dr. Desaguliers mentions an instance of a blundering engineer, who applied a fly-wheel to the slowest mover of the machine, instead of the swiftest. The machine was driven by 4 men, and when the fly was taken away, one man was sufficiently able to work it. The error of the workman arose from his conceiving, like many others, that the fly added power to the machine; but we presume, that Dr. Desaguliers himself has been accessory to this general misconception of its nature, by denominating it a *mechanical power*.[4] By the interposition of a fly, however, as the doctor well knew, we gain no mechanical force; the impelling power, on the contrary, is wasted, and the fly itself even loses some of the force which it receives, by the resistance of the air.

---

[4] Dr. Desaguliers calls it a *mechanical organ*; but he gives the same appellation to the lever, and all the other mechanical powers. See his experimental Philosophy, Vol. i, p. 344.

MECHANICS.

ON THE CONSTRUCTION AND EFFECTS OF MACHINES,[1]

By Mr. John Leslie, Professor of Mathematics in the University of Edinburgh.

1, It is a principle in statics, that, if a body act upon another by the intervention of machinery, an equilibrium will obtain when their *potential* velocities are reciprocally as their masses. If the power exerted be augmented beyond what is barely sufficient to maintain the balance, a motion will immediately commence, and if it be still increased, the velocity will continually

---

[1] This excellent paper, which Professor Leslie was so kind as to communicate to the editor, was written at London so early as February 1790. The same subject was afterwards (in 1801) treated at great length by the late Dr. Robison, in the art. Machinery, Sup. Encycl. Britan.; and we do not conceive that we are derogating in the least from the talents of that learned and good man, when we say, that the present paper is written with greater perspicuity, and gives a more elementary and connected view of this interesting subject. At some future period Mr. Leslie intends to resume the investigation of this subject.—Ed.

increase. But this velocity will increase in a smaller ratio than the power; and there will, therefore, be a certain point of augmentation, at which the force employed will produce the greatest proportional effect. Such is the grand object that we ought to have always in view in the construction of machines.

2. Forces have been divided into two kinds; those whose action is supposed to be *instantaneous*, and those whose action is *continued* and *incessant*. The former have been termed *impulsive*, the latter *accelerating* or *retarding*. Though accelerated or retarded motions perpetually occur to our observation, the ancients seem to have admitted no other force but that of impulsion. It is difficult, indeed, to conceive, that a body can act at a distance; and the idea that motion is always communicated by contact, is one of our earliest and strongest prejudices. Sir Isaac Newton himself was in this instance carried away by the current of opinion. His theory of æther was an attempt to explain gravitation by impulsive forces.—But there are many facts and experiments which satisfactorily prove, that between the particles of matter there subsists a repulsion, increasing as the distance diminishes, and that no *absolute* contact can ever take place. A body does not acquire its celerity *in an instant*. Nothing material can exist but what is *finite*; and the beautiful law of *continuation*, by which changes are produced by imperceptible shades, can never be violated. But an amazing force may be exerted, and an effect may be produced, in a time so small as to elude the acuteness of our senses. Hence the origin of our idea that motion is derived from impulse. If, however, we consider the subject with more

attention, we shall find that it is really as difficult to conceive action in contiguity as at a distance. In neither case can we deduce the consequences *a priori*. The connexion which subsists between cause and effect is not necessary and absolute; it is founded upon the invariable experience of our senses. We may, therefore, conclude, that there is only one kind of force, and that is the *accelerating* or the *retarding*. Hence it will always be possible to determine the proportional intensity of any given force, compared with that of gravity, and to assign a weight, which, by its pressure alone, would in a given time produce the same effect.

3. If the gravity of an elementary point at the earth's surface be denoted by 1, the whole attractive force will be as the number of points, or as M, the mass of the body. Let F express the intensity of another force urging the same body; then $M \times F$ will denote the quantity of force exerted, or Φ; but $\frac{\Phi}{M} = F$; wherefore, the intensity of a force is directly as its quantity, and inversely as the mass which is urged.

4. Let $V =$ the velocity of a body, $S =$ the space described, and $T =$ the time of description; the velocity that is acquired may be conceived to be composed of all the successive augmentations which are produced by the continued exertion of the force, and which are proportional to the intensity of its action. But the force may for a moment be conceived to be uniform; whence the increment of velocity is compounded of the force, and of the increment of the time, or $\dot{V} \doteq FT$. Suppose the force to be constant, then $\dot{V} \doteq FT$; and when the time is

given, the velocity must be as the accelerating force. Let $V=CFT$, and V and T denote feet and seconds of time. When $F=1$, and $T=1$, we shall have $V=C=$ the velocity acquired by descent at the surface of the earth at the end of the first second. Put $d=16.1$ feet, then $C=2d$; whence $\dot{V}=2dF\dot{T}$ and $\dot{T}=\frac{\dot{V}}{2dF}$.

5. We may conceive that the velocity is uniform for an indefinitely small portion of time. Whence $\dot{S}=V\dot{T}$ and $\dot{T}=\frac{\dot{S}}{V}$; hence also $V=\frac{\dot{S}}{\dot{T}}$; but, by the last article, $\dot{V}=2dF\dot{T}$, consequently $V\dot{V}=2dF\dot{S}$; from which equation the velocity may be determined, when the relation is given between the accelerating force and the space described. If F be constant, then by integration, $\frac{1}{2}VV=2dFS$ and $V^2=4dFS$; wherefore $V=2\sqrt{dFS}$. At the same time, because $\dot{V}=2dF\dot{T}$, $\dot{S}=2dFT\dot{T}$; whence, $S=2d\times FT^2$, and $T=\sqrt{\frac{S}{2dF}}$.

6. We may divide machines into two general kinds; into those where the action is interrupted and renewed at short intervals, and into those where the action is continued for a certain period. In the former, the effect of friction not having time to accumulate, may generally be disregarded, and the motion may be considered as uniformly accelerated. With regard to the latter, if a machine be constructed so that the resistance is great, it increases rapidly with the celerity; it soon counterbalances the accelerating force, and produces a motion which is equal and constant.

7. Let us abstract the momenta and friction

of the parts of communication, and consider the effects of a machine which is uniformly impelled. Suppose the motion of a power, equal to the gravity of the mass p, be connected to that of a weight w, so that the *potential* velocity of the former be constantly to that of the latter as v: 1, and let v be termed the *advantage*. It is manifest, from the principles of statics, that a part $\frac{w}{v}$ of the power is able to maintain the equilibrium, and that the remaining part $p-\frac{w}{v}$ only is employed in producing the motion. But the action of this force $p-\frac{w}{v}$ is divided between the power and the weight. Put $y=$ the part which urges the power, and $z=$ the part which is exerted against the weight. But (3) the intensity of the force y, which impels the power, is denoted by $\frac{y}{p}$; and therefore the velocity acquired in a given time is (4) also $\frac{y}{p}$. But the influence of the force z upon the weight, will, in consequence of the mechanism, be equal to the direct action of a force vz; whence the velocity acquired by the weight in the same time will be $\frac{vz}{w}$. Wherefore, by hypothesis, $\frac{y}{p}:\frac{vz}{w}::v:1$; consequently $\frac{y}{p}=\frac{vz}{w}$ and $y=\frac{v^2pz}{w}$. But, from the notation, $p-\frac{w}{v}=y+z$ and $y=p-z-\frac{w}{v}$, or $\frac{pv-zv-w}{v}$; therefore $\frac{v^2pz}{w}=\frac{pv-zv-w}{v}$ and reducing, $v^3pz=pvw-zvw-w^2$, and transposing, $v^3pz-vwz=pvw-w^2$, whence $z=\frac{pvw-w^2}{v^3p+vw}$, consequently the real action upon the weight, or $vz=\frac{pvw-w^2}{v^2p+w}$.

8. Hence the intensity of the force which urges the weight, or F is $\frac{1}{w}\left(\frac{pvv-w^2}{v^2p+w}\right)$ or $\frac{pv-w}{v^2p+w}$; consequently this intensity is to that of terrestrial attraction as $pv-w : v^2p+w$. But this action is uniform; whence (4) $V=2dF\dot{T}$, or the actual velocity which the weight acquires in its ascent during the time T is $2dT\left(\frac{pv-w}{pv^2+w}\right)$. Wherefore $\dot{S}=2dT\dot{T}\times\frac{pv-w}{pv^2+w}$, and integrating, the space described is $dT^2\left(\frac{pv-w}{pv^2+w}\right)$.

9. When the velocity of the power is equal to that of the weight, then $v=1$ and the intensity of action $=\frac{p-w}{p+w}$ or $1-\frac{2w}{p+w}$. Whence the effect increases more slowly than the power. Thus, according as the power is equal to the weight, is double, triple, or quadruple, &c. the intensity of action is 0, $\frac{1}{3}$, $\frac{2}{4}$, $\frac{3}{5}$, $\frac{4}{6}$, &c. . . . . and ultimately $=1$. The comparative intensity is, therefore, 0, $\frac{2}{6}$, $\frac{1}{6}$, $\frac{3}{20}$, $\frac{2}{15}$, $\frac{5}{42}$, $\frac{3}{28}$, &c. and ultimately $=0$. If $p=w$, the intensity of action is $\frac{wv-w}{wv^2+w}$ or $w\left(\frac{v-1}{v^2+1}\right)$. Suppose the advantage to be successively 1, 2, 3, 4, 5, &c. then the intensity of action is 0, $\frac{1}{5}$, $\frac{1}{5}$, $\frac{3}{17}$, $\frac{2}{13}$, $\frac{5}{37}$, $\frac{3}{25}$, &c. and ultimately vanishing. Both these series commence at *zero*, increase, become stationary, and then continually decrease, till they vanish. In the present case, the *maximum* must lie between the 2d and 3d terms; for these are equal in both.

10. Since the intensity of action produced by the power p is $\frac{pv-w}{pv^2+w}$, the comparative intensity, or the effect produced by a given force 1,

will be $= \frac{1}{p} \times \frac{pv-w}{pv^2+w}$ or $\frac{pv-w}{p^2v^2+pw}$. This quantity is, therefore, the proper measure of effect, and to increase it must be our great object in improving the machine.—Let the power and weight be constant; to find the value of v, when the comparative intensity of action is a *maximum*. By taking the fluxion of $\frac{pv-w}{p^2v^2+pw}$, we obtain $\frac{\dot{pv}(p^2v^2+pw)-2p^2\dot{v}v(pv-w)}{(p^2v^2+pw)^2} = 0$; whence, by transposition and reduction, $p^3v^2+p^2w = 2p^3v^2-2p^2wv$, or $p^2v^2+w=2pv^2-2wv$, and transposing, $pv^2-2wv=w$, and dividing, $v^2-\frac{2w}{p}v=\frac{w}{p}$, and resolving the quadratic, $v-\frac{w}{p}=\sqrt{\left(\frac{w}{p}+\frac{w^2}{p^2}\right)}$ and $v=\frac{w}{p}+\sqrt{\left(\frac{w}{p}+\frac{w^2}{p^2}\right)}$, or $v=\frac{w+\sqrt{(w^2+wp)}}{p}$. Hence, according as the weight is equal to the power, is double, triple, or quadruple, &c. the *advantage* ought to be $1+\sqrt{2}$, $2+\sqrt{6}$, $3+\sqrt{12}$, $4+\sqrt{20}$, $5+\sqrt{30}$, $6+\sqrt{42}$, &c.

11. When w is very large compared with p, the expression $\frac{w+\sqrt{(w^2+wp)}}{p}$ is nearly $\frac{2w}{p}+\frac{1}{2}$. In most cases, it will be sufficiently accurate to suppose $v=\frac{2w}{p}$; and hence, in order that a machine may produce the greatest possible effect, without increasing the power applied, the *advantage* which would procure an equilibrium ought to be at least doubled. Substituting this value in the formulæ in art. 9, we obtain $V=2dT\left(\frac{pv-w}{pv^2+w}\right)=2dT\left(\frac{p}{4w+p}\right)$, and $S=dT^2\left(\frac{p}{4w+p}\right)$.

12. If the true value of v, or $\frac{w+\sqrt{(w^2+wp)}}{p}$

be substituted in those formulæ, we shall obtain $V=2dpT\left(\frac{\sqrt{(w^2+wp)}}{2w^2+2wp+2w\sqrt{(w^2+wp)}}\right)$, and $S=dpT^2\left(\frac{\sqrt{(w^2+wp)}}{2w^2+2wp+2w\sqrt{(w^2+wp)}}\right)$. Whence, when the power is equal to the weight, the greatest intensity is $\frac{\sqrt{2}}{4+2\sqrt{2}}$ or $\frac{\sqrt{2}-1}{2}$, or about one fifth of the force of gravity. If w be supposed to be successively $=2p$, $3p$, $4p$, &c. the intensity of action will be $\frac{\sqrt{6}}{24+8\sqrt{6}}$, $\frac{\sqrt{12}}{72+18\sqrt{12}}$, $\frac{\sqrt{20}}{160+32\sqrt{20}}$, $\frac{\sqrt{30}}{300+50\sqrt{30}}$, &c. nearly equal to $\frac{1}{6}$, $\frac{1}{13}$, $\frac{1}{17}$, $\frac{1}{21}$, &c. derived from the expressions in the last article. If the weight be great in respect of the power, the intensity of action will be nearly $\frac{w+\frac{1}{2}p}{2w^2+2wp+2w^2+wp}$, or $p\left(\frac{2w+p}{8w^2+6wp}\right)$. Hence the other formulæ will be found; $V=2dT\left(\frac{2wp+p^2}{8w^2+6wp}\right)$ and $S=dT^2\times\frac{2wp+p^2}{8w^2+6wp}$. Wherefore, in a machine constructed in the best manner, the accelerating force which impels the weight never amounts to one fourth of the gravity of the power.

13. Let the weight and advantage be given, and let it be required to find the power, when the measure of effect or comparative intensity of action is a *maximum*. Suppose p to be variable in the expression $\frac{pv-w}{p^2v^2+pw}$ of art. 10; and taking the fluxion, we shall have $\frac{\dot{p}v(p^2v^2+pw)-(2ppv^2+pw)(pv-w)}{(p^2v^2+pw)^2}=0$; whence $p^2v^3+pvw=(2pv^2+w)(pv-w)$, and reducing, $v^3p^2+vwp=2v^3p^2+pvw-2v^2wp-w^2$, and transposing, $v^3p^2-2v^2wp=w^2$ and dividing,

$p^2 - \frac{2w}{v}p = \frac{w^2}{v^2}$ and resolving the quadratic, $p - \frac{w}{v} = \sqrt{\left(\frac{w^2}{v^2} + \frac{w^2}{v^2}\right)}$ and $p = \frac{w}{v} + \sqrt{\left(\frac{w^2}{v^2} + \frac{w^2}{v^2}\right)}$. Hence if the advantage be 1, 2, 3, 4, 5, &c. the power ought to be $w\ (1+\sqrt{2})$, $w\ (\frac{1}{2}+\sqrt{\frac{3}{8}})$, $w\ (\frac{1}{3}+\sqrt{\frac{4}{27}})$, $w\ (\frac{1}{4}+\sqrt{\frac{5}{64}})$, $w\ (\frac{1}{5}+\sqrt{\frac{6}{125}})$, &c.

14. If v be large, the value of p will be nearly $= \frac{2w}{v} + \frac{w}{2v^2}$, or $\frac{2w}{v}\left(1+\frac{1}{4v}\right)$, or in general $= \frac{2w}{v}$ nearly; that is, the power sufficient to maintain an equilibrium, must at least be doubled to produce a *maximum* effect. Substituting the proximate value of p in art 8, we shall have $V = 2dT\left(\frac{2w(1+\frac{1}{4v})-w}{2wv(1+\frac{1}{4v})+w^2}\right)$, or $2dT\left(\frac{2v+1}{4v^2+3v}\right)$. Hence also $S = dT^2\left(\frac{2v+1}{4v^2+3v}\right)$.

15. Since, by the last article, $p = \frac{2w}{v} + \frac{w}{2v^2}$ nearly, reducing and transposing, $4v^2p = 8wv + 2w$, and dividing, $v^2 - \frac{2w}{p}v = \frac{w}{2p}$, and resolving the quadratic, we obtain $v = \frac{w}{p} + \sqrt{\left(\frac{w^2}{p^2} + \frac{w}{2p}\right)}$, or $v = \frac{2w}{p} + \frac{1}{4}$ nearly. Substituting this value of v in the above formulæ, we shall obtain in terms of p, after proper reductions, $V = 2dT\left(\frac{8wp+3p^2}{32w^2+20wp+2p^2}\right)$ and $S = dT^2\left(\frac{8wp+3p^2}{32w^2+20wp+2p^2}\right)$. But when v is large, these formulæ will be expressed with sufficient accuracy thus, $V = 2dT\left(\frac{p}{4w}\right)$ and $S = dT^2\left(\frac{p}{4w}\right)$.

16. Let the true value of p or $\frac{w}{v} + \sqrt{\left(\frac{w^2}{v^2} + \frac{w^2}{v^2}\right)}$ be substituted, and we shall obtain

$V=2dT\left(\frac{\sqrt{(w^2v^2+wv)}}{wv^2+wv+\sqrt{(w^2v^4+wv^3)}}\right.$ and $S=dT^2$ $\frac{\sqrt{(w^2v^2+wv)}}{wv^2+wv+\sqrt{(w^2v^4+wv^3}}$ If $w=1$, and v be denoted by 1, 2, 3, 4, 5, &c. the corresponding absolute intensity will be $\frac{\sqrt{2}}{2+\sqrt{2}}$, or $\sqrt{2}-1$, $\frac{\sqrt{6}}{6+\sqrt{24}}$, $\frac{\sqrt{12}}{12+\sqrt{108}}$, $\frac{\sqrt{20}}{20+\sqrt{320}}$, $\frac{\sqrt{30}}{30+\sqrt{750}}$, &c.

17. If the accurate value of p be substituted in the expression $\frac{pv-w}{p^2v^2+pw}$ for the comparative intensity, we obtain $\frac{1}{w}\left(\frac{\sqrt{(v^2+v}}{2v+2+2\sqrt{(v^2+v)}+\sqrt{(1+\frac{1}{v})}}\right.$. Suppose $w=1$ and v successively $=1, 2, 3, 4, 5,$ &c. then the measure of the effect will be $\frac{\sqrt{2}}{4+\sqrt{8}+\sqrt{2}}$ or $3-\sqrt{8}$, $\frac{\sqrt{24}}{12+\sqrt{96}+\sqrt{6}}$, $\frac{\sqrt{108}}{24+\sqrt{432}+\sqrt{12}}$, $\frac{\sqrt{300}}{40+\sqrt{1280}+\sqrt{20}}$, $\frac{\sqrt{750}}{70+\sqrt{3000}+\sqrt{25}}$ &c. Let v be a large number, the proximate measure of the effect will then be $=$ $\frac{v+\frac{1}{2}}{2v+2+2v+1+1+\frac{1}{2v}}$ or $\frac{2v+1}{8v+8+\frac{1}{v}}$; and this expression will be ultimately $=\frac{1}{4}$. Wherefore, comparing this result with that in art. 12, it appears, that, in whatever way the *maximum* be procured, the force which impels the weight can never amount to one fourth part of the direct action of the power.

18. Hitherto we have not taken into account the force expended in impressing motion upon the parts of the machine which connect the power and weight. Let a, b, c, d, &c. denote the masses of the communicating parts, and let α, β, γ, δ, &c. be proportional to their corresponding velocities, and Q to that of the weight,

It is obvious. that the momentum of the part a is equal to the momentum of the mass $\frac{a\alpha}{Q}$: In the same manner, the momentum of b, c, d, &c. will be equal to that of the quantities of matter $\frac{b\beta}{Q}$, $\frac{c\gamma}{Q}$, $\frac{d\delta}{Q}$, &c. moving with the celerity of the weight to be raised. But from the permanency of the construction, these quantities are constant. Whence the total quantity of motion is the same with that of a mass $\frac{a\alpha+b\beta+c\gamma+d\delta}{Q}$, which is given. Let it be equal to q, and supposing, as before, the power $=p$ and the weight $=w$, the whole mass, on which the celerity of the weight to be raised must be impressed, will be denoted by $w+q$.

19. It is obvious that $\frac{w}{v}$ is still that part of the power which is sufficient to maintain the equilibrium, and that the motion is produced by the remaining part $p-\frac{w}{v}$ or $\frac{pv-w}{v}$. This accelerating force may be resolved into x, which is exerted against the compound weight $w+q$, and $\frac{pv-w}{v}-x$, or $\frac{pv-vx-w}{v}$, which acts directly upon the power p. But the velocity generated in a given time is (5) as the intensity of the force divided by the mass. The velocity of the power, therefore, will be denoted by $\frac{1}{p}\left(\frac{pv-vx-w}{v}\right)$ or $\frac{pv-vx-w}{pv}$. But the exertion of the force x, which urges the compound weight, is, in consequence of the mechanism, equal to the direct action of vx. Whence the celerity acquired in the same time will be ex-

pressed by $\frac{vx}{w+q}$. Therefore, from the conditions of the motion $\frac{vx}{w+q} : \frac{pv-vx-w}{pv} :: 1 : v$; consequently $\frac{v^2x}{w+q} = \frac{pv-vx-w}{pv}$, and reducing, $pv^3 + qvx \times wvx = pvw - w^2 + pqv - qw$, and dividing, $x = \frac{pvw-w^2+pqv-qw}{pv^3+qv+wv}$, or $\frac{(pv-w)(w+q)}{pv^3+qv+wv}$. Whence vx, the real force exerted upon the compound weight, is $= \frac{(pv-w)(w+q)}{pv^2+q+w}$. The intensity of force is, therefore, $= \frac{pv-w}{pv^2+q+w}$. Hence we shall obtain expressions for the space described, and the velocity of description. For $V = 2dT\left(\frac{pv-w}{pv^2+q+w}\right)$ and $S = dT^2\left(\frac{pv-w}{pv^2+q+w}\right)$.

20. Since the intensity of action is $= \frac{pv-w}{pv^2+q+w}$, the measure of effect will be $= \frac{pv-w}{p^2v^2+pq+pw}$. Supposing p to be variable, and taking the fluxion, we shall obtain, when the effect is a *maximum*,

$$\frac{\dot{p}v(p^2v^2+pq+pw)-(2\dot{p}pv^2+\dot{p}q+\dot{p}w)(pv-w)}{(p^2v^2+pq+pw)^2} = 0.$$

Whence $p^2v^3+pqv+pwv = (2pv^2+q+w)(pv-w) = 2p^2v^3 + pqv + pwv - 2pv^2w - qw - w^2$, and transposing, $p^2v^3 - 2pv^2w = qw + w^2$, and dividing, $p^2 - \frac{2w}{v}$, $p = \frac{qw+w^2}{v3}$, and resolving the quadratic, $p = \frac{w}{v} + \sqrt{\left(\frac{w^2}{v^2} + \frac{w^2}{v^3} + \frac{qw}{v3}\right)}$. If v be large, the value of p will be nearly $\frac{2w}{} + \frac{w}{2v^2} + \frac{q}{2v^2}$. Whence in machines, where the advantage is great, we may disregard the mo-

menta of the connecting parts, and consider the force which ought to be employed as double of what is barely able to maintain the equilibrium.

21. In our investigations, we have always supposed that the same accelerating force is uniformly exerted. But instances frequently occur, where the power applied increases or diminishes during the action of the machine. This variation may be affected by numberless circumstances, and the general hypothetical solution of the problem would involve tedious and complicated formulæ. We shall content ourselves with a familiar example. Suppose that a weight P is attached to one of the extremities of a rope, $WABP$, of equal and uniform texture, and applied to the circumference of a wheel, and to the other extremity a smaller weight W is appended.[3] PLATE IX, Fig. 4.

It is manifest, that P will at first descend solely by its excess of weight; but its exertion will be continually increased, from the addition of the portion of the rope BP, while the antagonist power W suffers an equal diminution.

---

[3] A machine, constructed upon this principle, is actually employed in some coal works. P is a light capacious bucket, W another that is strong and massy. When both are empty, W descends and elevates P; W is then loaded with coals, and, at the same time, a cock is opened which fills P with water. P then descends, by its superior weight, and raises the load. But when it reaches the bottom of the pit, it pushes up a valve, the water is discharged, and the action of the machine is renewed.

22. It will be proper to take into account the momentum of the wheel. Let it be supposed to be solid and homogeneous, and let the radius of the whole $AC=r$, and of the variable circle $CD=x$, and let $\pi=$ 6.2832; then the minute annulus $DEde$ is equal to the rectangle of its length and its breadth, or $\pi x\dot{x}$; but the velocity is directly as the distance from the centre of motion; whence the momentum of the annulus will be equal to that of $\frac{\pi x^2\dot{x}}{r}$ applied at A. And since $\int\frac{\pi x^2\dot{x}}{r}=\frac{\pi x^3}{3r}$, the momentum of the whole matter of the wheel is equal to the momentum of a quantity of matter $\frac{\pi r^3}{3r}$ or $\frac{\pi r^2}{3}$, having the velocity of the point A. But $\frac{\pi r^2}{2}=$ area or A and $\frac{\pi r^2}{3}=\frac{2}{3}A$, and hence the momentum of the wheel will be the same, if $\frac{2}{3}$ of its matter were collected and accumulated at its circumference.

PLATE IX. Fig. 3.

23. Now let us denote the weight to be raised, together with that of the rope and $\frac{2}{3}$ of the wheel, $p=$ the power applied, $h=$ the length of the rope, or the whole height of ascent, $a=$ the weight of the rope, and $b=\frac{2}{3}$ of the weight of the wheel, and $x=$ the space through which the ascent is already made. The force applied is therefore $=p+\frac{ax}{h}$ and the resistance opposed $=w-b-\frac{ax}{h}$, consequently, the accelerating force, which must be the dif-

ference of these, is $=p+b-w+\frac{2ax}{b}$, or $\frac{pb+bb-wb+2ax}{b}$. But this must be diffused through the whole mass $w+p$; wherefore the intensity of action is $=\frac{pb+bb-wb+2ax}{pb+wb}$. It was shewn in art. 5, that $V\dot{V}=2d\times\frac{pb\dot{x}+bb\dot{x}-wb\dot{x}+2ax\dot{x}}{pb+wb}$, and integrating, $\frac{1}{2}V^2=2d\times\frac{pbx+bbx-wbx+ax^2}{pb+wb}$; consequently $V=2\sqrt{d}\sqrt{\left(\frac{pbx+bbx-wbx+ax^2}{pb+wb}\right)}$; hence the final velocity is $=2\sqrt{dh}\sqrt{\left(\frac{p+b-w+a}{p+w}\right)}$,

24. Let the power applied be equal to the whole weight of the rope, and suppose that nothing is appended to the other; then, if the momentum of the wheel be disregarded, the final velocity will be $=2\sqrt{dh}\times\sqrt{\frac{p}{2p}}$, or $\sqrt{2dh}$. But the velocity which a body would acquire by descending through the same space, if entirely disengaged, is $\sqrt{4dh}$; its velocity is, therefore, to that of the former, as $1:\sqrt{2}$.

25. It was shewn in art. 5, that $\dot{T}=\frac{\dot{S}}{V}$; whence, from the formulæ in art. 23; $\dot{T}=\frac{\dot{x}}{2\sqrt{d}\sqrt{\left(\frac{pbx+bbx-wbx+ax^2}{pb+wb}\right)}}$, or $\dot{T}=\frac{1}{2\sqrt{d}}\times\frac{\dot{x}}{\sqrt{x^2\times\frac{a}{pb+wb}+x\times\frac{pb+bb-wb}{pb+wb}\times x}}$, or multiplying the numerator and denominator by $\sqrt{\left(\frac{pb\times wb}{a}\right)}$, we shall obtain $\dot{T}=\frac{1}{2\sqrt{d}}\times$

$\sqrt{\left(\frac{ph+wb}{a}\right)} \times \frac{\dot{x}}{\sqrt{\left(x^2 \times \frac{ph+bb-wb}{a} \times x\right)}}$. Put $\frac{ph+bb-wb}{a} = n$; then $\dot{T} = \sqrt{\left(\frac{ph+wb}{4ad}\right)} \times \frac{\dot{x}}{\sqrt{(x^2+nx)}}$; wherefore $T = \sqrt{\frac{ph+wb}{4ad}} \times \int \frac{\dot{x}}{\sqrt{(x^2 \times nx)}}$.

26. To find the fluent of $\frac{\dot{x}}{\sqrt{(x^2+nx)}}$, put $\sqrt{(x^2+nx)} = x+z$; then $x^2+nx = x^2+2zx+z^2$ and $nx = 2zx+z^2$; and transposing, $nx-2zx = z^2$ and dividing, $x = \frac{z^2}{n-2z}$, and taking the fluxion, $\dot{x} = \frac{2z\dot{z}(n-2z)+2z^2\dot{z}}{(n-2z)^2}$, or $\frac{2nz\dot{z}-2z^2\dot{z}}{(n-2z)^2}$. But $\sqrt{(x^2+nx)} = x+z$, or substituting the value of x, $\sqrt{(x^2+nx)} = \frac{z^2}{n-2z}+z$, or $\frac{z^2+nz-z^2}{n-2z}$, or reducing, $= \frac{nz-z^2}{n-2z}$; whence the expression $\frac{\dot{x}}{\sqrt{(x^2+nx)}} = \frac{2nz\dot{z}-2z2z}{(n-2z)^2}$, divided by $\frac{nz-z^2}{n-2z}$, or $\frac{2z}{n-2z}$. The fluent of $\frac{2\dot{z}}{n-2z}$ is C—Hyperbolic Logarithm, $n-2z$. To find the correction, suppose $2z = o$; in this case the fluent vanishes, and C=Hyp. Log. n; whence the true fluent is Hyp. Log. n—Hyp. Log. $n-2z$, or Hyp. Log. $\frac{n}{n-2z}$. But $z = \sqrt{(x^2+nx)}-x$, and substituting the fluent, is Hyp. Log. $\frac{n}{n+2x-2\sqrt{(x^2+nx)}}$. To procure a more convenient expression,

multiply the numerator and denominator by $n+2x+2\sqrt{(x^2+nx)}$; then we have Hyp. Log. $\frac{n(n+2x+2\sqrt{(x^2+nx)})}{n^2}$, or Hyp. Log. $\frac{n+2x+2\sqrt{(x^2+nx)}}{n}$, and resuming the value of n,

$$T=\sqrt{\left(\frac{pb+wb}{4ad}\right)}\times H,L,$$

$$\frac{2x+\frac{pb+bb-wb}{a}-2\sqrt{\left(x^2+\frac{pb+bb-wb}{a}.x\right)}}{\frac{pb+bb-wb}{a}}.$$

or by reduction, $T=\sqrt{\left(\frac{pb+wb}{4ad}\right)}\times H,L,$

$$\frac{2ax+pb+bb-wb+2\sqrt{(a^2x^2+apbx+abbx-awbx}}{pb+bb-wb}.$$

When $x=h$, we obtain for the whole time of the performance $T=\sqrt{\left(\frac{pb+wb}{4ad}\right)}\times H,L,$ $\frac{2a+p+b-w+2\sqrt{(a^2+ap+ab-aw}}{p+b-w}$. The value of p, when the comparative quantity of action is a *maximum*, may also be determined, but it will be involved in a transcendent equation.

27. When the resistance of the parts of a machine is inconsiderable, we perceive from all these investigations the importance of continuing the action. The successive impulses are retained and accumulated, and the performance constantly increases. The whole quantity of action, produced by the machine, is not in the simple ratio of the time of continuance, but in that of the square.

28. When we attempt to take the resistance of the moving parts of the machine into the account, we have great difficulties to encounter. Friction is affected by numberless circumstances; by the nature of the substances employed in the

construction; by their form; by the degree of polish; by their velocity, &c. Nor is it probable that its quantity can be derived from general principles; it must often be determined from the individual case, and can never be accurately ascertained. Friction may be considered as a continual retarding force. It may therefore be compared with that of gravity, and its effect may be estimated from that of a counteracting weight. The mass of the connecting parts, and their friction, both contribute to diminish the celerity of the motion; but they produce this retardation in different ways. The momentum which must be impressed upon the connecting parts of the machine requires a greater diffusion of power, and thus diminishes in some degree its effect. Friction does not alter the general mass, but reduces the quantity of accelerating force, and consequently the intensity of its action. If the quantity of friction were equal and constant, it is obvious, that if the moving power exceed it, the motion would be perpetually accelerated. But this is very far from the fact; for all the motions with which we are acquainted tend to an uniform celerity, and in a certain time would actually attain it. We may therefore conclude, that in the same machine, the friction increases in a certain ratio with the velocity. The great desideratum in mechanics is to determine the law of progression, and our deductions upon this subject must be considered as merely hypothetical.

29. Suppose, as before, $w=$ the weight to be raised; $q=$ the mass, which, if attached to the weight, would have the momentum of the connecting parts; $p=$ the power employed; $v=$ the *advantage*; and let the friction be equal

to φ, some function of the celerity of the weight. Because the moving parts of the machine remain the same as before, it is manifest that the intensity of action will be proportioned to the quantity of accelerating force; whence $p-\frac{w}{v} : p-\frac{w}{v}\varphi$ or $pv-w : pv-w-v\varphi ::$ $\frac{pv-w}{pv^2+qv+w} : \frac{pv-w-v\varphi}{pv^2+qv+w}$, the true force which constantly acts upon the weight. Whence, if the quantity $v\varphi$ be less than $pv-w$, the motion will be accelerated; if $v\varphi$ be greater than $pv-w$, the motion will be retarded. In the natural progress of motion, the celerity at first increases, or $v\varphi$ constantly approaches to an equality with the constant quantity $pv-w$, and when this equality takes place, the velocity is perfectly uniform. Hence the final celerity may be determined from the equation $\varphi=\frac{pv-w}{v}$. Thus, if we suppose that the friction increases in the simple ratio of the velocity, then $mV=\frac{pv-w}{v}$ or $V=\frac{pv-w}{mv}$. If $\varphi=mV^{\frac{1}{n}}$, then $V=\left(\frac{pv-w}{mv}\right)^n$.

30. We may neglect the performance which is made during the first acceleration of motion as inconsiderable, when compared with the whole. The quantity of action will therefore be as V; and if the power affects the friction only by altering the velocity, the comparative action will be denoted by $\frac{V}{p}$; whence the performance will be a *maximum*, when $p\dot{V}=\dot{V}p$. If, as before, $\varphi=mV^{\frac{1}{n}}$; then $\left(\frac{pv-w}{mv}\right)^{n-1}\times\frac{n\dot{p}}{m}$ $\times p=\dot{p}\left(\frac{pv-w}{mv}\right)$, and reducing $\frac{np}{m}=\frac{pv-w}{mv}$, and

$nvp = pv - w$, and transposing. $w = pv - pvn$, and dividing, $p = \frac{w}{v - vn}$. Or put $\frac{w}{v}$, the power which would barely maintain an equilibrium $= \pi$; then $p = \pi \times \frac{1}{1-n}$.

31. The law of the increase of velocity at first may also be ascertained. For (art. 4), the time corresponding to the velocity V is $= \int \frac{\dot{V}}{2dF}$, and in the present case $T = \int \frac{1}{2d} \times \frac{pv^2 + q + w}{pv - w - v\varphi} \times \dot{V}$. As φ is a function of V, the fluent may always be expressed at least by an infinite series.—These formulæ might also be applied to rectilineal motions performed in resisting *media*; but this would rather be a digression from the subject.

MECHANICS.

DESCRIPTION OF A SIMPLE AND POWERFUL CAPSTANE.

THIS capstane is represented in Fig. 1, where *AD* is a compound barrel consisting of two cylinders *C*, *D* of different radii. The rope *DEC* is fixed at the extremity of the cylinder *D*, and after passing over the pulley *E*, which is attached to the load by means of the hook *F*, it is coiled round the other cylinder *C*, and fastened at its upper end. *AB* is the bar by which the compound barrel *CD* is urged about its axis, so that the rope may coil round the cylinder *D*, while it unwinds itself from the cylinder *C*. Let us now suppose that the diameter of the part *D* of the barrel is 21 inches, while the diameter of the part *C* is only 20, and let the pulley *E* be 20 inches in diameter. It is evident, then, that when the barrel *AD* is urged round by a pressure exerted at the point *B*, 63 inches of rope will be gathered upon the cylinder *D*, and 60 inches will be unwinded from the cylinder *C* by one revolution of the bar *AB*, these numbers representing the circumference of each cylinder. The quantity of wound rope, therefore, exceeds the quantity that is unwound by 63—60, or 3 inches, the difference of their respective perimeters; and the half of this quantity, or $1\frac{1}{2}$ inches, will be the space through which the load or the pulley *E* moves by one turn of the bar. But if a simple capstane of

PLATE IX, Fig. 1, App. Description of a simple capstane.

the same dimensions had been employed, the length of rope coiled round the barrel by one revolution of the bar would have been 60 inches, and the space described by the pulley or load to be overcome would have been 30 inches. Now, it is a maxim in mechanics,[1] that the power of any engine is universally equal to the velocity of the impelled point divided by the velocity of the working point, or to the velocity of the power divided by the velocity of the weight, that is, to the velocity of the point *B* divided by the velocity of the pulley *E*; consequently if the lever in both capstanes is the same, and the diameter of their barrels equal, the power of the common will be to the power of the improved capstane as $1\frac{1}{2}$ to 30, that is, inversely as the velocity of their weights, and the power of the latter will be $\frac{30}{1\frac{1}{2}} = 20$, or in other words, will be equivalent to a 20 fold tackle of pulleys.[2] If it is wished to double the power of the machine, we have only to cover the cylinder *C* with lathes a quarter of an inch thick, so that the difference between the radii of each cylinder may be half as little as before; for the power of the capstane increases as the difference between the radii of the cylinders is diminished. As we increase the power, therefore, we increase the strength of our machine, while all other engines are proportionably enfeebled by an augmentation of power. Were we, for example, to increase the power of the common

Method of computing its power.

[1] See vol. i, pp. 57, 58.

[2] In practice it will be found equivalent to a 26 fold tackle of pulleys, as about *one third* of the power of a system of pulleys is destroyed by friction and the bending of the ropes.

capstane, we must diminish the barrel in the same proportion, supposing the bar or handspike not to admit of being lengthened, and we not only weaken its strength, but destroy much of its power by a greater flexure or bending of the ropes.

Convertible into a crane.

The reader will perceive that this capstane may be converted into a crane or windlass for raising weights, merely by giving the compound barrel AB a horizontal position, and substituting a winch instead of the bar AB. The superiority of such a crane above the common one is obvious from what has been said; but it has this additional advantage, that it allows the weight to stop at any part of its progress, without the aid of a ratchet wheel and catch, from the two parts of the rope pulling on contrary sides of the barrel. The rope, indeed, which coils round the larger part of the barrel acts with a larger lever, and consequently with greater force than the other; but as this excess of force is not sufficient to overcome the friction of the gudgeons, the weight remains stationary in any part of its path.

A crane of this kind was erected in 1797 at Bordenton in New Jersey, by Mr. M'Kean, for the purpose of raising logs of wood to the frame of a saw mill, which was 10 feet distant from the ground. The diameter of the largest cylinder was 2 feet, and its length 8 feet; the other cylinder was 1 foot in diameter, and of the same length with the largest. The difference of their circumferences, therefore, was 3 feet, and the log would move through a space of 18 inches with 1 turn of the handspike; and through the required height with only 8 turns. The length of the bar or handspike was 6 feet, which, at the point where the power was applied, described a circle of about 30 feet, so that the power of the crane was as 1 to 20. The length of the rope was only 55 feet, where-

as if the weight had been raised through the same height with a similar power by means of a tackle of pullies, 270 feet of rope must have been employed. In the latter case, however, the rope sustains only $\frac{1}{270}$ of the weight, but in the former it supports one half of the load.

In describing a capstane of this kind, Dr. Robison asserts,[1] that when the diameters of the cylinders which compose the double barrel are as 16 to 17, and their circumferences as 48 to 51, the pulley is brought nearer to the capstane by about 3 inches for each revolution of the bar. This however, is a mistake, as the pulley is brought only $1\frac{1}{2}$ inches nearer the axis. This will be evident, if we conceive a quantity of rope equal to the circumference of the larger cylinder to be winded up all at once, and a quantity equal to the circumference of the lesser one to be unwinded all at once. In the present case, 51 inches of rope will be coiled round the larger part of the barrel by one revolution of the capstane bar, and consequently the load would be raised $25\frac{1}{2}$ feet, the rope being doubled. Let 48 inches of rope be now unwinded from the lesser cylinder, and the load will sink 24 feet; therefore $25\frac{1}{2} - 24 = 1\frac{1}{2}$ feet is the whole height or distance through which the weight has been moved.

Dr. Robison observes that the capstane now described was invented by an untaught but ingenious country tradesman. It appears, however, to be the invention of George Eckhardt, and wise of Mr. Robert M'Kean of Philadelphia, son to the present governor of Pennsylvania. Mr. Gregory observes, that he has seen a figure of this capstance among some Chinese drawings nearly a century old.

---

[1] Encyclopœdia Britannica Supplement Art. *Machinery*, vol. xx, p. 107.

MECHANICS.

ACCOUNT OF AN IMPROVEMENT ON THE BALANCE.

Improvement on the balance.

It must be a matter of great convenience to the experimental philosopher, as well as the practical chemist, to have a method of ascertaining the gravities of bodies without the aid of a number of small weights. The following contrivance has occurred to me as likely to answer this purpose, while it has the advantage of facility in its application, and accuracy in its results.

In Figure 6, *FA*, *FB*, represent the arms of a common balance. A micrometer screw *DC*, is fitted to the arm *FA*, in such a manner, that when it is turned round by the nut *D*, it neither approaches to, nor recedes from, the centre of motion *F*. The screw *DC* works in a female screw in the small weight *n*, and, by revolving in one direction, carries this weight from *S* to *R*, and thus gives the preponderance to the scale *G*. When the weight *n* is screwed close to the shoulder *S*, the scales are in equilibrio; but when it is made to recede from *S*, this equilibrium is destroyed, and the same effect is produced as if an additional weight had been put into the scale *G*. In most cases, it might be preferable to make the scales in equilibrio, when the weight *n* is equi-

PLATE XIII, Fig. 6.

distant from S and R. The recession of the weight n from the shoulder S, is measured by a scale of equal parts engraven on the arm AF. Each unit of this scale is equivalent to one revolution of the screw, and is subdivided into 100 parts by a divided scale on the circumference of the nut D, to which the projecting part of the shoulder S is the index.

Let us now see what weight put into the scale G, or suspended at A, will be equivalent to the given weight n, when moved to a given distance from S. It is evident from the property of the lever, that if x be the equivalent weight required, $FA : Sn = n : x$, and $x = \frac{Sn \times n}{FA}$; that is, the real weight n exceeds the equivalent weight x, as much as FA exceeds Sn. Let n be $= 20$ grains, $Sn = 5$ tenths of an inch, and $FA = 10$ inches, then $x = \frac{20 \times .5}{10} = 1$ grain; so that by shifting a weight 20 grains 5 tenths of an inch from S, the same effect is produced as if 1 grain had been thrown into the scale G. By having several weights instead of n, the utility of this contrivance may be much increased.

MECHANICS.

A MECHANICAL METHOD OF FINDING THE CENTRE OF GRAVITY.

As it is frequently necessary in mechanical operations to find the centre of gravity, the following practical method may probably be acceptable to some readers, as it is not to be met with in any of the elementary treatises in our language.— On the centre of gravity,

1. If the body, whose centre of gravity is to be found, can be easily suspended by a thread or cord, then the centre of gravity will be situated in some point in the direction of the cord prolonged. Suspend the body at another part, so that the new direction of the cord may be nearly at right angles with its former direction; then, as the centre of gravity must lie somewhere in the new direction of the cord prolonged, the point where these two lines (formed by prolonging the cord) intersect each other, will determine the centre of gravity.

2. If the body is of such a size or quality that it cannot be conveniently suspended, place it upon an horizontal edge so that it may be in equilibrio; the horizontal edge will make a line or mark on the body in the same direction with itself, and the centre of gravity will be in some point in this line. Balance the

body a second time, so that the line upon the body may be nearly at right angles to the horizontal edge, which will make a new line or mark upon the body; the centre of gravity therefore will be somewhere in this new line, and consequently in the point where it intersects the former line.

3. If the body is so flexible that it can neither be suspended nor balanced, then let a board be balanced, as in case 2[d], and upon it, when balanced, lay the body, whose centre of gravity is to be found, in such a manner that the board may still be in equilibrio; then the centre of gravity will be in a line opposite to that which is made on the board by the horizontal edge; and by shifting the position of the board, and again balancing it, a new line will be found, the intersection of which, with the former line, will determine the centre of gravity.

HYDRAULICS.

ON THE STEAM ENGINE.[1]

THE superiority of inanimate power to the exertions of animals in turning machinery has been universally acknowledged. In the former, the power generally continues its action without the smallest intermission, but frequent and long relaxations are necessary for restoring the strength and activity of exhausted animals. There are many places, however, where a sufficient quantity of water cannot be procured, or where it cannot be employed for the want of proper declivities; and there are situations also which are highly unfavourable for the erection of windmills. But even when water and wind mills can be conveniently erected, there is such a variation in the impelling power, arising from accidental and unavoidable causes, that sometimes, in the case of water, and often in the case of

Importance of the steam engine.

[1] The theory of the steam engine is given at great length by the Abbe Bossut, in his Traite de Hydrodynamique, 1785, tom. i, p. 119, § 145, under the title *La Machine a Feu*; and also by Pony, in his Nouvelle Architecture Hydralique, part 2d. In the last of these works, the construction of the engine is very minutely described, and illustrated by a great number of engravings.

wind, there is not a sufficient force for putting the machinery in motion. In such circumstances, the discovery of steam as an impelling power may be regarded as a new æra in the progress of the arts. Wherever fire and water can be obtained, we can procure a quantity of steam capable of overcoming the most powerful resistance, and free from those accidental variations of power which affect every inanimate agent that has hitherto been employed as the first mover of machines.

History of the steam engine.

The invention of the steam engine has been universally ascribed by the English to the marquis of Worcester, and to Papin by the French; but there can be little doubt that about 34 years prior to the date of the marquis's invention, and about 61 years before the publication of Papin's, steam was applied as the impelling power of a stamping engine by one *Brancas* an Italian, who published an account of his invention in the year 1629. It is extremely probable, however, that the marquis of Worcester was unacquainted with the discovery of Brancas, and that the fire engine which he mentions so obscurely in his Century of inventions, was the result of his own ingenuity.[2]

The utility of steam as an impelling power being thus known, the ingenious Captain Savary took advantage of this important discovery, and invented an engine which raised water by the expansion and condensation of steam. Several of Savary's engines were actually erected in England and in France, but they were never capable

[2] It is said that Gerbert employed steam before the time of the marquis of Worcester, to produce the sounds for his automata

of raising water from a depth which exceeded 35 feet.

The steam engine received great improvements from the hands of Newcomen, Beighton, Blakey, and other ingenious men; but it was brought to its present state of perfection by the celebrated Mr. Watt of Birmingham, one of the most accomplished engineers of the present age. Hitherto the steam engine had been employed merely as a hydraulic machine for draining mines or for raising water; but in consequence of Mr. Watt's improvements, it has for a series of years been employed as the impelling power or first mover of almost every species of machinery.

Figure 1, of Plate X, represents one of Mr. Watt's latest engines. *CD* is the boiler in which the water is converted into steam by the heat of the furnace *D*. It is sometimes made of copper, but more frequently of iron; its bottom is concave, and the flame is made to circulate round its sides, and is sometimes conducted by means of flues through the very middle of the water, so that as great a surface as possible may be exposed to the action of the fire. In some of Mr. Watt's engines, the fire contained in an iron vessel was introduced into the very middle of the water, and the outer boiler was formed of wood, as being a slow conductor of heat. When the furnaces are constructed in the most judicious manner, 8 square feet of the boiler's surface must be acted upon by the fire or the flame, in order to convert 1 cubic foot of water into steam in the space of an hour; and this effect will be produced by between $\frac{1}{8}$ or $\frac{1}{12}$ of a bucket of good Newcastle coals. When fire is applied to the boiler, the water does not evaporate into steam till it has reached the temperature of 212°

PLATE X, Fig. 1. Description of Mr. Watt's steam engine.

of Fahrenheit, or the boiling point. This arises from the superincumbent weight of the atmosphere; for when the water is heated in a vessel exhausted of air, steam is generated even below the temperature of 96°, or blood-heat. When the water, however, is pressed by air or steam more condensed than the atmosphere, a temperature greater than 212° is necessary for the production of steam; but the heat requisite for this purpose increases in a less ratio than the pressures to be overcome. The steam which is produced in the boiler CD is about 1800 times rarer than water, and is conveyed through the steam-pipe CE into the cylinder G, where it acts upon the piston q, and communicates motion to the great beam AB. But before we proceed to consider the manner by which this motion is conveyed, we shall point out the very ingenious method which Mr. Watt has employed for supplying the boiler regularly with water, and preserving it at the same height OP. This is absolutely necessary in order that the quantity and elasticity of the steam in the boiler may be always the same. The small cistern u, placed above the boiler, is supplied with water from the hot well h by means of the pump z and the pipe f. To the bottom of this cistern is fitted the pipe ur which is immersed in the water OP, and is bent at its lower extremity in order to prevent the entrance of the rising steam. A crooked arm ud attached to the side of the cistern u, supports the small lever $a'b'$, which moves upon d' as a centre. The extremity b' of this lever carries, by means of the wire $b'P$, a stone or piece of metal P, which hangs just below the surface of the water in the boiler, and the other extremity a' is connected by the wire $a'u$ with a valve at

Method of supplying the boiler with water.

the bottom of the cistern *u*, which covers the top of the pipe *u r*. Now, it is a maxim in hydrostatics,[s] that when a heavy body is suspended in a fluid, the body loses as much of its weight as the quantity of water which it displaces. When the water *O P*, therefore, is diminished by part of it being converted into steam, the upper surface of the body *P* will be above the water, and its weight will consequently be increased in proportion to the quantity of the body that is out of the water; or, to speak more precisely, the additional weight which the body *P* receives by a diminution of the water in the boiler, is equal to the weight of a quantity of the fluid, whose bulk is the same as the part of the body *P* which is above the water. By this addition to its weight, the stone *P* will cause the extremity *b'* of the lever to descend, and by elevating the arm *a' d'*, will open the valve at the top of the pipe *u r*, and thus gradually introduce a quantity of water into the boiler, equal to that which was lost by evaporation. This process is continually going on while the water is converting into steam; and it is evident that too much water can never be introduced; for as soon as the surface of the water coincides with the upper surface of the body *P*, it recovers its former weight, and the valve at *u* shuts the top of the pipe *u r*. In order to know the exact height of the water in the boiler, two cocks *k* and *l* are employed, the first of which, *k*, reaches to within a little of the height at which the water should stand, and the other, *l*, reaches a very little below that height. If the water stands at the desired height, the cock *k* being

[s] See vol. i, p. 189.

opened will give out steam, and the cock *l* will emit water, in consequence of the pressure of the superincumbent steam on the water *O P*; but if water should issue from both cocks, it will be too high in the boiler, and if steam issues from both, it will be too low. As there would be great danger of the boiler's bursting if the steam should become too strong, it is furnished with the safety valve *x*, which is loaded in such a manner, that its weight, added to that of the atmosphere, may exceed the pressure of the interior steam when of a sufficient strength. As soon as the steam becomes so elastic as to endanger the boiler, its pressure preponderates over the pressure of the safety valve and the atmosphere. The valve therefore opens, and the steam escapes from the boiler, till its strength is sufficiently diminished, and the safety valve shuts by the predominance of its pressure over that of the interior steam. By opening the safety valve, the engine may be stopt at pleasure. A small rectangular lever, with equal arms, is fixed upon the side of the valve, and connected with its top. To one of these arms a chain is attached, which passes over a pulley from a horizontal to a vertical direction, and by pulling which, the safety valve is opened, and the machine stopped.

Safety valve.

From the dome of the boiler proceeds the steam-pipe *G E*, which conveys the steam into the top of the cylinder *G* by means of the steam-valve *a*, and into the bottom of the cylinder by means of the valve *c*. The branch of the pipe which extends from *a* to *c* is cut off in Fig. 1, in order to shew the valve *b*, but is distinctly visible in Fig. 2, which is a view of the pipes and valves in the direction *F M*. The cylinder *G* is sometimes inclosed in a wooden case, in

Fig. 2.

order to prevent it from being cooled by the ambient air; and sometimes in a metallic case, that it may be surrounded and kept warm by a quantity of steam, which is brought from the steam-pipe *E C*, through the pipe *E G*, by turning a cock. It is generally thought, however, that little benefit is obtained by encircling the cylinder with steam, as the quantity thus lost is almost equal to what is destroyed by the coldness of the cylinder. After the steam, which was admitted above the piston *q* by the valve *a*, and below it by the valve *c*, has performed its respective offices of depressing and elevating the piston, and consequently the great beam *A B*, it escapes by the eduction valves *b* and *d* into the condenser *i*, where it is converted into water by means of a jet playing in the inside of it. The water thus collected in the condenser is carried of, along with the air which it contains, into the hot well *h*, by the air pump *c*, which is wrought by the piston road *T M*, attached to the great beam *A B*. From the hot well *h* this water is conveyed by the pump *z* and the pipe *f*, into the cistern *u*, for the purpose of supplying the boiler. The water *w*, which renders air-tight the pump *e*, and supplies the jet of water in the condenser, is furnished by the pump *g*, which is worked by the great beam. The steam and eduction valves *a*, *c*, *b*, *d*, are opened and shut by the spanners *a M*, *d M*, *c N*, *b N*, whose handles *M* and *N* are moved by the plugs 1, 2, fixed to *T N* the piston rod of the air pump. This part of the machinery has been called the *working geer*; and is so constructed that the steam and eduction valves can be worked either by the hand or by the piston of the air pump. The piston rod *B*, which moves the piston *q*, passes through a box

Construction of the cylinder.

Fig. 1 & 2.

or collar of leathers fixed in a strong metallic plate on the top of the cylinder. The rod is turned perfectly cylindrical, and is finely polished, in order to prevent any air from passing by its sides. The top V of the piston rod R is fixed to the machinery TV, which is called the parallel joint, and is so contrived as to make the rod VR ascend and descend in a vertical or perpendicular direction. When the lever or beam rises into its present position from a horizontal one, the piston rod VR has a tendency to move towards μ, and would move towards it were the bar $\mu\nu$ fixed in its present position; for while the point V rises, the bar μV also rises; at the same time the angle $V\mu\nu$ increases, and likewise the angle $\lambda V\mu$; so that the vertex V of the angle $\lambda V\mu$ would move towards T. The bar $\mu\nu$, however, is not at rest, but moves round the fixed point ν, and rises along with the point V; while $\mu\nu$, therefore, rises upon ν as a centre, the adjoining bar μT moves round the point T towards V, the angle $T\mu\nu$ increases, and the point μ approaches to V, and keeps VR in a perpendicular position; so that whatever tendency the point V has towards T by the increase of the angle $\lambda V\mu$, it has an equal tendency in the contrary direction, by the increase of the angle $T\mu\nu$: but as the beam AB falls into a horizontal position, all these motions are reversed. When the piston rod VR rubs most upon the side of the collar of leathers nearest to a, the fixed point ν must be shifted a little in the contrary direction, viz. to the right hand of R. That the nature of this parallel joint may be better understood, it may be proper to observe, that all the bars which have been mentioned are double, as may be seen in the Figure, —that they move round centres at λ, T, V, μ, and

Parallel joint.

ν, and that the two bars between μ and V move between the bars at $\mu\nu$.[6]

In the steam-engines of Newcomen and Beighton, where the piston was raised merely by a counterweight at the extremity A of the great beam, the piston rod was connected with its other extremity by means of a chain bending round the arch of a circle fixed at B; but in Mr. Watt's improved engines with a double stroke, in which the piston receives a strong impulse upwards as well as downwards, the chain would slacken, and could not communicate motion to the beam. An inflexible rod, therefore, must be employed for connecting the piston with the beam, or the piston must be suspended by double chains, like those of engines for extinguishing fire. In some of Mr. Watt's engines, the latter of these methods was adopted. He then employed a toothed rack working in a toothed sector fixed at B, and afterwards fell upon the very superior method which we have now been describing.

Mode of converting a reciprocating into a rotatory motion.

All the engines which were constructed before the time of Mr. Watt were employed merely for raising water, and were never used as the first

[6] As the authors who have written on the steam engine have not taken any notice of the operation of the parallel point, it was thought proper to give the preceding description of it, which we trust will be satisfactory to the reader. The ingenious idea of making the piston rod ascend vertically, by a combination of circular motions, was suggested to Mr. Watt by attending to Suardi's pen; an instrument by which a variety of curves may be described by a combination of circular motions. The piston rod, however, does not ascend in a vertical line. It describes an algebraic curve; the deviations of which from a right line are too inconsiderable to be noticed in practice.

movers of machinery. Mr. R. Fitzgerald, indeed, published in the Transactions of the Royal Society, a method of converting the irregular motion of the beam into a continued rotatory motion, by means of a crank and a train of wheel work, connected with a large and massy fly, which, by accummulating the pressure of the machine during the working stroke, urged round the machinery during the returning stroke, when there is no force pressing it forward. For this new and ingenious contrivance, Mr. Fitzgerald received a patent, and proposed to apply the steam engine as the moving power of every kind of machinery; but it does not appear that any mills were erected under this patent. In order to convert the reciprocating motion of the beam into a circular motion, Mr. Watt fixed a strong and inflexible rod *AU* to the extremity of the great beam. To the lower end of this rod, a toothed wheel *U* is fastened by bolts and straps, so that it cannot move round its axis. This wheel is connected with another toothed wheel *S* of the same size, by means of iron bars, which permits the former to revolve round the latter, but prevents them from quitting each other. This apparatus is called the Sun and Planet wheels, from the similarity of their motion to that of the two luminaries. On the axis of the wheel *S* is placed the large and heavy fly-wheel *F* which regulates the desultory motion of the beam. When the extremity *A* of the great beam rises from its lowest position, it will bring along with it the wheel *U*, and cause it to revolve upon the circumference of the wheel *S*, so that the interior part of the former, or the part next the cylinder, will act upon the exterior part of the latter, or the part farthest from the cylin-

der, and put it in motion along with the fly *F*. After the wheel *U* has got to the top of the wheel *S*, the end *A* of the beam will have reached its highest position, and the wheel *S*, along with the fly, will have performed one complete revolution. When the wheel *U* passes from the top of *S* into its former position below it, the extremity *A* of the beam will also descend from its highest to its lowest position; so that for every ascent or descent of the piston or the great beam, the planet wheel *U* will make one turn, while the sun wheel and fly will perform two complete revolutions.

On account of the weight of the fly, and the great celerity of its motion, there is much friction between its gudgeons and the sockets in which they move. In order to diminish the heat which is thus generated, it is customary with the French engineers to add to the engine a small pump, which conveys a gentle stream of water to the gudgeons of the fly.

When the steam engine is employed to drive machinery in which the resistance is very variable, and where a determinate velocity cannot properly be dispensed with, Mr. Watt has applied a conical pendulum, which is represented at *m n*, for procuring an uniform velocity. This regulator consists of two heavy balls *m*, *n*, suspended by iron rods which move in joints at the top of the vertical axis *o p*, and is put in motion by the rope *o o* which passes over the pulleys *o*, *o*, and round the axis *o* of the fly. Since the velocity of the fly and sun wheel increases and diminishes with the quantity of steam that is admitted into the cylinder, let us suppose that too much is admitted,—then the velocity of the fly will increase, but the velocity of the vertical

Conical pendulum.

axis *o p* will also increase, and the balls *m n* will recede from the axis by the augmentation of their centrifugal force. By this recess of the balls, the extremity *p* of the lever *p s*, moving upon *y* as a centre, is depressed; its other extremity *s* rises, and by forcing the cock at *a* to close a little, diminishes the supply of steam. The impelling power being thus diminished, the velocity of the fly and the axis *o p* decrease in proportion, and the balls *m*, *n*, resume their former position.

Construction of the valves. PLATE XI, Fig. 1.

In Mr. Watt's improved engine, the steam and eduction valves are all puppet clacks. One of these valves, and the method of opening and shutting it, is represented in Fig. 1 of Plate XI. Let it be one of the eduction valves, and let *AA* be part of the pipe which conducts the steam into the cylinder, and *MM* the superior part of the pipe which leads to the condenser. At *OO*, the seat of the valve, a metallic ring, of which *n n* is a section, is fitted accurately into the top of the pipe *MM*, and is conical on the outer edge, so as to suit the conical part of the pipe. These two pieces are ground together with emery, and adhere very firmly when the contiguous surfaces are oxidated or rusted. The clack is a circular brass plate *m*, with a conical edge ground into the inner edge of the ring *n n*, so as to be air-tight, and is furnished with a cylindrical tail *m P*, which can rise or fall in the cavity of the cross-bar *NN*. To the top of the valve *m*, a small metallic rack *m F* is firmly fastened, which can be raised or depressed by the portion *E* of a toothed wheel, moveable upon the centre *D*. The small circle *D* represents a section of an iron cylindrical axis, whose pivots move in holes in the opposite sides of the pipe

AA. Its pivots are fitted into their sockets, so as to be air-tight; and the admission of air is farther prevented by screwing on the outside of the holes necks of leather soaked in rosin or melted tallow. One end of this axis reaches a good way without the pipe *AA*, and carries a handle or spanner *b N*, which may be seen in Fig. 1, Plate X, and which is actuated by the plugs 1, 2, of the rod *TN*. When the plug 2, therefore, elevates the extremity of the spanner *Nb*, during the ascent of the piston rod *TN*, the axle *D*, Plate XI, Fig. 1, is put in motion, the valve *m* is raised by means of the toothed racks *E* and *F*, and the steam rushes through the cavity of the circular ring *n n*, by the sides of the cross piece of metal *OO*, *NN*. When the valve needs repair, the cover *B*, which is fastened to the top of the valve box by means of screws, can easily be removed.

PLATE X, Fig. 1.

PLATE XI, Fig. 1.

Having thus described the different parts of the most improved steam engine, we shall now attend to the mode of its operation. Let us suppose that the piston is at the top of the cylinder, as is represented in the figure, and that the upper steam valve *a*, and the lower eduction or condensing valve *d*, are opened by means of the spanner *M*, while the lower steam valve *c*, and the upper eduction valve *b*, are shut; then the steam in the boiler will issue through the steam pipe *CE*, and the valve *a*, into the top of the cylinder, and by its elasticity depress the piston, to the very bottom. But when the piston *q* is brought to the bottom of the cylinder, the extremity *B* of the great beam is dragged down by the parallel joint *TV*. Its other extremity *A* rises, and the wheel *U* having passed over $\frac{1}{2}$ of the circumference of *S*, will have urged forward

Mode of operation.

the fly-wheel *F*, and consequently, the machinery attached to it, one complete revolution. When the piston *q* has reached the bottom of the cylinder, the piston-rod *TN* of the air pump, by the pressure of the plug 1 upon the spanner *M*, has shut the steam-valve *a*, and the eduction-valve *d*, while the plug 2 has, by means of the spanner *N*, opened the eduction-valve *b*, and the steam-valve *c*. The steam, therefore, which is above the piston, rushes through the eduction-valve *b* into the condenser *i*, where it is converted into water by the jet in the middle of it, and by the coldness arising from the surrounding fluid *w*, while, at the same time, a new quantity of steam from the boiler issues through the open steam-valve *c*, into the cylinder, forces up the piston, and, by raising one end of the working beam, and depressing the other, makes the wheel *U* describe the other semi-circumference of *S*, and causes the fly and the machinery on its axis to perform another complete revolution. As the plugs 1, 2, ascend with the piston *q*, they open or shut the steam and eduction-valves, and the operation of the engine will be thus continued for any length of time.

Value of Mr. Watt's improvements.

From this brief description of the steam-engine, the reader will be enabled to perceive the nature, and appreciate the value of Mr. Watt's improvements. It had hitherto been the practice to condense the steam in the cylinder itself, by the injection of cold water; but the water which is injected acquires a considerable degree of heat from the cylinder, and being placed in air, highly rarified, part of it is converted into steam, which resists the piston, and diminishes the power of the engine. When the steam is next admitted, part of it is converted into water

by coming in contact with the cylinder, which is of a lower temperature than the steam, in consequence of the destruction of its heat by the injection-water. By condensing the steam, therefore, in the cylinder itself, the resistance to the piston is increased by a partial reproduction of this elastic vapour, and the impelling power is diminished by a partial destruction of the steam which is next admitted. Both these inconveniencies Mr. Watt has in a great measure avoided, by using a condenser separate from the cylinder, and incircled with cold water;[x] and by surrounding the cylinder with a wooden case, and interposing light wood ashes, in order to prevent its heat from being abstracted by the ambient air.

The greatest of Mr. Watt's improvements consists in his employing the steam both to elevate and depress the piston. In the engines of Newcomen and Beighton, the steam was not the impelling power; it was used merely for producing a vacuum below the piston, which was forced down by the pressure of the atmosphere, and elevated by the counterweight at the other extremity of the great beam. The cylinder, therefore, was exposed to the external air at every descent of the piston, and a considerable portion of its heat being thus abstracted, a corresponding quantity of steam was of consequence destroyed. In Mr. Watt's engines, however,

[x] Even in Mr. Watt's best engines, a very small quantity of steam remains in the cylinder, having the temperature of the hot well *b*, or of the water, into which the ejected steam is converted. Its pressure is indicated by a barometer, which Mr. Watt has ingeniously applied to his engines for exhibiting the state of the vacuum.

the external air is excluded by a metal plate at the top of the cylinder, which has a hole it it for admitting the piston-rod; and the piston itself is raised and depressed merely by the force of steam.

When these improvements are adopted, and the engine constructed in the most perfect manner, there is not above $\frac{1}{4}$ part of the steam consumed in heating the apparatus; and, therefore, it is impossible that the engine can be rendered $\frac{1}{4}$ more powerful than it is at present. It would be very desirable, however, that the force of the piston could be properly communicated to the machinery without the intervention of the great beam. This, indeed, has been attempted by Mr. Watt, who has employed the piston-rod itself to drive the machinery; and Mr. Cartwright has, in his engine, converted the perpendicular motion of the piston into a rotatory motion, by means of two cranks fixed to the axis of two equal wheels which work in each other. Notwithstanding the simplicity of these methods, none of them have come into general use, and Mr. Watt still prefers the intervention of the great beam, which is generally made of hard oak, with its heart taken out, in order to prevent it from warping. A considerable quantity of power, however, is wasted by dragging, at every stroke of the piston, such a mass of matter from a state of rest to a state of motion, and then from a state of motion to a state of rest. To prevent this loss of power, a light frame of carpentry[1] has been employed by several engin-

[1] The great beam in Mr. Hornblower's engine, is constructed in this manner, and is formed upon truly scientific principles.

eers, instead of the solid beam; but after being used for some time, the wood was generally cut by the iron bolts, and the frame itself was often instantaneously destroyed. In some of the engines lately constructed by Mr. Watt, he has formed the great beam of cast iron, and while he has thus added to its durability, he has at the same time diminished its weight, and increased the power of his engine.

Encouraged by Mr. Watt's success, several improvements upon the steam engine have been made by Hornblower, Cartwright, Trevethick, and other engineers of this country. But it does not appear that they have either materially increased the power of the engine, or diminished its expence. Most of these improvements, on the contrary, excepting those of Hornblower, and the engineers just mentioned, consist merely in having adopted Mr. Watt's discoveries, in such a manner as not to infringe upon his patent.

In Figure I of Plate XIV, we have represented a new form which the steam engine has received in France. In particular situations it has some advantages over the common construction; but it is particularly remarkable for the ingenious contrivance by which the piston-rod is made to rise in a vertical line. This is effected by means of two beams AB and CD, moving upon the centres B and C, which are always of the same size, though represented otherwise in the figure, for want of room. The sum of the lengths of the two beams, viz. $CD+AB$, reckoning from the centres of motion C and B,

PLATE XIV, Fig. 1, App.

Another form of the steam engine.

principles. Dr. Robison observes, that it is stronger than a beam of the common form, which contains 20 times its quantity of timber.

must be equal to the horizontal distance between these centres. The piece of iron Anm has joints at A and m, and is equal in length to the difference of level between the centres of motion C and B. Now, when the beams AB and CD are in a horizontal position, the line joining the points A and m will form a vertical line; and when these beams have risen from this position through equal arches, the points A and m will be equally distant from that vertical line, which ought to coincide with the axis of the cylinder produced. The distances of A and m from this vertical line are obviously the versed sines of the arches which the beams have described; but as these arches, as well as their radii, are supposed equal, their versed sines, and consequently the distances of A and m from the vertical, are also equal. If, therefore, the piston-rod np be suspended at n, equidistant from A and m, the point n, and consequently the piston-rod, will move in a perpendicular direction. The point, in reality, describes an algebraic curve; but when the arches described are small, the deviation from the vertical does not exceed the 10th of an inch. In this engine I is the cylinder, Q the condenser, P the air-pump, wrought by a chain passing over the arched head, corresponding with op on the other side of CD; K is the pump which supplies the boiler by the pipe KN; LM is the steam-pipe, MG the furnace; H is the pump which furnishes the water in which the air-pump P is immersed, and is wrought by the chain yF and the wheel F. The machine is represented as raising water in the pump R, by means of the chain xE passing over the wheel E; but when a rotatory motion is required, the beam AB must be prolonged, and

the same apparatus fixed at its extremity, as is employed in Watt's steam engine.

Woolf's improvements.

About ten months ago, Mr. Arthur Woolf announced to the public a discovery respecting the expansibility of steam, which promises to be of very essential utility. Mr. Watt had formerly ascertained, that steam which acts with the expansive force of 4 pounds per square inch, against a safety valve exposed to the weight of the atmosphere, after expanding itself to four times the volume it thus occupies, is still equal to the pressure of the atmosphere. But Mr. Woolf has gone much farther, and has proved, that quantities of steam, having the force of 5, 6, 7, 8, 9, 10, &c. pounds on every square inch, may be allowed to expand 5, 6, 7, 8, 9, 10, &c. times its volume, and will still be equal to the atmosphere's weight, provided that the cylinder in which the expansion takes place, has the same temperature as the steam before it began to expand. It is evident, however, that an increase of temperature is necessary both to produce and to maintain this augmentation of the steam's expansive force above the pressure of the atmosphere. At the temperature of 212° of Fahrenheit, the force of steam is equal only to the pressure of the atmosphere, and, in order to give it an additional elastic force of 5 pounds per square inch, the temperature must be increased to about $227\frac{1}{2}°$, as is evident from the following table.

Woolf's improvements.

Table of the Pressures, Temperatures, and Expansibility of Steam, equal to the Force of the Atmosphere.

Elastic Force of Steam predominating over the Pressure of the Atmosphere, and acting upon a Safety Valve.	Degrees of Temperature requisite for bringing the Steam to the different Expansive Forces in the preceding Column.	N° of times its Vol^{e} that Steam of the preceding Force and Temperature will expand, and still continue equal to the pressure of the Atmosphere.
Pounds per square inch.	Degrees of Heat.	Expansibility.
5	227½	5
6	230¼	6
7	232¾	7
8	235¼	8
9	237½	9
10	239½	10
15	250½	15
20	259½	20
25	267	25
30	273	30
35	278	35
40	282	40

In this manner, by small additions of temperature, an expansive power may be given to steam, which will enable it to expand 50, 100, 200, 300, &c. times its volume, and still have the same force as the atmosphere.

Upon this principle Mr. Woolf has taken out a patent for various improvements on the steam engine, a short account of which we shall subjoin in the words of the specification.

'If the engine be constructed originally with the intention of adopting the preceding improvement, it ought to have two steam vessels of different dimensions, according to the expansive force to be communicated to the beam; for the

smaller steam cylinder must be a measure for the larger. For example, if steam of 40 pounds the square inch is fixed on, then the smaller steam vessel should be at least $\frac{1}{40}$ part the contents of the larger one. Each steam vessel should be furnished with a piston, and the smaller cylinder should have a communication both at its top and bottom, with the boiler which supplies the steam, which communications, by means of cocks or valves are to be alternately opened and shut during the working of the engine. The top of the small cylinder should have a communication with the bottom of the larger cylinder, and the bottom of the smaller one with the top of the larger, with proper means to open and shut these alternately by cocks, valves, or any other contrivance. And both the top and bottom of the larger cylinder should, while the engine is at work, communicate alternately with a condensing vessel, into which a jet of water is admitted to hasten the condensation. Things being thus arranged when the engine is at work, steam of high temperature is admitted from the boiler to act by its elastic force on one side of the smaller piston, while the steam which had last moved it has a communication with the larger cylinder, where it follows the larger piston now moving towards that end of its cylinder which is open to the condensing vessel. Let both pistons end their stroke at one time, and let us now suppose them both at the top of their respective cylinders ready to descend; then the steam of 40 pounds the square inch, entering above the smaller piston, will carry it downwards, while the steam below it, instead of being allowed to escape into the atmosphere, or applied to any other purposes, will pass into the larger

Woolf's improvements.

cylinder above its piston, which will take its downward stroke at the same time that the piston of the smaller cylinder is doing the same thing; and, while this goes on, the steam which last filled the larger cylinder, in the upward stroke of the engine, will be passing into the condenser, to be condensed in the downward stroke. When the pistons in the smaller and larger cylinder have thus been made to descend to the bottom of their cylinders, then the steam from the boiler is to be shut off from the top, and admitted to the bottom of the smaller cylinder, and the communication between the bottom of the smaller and the top of the larger cylinder is also to be cut off, and the communication to be opened between the top of the smaller and the bottom of the larger cylinder; the steam which, in the downward stroke of the engine, filled the larger cylinder, being now open to the condenser, and the communication between the bottom of the larger cylinder and the condenser cut off; and so on alternately, admitting the steam to the different sides of the smaller piston, while the steam last admitted into the smaller cylinder passes alternately to the different sides of the larger piston in the larger cylinder, the top and bottom of which are made to communicate alternately with the condenser.

'In an engine where these improvements are adopted, that waste of steam which arises in other engines, from steam passing the piston, is totally prevented, for the steam which passes the piston in the smaller cylinder is received into the larger.'

Mr. Woolf has also shewn how the preceding arrangement may be altered, and has pointed out various other modifications of his inven-

tion, and the method of applying his improvements to steam engines which are already constructed.

On the Power of Steam Engines, and the Method of Computing it.

From the account which has been given of the steam engine, and the mode of its operation, it must be evident that its power depends upon the breadth and height of the cylinder, or, in other words, on the area of the piston and the length of its stroke. If we suppose that no force is lost in overcoming the inertia of the great beam, and that the lever by which the power acts is equal to the lever of resistance; then, if steam of a certain elastic force is admitted above the piston *q*, so as to press it downwards with a force of a little more than 100 pounds, it will be able to raise a weight of 100 pounds hanging at the end of the great beam. When the piston has descended to the bottom of the cylinder, through the space of 4 feet, the weight will have risen through the same space; and 100 pounds raised through the height of 4 feet, during one descent of the piston, will express the mechanical power of the engine. But if the area of the piston *q*, and the length of the cylinder are doubled, while the expansive force of the steam, and the time of the piston's descent remain the same, the mechanical energy of the engine will be quadruple, and will be represented by 200 pounds raised through the space of 8 feet during the time of the piston's descent. The power of steam engines, therefore, is, *cæteris paribus*, in the compound ratio of

Power of steam engines.

PLATE X, Fig. 1.

the area of the piston, and the length of the stroke. These observations being premised, it will be easy to compute the power of steam engines of any size.

Method of computing it.

Thus, let it be required to determine the power of steam engines, whose cylinder is 24 inches diameter, and which make 22 double strokes in a minute, each stroke being 5 feet long, and the force of the steam being equal to a pressure of 12 pounds avoirdupois upon every square inch.[1] The diameter of the piston being multiplied by its circumference, and divided by 4, will give its area in square inches; thus, $\frac{24\times3.1416\times24}{4} = 452.4$, the number of square inches exposed to the pressure of the steam. Now if we multiply this area by 12 pounds, the pressure upon every square inch, we will have $452.4\times12=5428.8$ pounds, the whole pressure upon the piston, or the weight which the engine is capable of raising. But since the engine performs 22 *double* strokes, 5 feet long, in a minute, the piston must move through $22\times5\times2=220$ feet in the same time; and therefore the power of the engine will be represented by 5428.8 pounds avoirdupois, raised through 220 feet in a minute, or by 10.4 hogsheads of water, ale measure, raised through the same height in the same time. Now this is equivalent to $5428.8\times220=1194336$ pounds,

[1] The working pressure is generally reckoned at 10 pounds on every circular inch, and Smeaton makes it only 7 pounds on every circular inch. The effective pressure which we have adopted is between these extremes, being equivalent to 9.42 pounds on every circular inch.

or $10.4 \times 220 = 2288$ hogsheads raised through the height of 1 foot in a minute. This is the most unequivocal expression of the mechanical power of any machine whatever, that can possibly be obtained. But as steam engines were substituted in the room of horses, it has been customary to calculate their mechanical energy in *horse powers*, or to find the number of horses which could perform the same work. This indeed is a very vague expression of power, on account of the different degrees of strength which different horses possess. But still, when we are told that a steam engine is equal to 16 horses, we have a more distinct conception of its power, than when we are informed that it is capable of raising a number of pounds through a certain space in a certain time.

Horse powers.

Messrs. Watt and Boulton suppose a horse capable of raising 32,000 pounds avoirdupois 1 foot high in a minute, while Dr. Desaguliers makes it 27,500 pounds, and Mr. Smeaton only 22,916. If we divide, therefore, the number of pounds which any engine can raise 1 foot high in a minute, by these three numbers, each quotient will represent the number of horses to which the engine is equivalent. Thus, in the present example $\frac{1194336}{32000} = 37\frac{1}{3}$ horses according to Watt and Boulton; $\frac{1194336}{27500} = 43\frac{1}{3}$ horses, according to Desaguliers; and $\frac{1194336}{22916} = 52\frac{1}{7}$ horses, according to Smeaton. In this calculation, it is supposed that the engine works only eight hours a-day; so that if it wrought during the whole 24 hours, it would be equivalent to thrice the number of horses found by the preceding rule. We cannot help observing, and it is with sincere pleasure that we pay that tribute of respect to the honour and integrity of

Messrs. Watt and Boulton which has everywhere been paid to their talents and genius,—that in estimating the power of a horse, they have assigned a value the most unfavourable to their own interests. While Mr. Smeaton and Dr. Desaguliers would have made the engine in the preceding example equivalent to 52 or 43 horses, the patentees themselves state that it will perform the work only of 37. How unlike is this conduct to some of our modern inventors, who ascribe powers to their machines which cannot possibly belong to them, and employ the meanest arts for ensnaring the public!

Performance of Watt's steam engines.

Before concluding this article, we shall state the performance of some of these engines, as determined by experiment. An engine whose cylinder is 31 inches in diameter, and which makes 17 double strokes per minute, is equivalent to 40 horses, working day and night, and burns 11,000 pounds of Staffordshire coal per day. When the cylinder is 19 inches, and the engine makes 25 strokes of 4 feet each per minute, its power is equal to that of 12 horses working constantly, and burns 3700 pounds of coals per day. And a cylinder of 24 inches which makes 22 strokes of 5 feet each, performs the work of 20 horses, working constantly, and burns 5500 pounds of coals. Mr. Boulton has estimated their performance in a different manner. He states, that 1 bushel of Newcastle coals, containing 84 pounds, will raise 30 million pounds 1 foot high; that it will grind and dress 11 bushels of wheat; that it will slit and draw into nails 5 cwt. of iron; that it will drive 1000 cotton spindles, with all the preparation machinery, with the proper velocity; and that these effects are equivalent to the work of 10 horses.

HYDRAULICS

DESCRIPTION OF A WATER-BLOWING MACHINE.

THIS machine is so useful for conveying wind to the furnaces of iron forges, and the principle by which it operates is so curious, as to entitle it to the particular attention of the practical mechanic, as well as the speculative philosopher. Although it has been known and generally adopted on the Continent for above a century, yet it has neither been generally introduced into the forges of this country, nor has it found its way into many of our treatises upon machinery. Water-blowing machine.

Let *A B*, Fig. 2, be a cistern of water, with the bottom of which is connected the bended leaden pipe *B C H*. The lower extremity *H* of the pipe is inserted into the top of a cask or vessel *D E*, called the condensing vessel, having the pedestal *P* fixed to its bottom, which is perforated with two openings *M*, *N*. When the water, which comes from the cistern *A*, is falling through the part *C H* of the pipe, it is supplied by the openings or tubes *m*, *n*, *o*, *p*, with a quantity of air which it carries along with it. This mixture of air and water issuing from the aperture *H*, and impinging upon the surface of the stone pedestal *P*, is driven back and dispersed in PLATE IX, Fig. 2.

various directions. The air being thus separated from the water, ascends into the upper part of the vessel, and rushes through the opening *F*, whence it is conveyed by the pipe *FG* to the fire at *G*, while the water falls to the lower part of the vessel, and runs out by the openings *M*, *N*.

In order that the greatest quantity of air may be driven into the vessel *DE*, the water should begin to fall at *C* with the least possible velocity; and the distance of the lowest tubes *o*, *p*, from the extremity of the pipe *H* should be to the length of the vertical tube *CH* as 3 to 8, in order that the air may move in the pipe *FG* with sufficient velocity. The part of the tube between *op* and *H*, and the vessel *DE*, must be completely closed, to prevent the escape of the internal air.

The wind is supplied from the atmosphere.

Fabri and Dietrich imagined that the wind is occasioned by the decomposition of the water, or its transformation into gas, in consequence of the agitation and percussion of its parts. But M. Venturi,[1] to whom we are indebted for the first philosophical account of this machine, has shewn that this opinion is erroneous, and that the wind is supplied from the atmosphere; for when the lateral openings *m*, *n*, *o*, *p*, were shut, no wind was generated.

Hence the principal object in the construction of these machines is to combine as much air as possible with the descending current. With this view the water is often made to pass through a kind of cullendar placed in the open air, and perforated with a great number of small trian-

[1] Experimental Enquiry concerning the lateral communication of motion in Fluids. Prop. 8.

gular holes. Through these apertures the water descends in many small streams, and by exposing a greater surface to the atmosphere, it carries along with it an immense quantity of air, and is conveyed to the pedestal *P* by a tube *C H*, open and enlarged at *C*, so as to be considerably wider than the end of the pipe which holds the cullendar.

It has been generally supposed that the water-fall should be very high;[2] but Dr. Lewis has shewn, by a variety of experiments, that a fall of 4 or 5 feet is sufficient, and that when the height is greater than this, two or more blowing machines may be erected, by conducting the water from which the air is extricated into another reservoir, from which it again descends and generates air as formerly. That the air, which is necessarily loaded with moisture, may arrive at the furnace in as dry a state as possible, the condensing vessel *D E* should be made as high as circumstances will permit; and in order to determine the strength of the blast, it should be furnished with a gage *a b* filled with water.

Franciscus Tertius de Lanis observes,[3] that he has seen a greater wind generated by a blowing machine of this kind, than could be produced by bellows 10 or 12 feet long.

Cause of the rain wind.

The *rain wind* is produced in the same way as the blast of air in water-blowing machines. When the drops of rain impinge upon the surface of the sea, the air which they drag along with them often produces a heavy squall, which is sufficiently strong to carry away the mast of a ship. The

[2] Wolfius makes the length of the tube *C H* 5 or 6 feet Opera Mathematica, tom. i, p. 830.

[3] In Magisterio Naturæ et Artis, lib. v, cap. 3.

same phenomena happens at land, when the clouds empty themselves in alternate showers. In this case, the wind proceeds from that quarter of the horizon where the shower is falling. The common method of accounting for the origin of winds by local rarefactions of the air, appears to me pregnant with insuperable difficulties; and I am apt to think, that these agitations in our atmosphere, ought rather to be referred to the principle which we have now been considering.[4]

---

[4] Those who wish for more information upon the subject of water-blowing machines, may consult Lewis's Commerce of Arts; the Journal des Mines, N° 91; or Nicholson's Journal, vol. xii, p. 48.

HYDRAULICS.

DESCRIPTION OF WHITEHURST'S MACHINE FOR RAISING WATER BY ITS MOMENTUM; AND MONTGOLFIER'S HYDRAULIC RAM.

THE ingenious idea of raising water by the momentum of the water itself was first suggested by Mr. Whitehurst in the Philosophical Transactions for 1775. The same principle, in an improved form, has lately been revived in France, and has excited considerable attention both on the continent and in this country. Whatever credit, therefore, is due to the inventor of the hydraulic ram, properly belongs to our countryman Mr. Whitehurst, and Montgolfier can lay claim to nothing more than the merit of an improver.

The idea of raising by its momentum suggested by Mr. Whitehurst.

Mr. Whitehurst's machine, which is represented in figure 2d of Plate XIV, was actually erected at Oulton in Cheshire, and completely answered the expectation of its inventor. AM is the original reservoir, whose surface is on a level with B, the bottom of the reservoir BN. The main pipe AE, is $1\frac{1}{2}$ inches diameter, and nearly two hundred yards long, and the branch pipe EF is of such a size, that the cock F is about

Description of Mr. Whitehurst's machine. PLATE XIV, Fig. 2. App.

16 feet below the surface M of the reservoir. D is a valve box, with its valve a, and C is an air vessel, into which are inserted the extremities m, n, of the main pipe, bent downwards to prevent the air from being driven out when the water is forced into it. Now, since the difference of level between the cock F, and the top of the reservoir AM is 16 feet, upon opening the cock F the water will rush out with a velocity of nearly 30 feet per second. A column of water, therefore, two hundred yards long, is thus put in motion, and, though the aperture of the cock F be small, it must have a very considerable momentum. Let the cock F be now suddenly stopped, the water must evidently rush through the valve a into the air vessel C, and condense the included air. This condensation must take place every time the cock is opened and shut, and the included air being highly compressed, will press upon the water in the air vessel, and raise it into the reservoir BN.

Description of Montgolfier's hydraulic ram. PLATE XIV, Fig. 3. App.

From this brief description of Whitehurst's engine, the reader will easily perceive its resemblance to that of Montgolfier, a section of which is represented by figure 3[d]. R is the reservoir, RS the height of the fall, and ST the horizontal tube which conducts the water to the engine $ABHTC$. E and D are two valves, and FG a pipe reaching within a very little of the bottom CB. Now let water descend from the reservoir, it will rush out at the aperture $m\,n$ till its velocity becomes so great as to force up the valve E. The water being thus suddenly checked, and unable to find a passage at $m\,n$, will rush forwards towards H, and raise the valve D. A portion of water being admitted into the vessel ABC, the impulse of the column of

fluid is spent, the valves *D* and *E* fall, and the water rushes out at *m n* as before, when its motion is again stopped, and the same operation repeated which has now been described. Every time therefore that the valve *E* closes, a portion of water will force its way into the vessel *A B C*, and condense the air which it contains; for the included air has no communication with the atmosphere after the water is higher than the bottom of the pipe *F G*. This condensed air will consequently exert great force upon the surface *o p* of the water, and raise it in the tube *F G* to a height proportioned to the elasticity of the imprisoned air. The external appearance of the engine, copied from one in the possession of Professor Leslie, is exhibited in Figure 4, where Fig. 4. *A B C* is the air vessel, *F* the valve box, *G* the extremity of the valve, and *M*, *N*, screws for fixing the horizontal tube to the machine. A piece of brass *A*, with a small aperture, is screwed on the top when the engine is employed to form a jet of water. From this description, the reader will perceive, that the only difference between the engines of Montgolfier and Whitehurst is, that the one requires a person to turn the cock, while the other has the advantage of acting spontaneously. Montgolfier indeed observes, that the honour of this invention was not due to England, but that he was the sole inventor, and did not receive a hint from any person whatever.[1] We leave it to the reader to determine what degree of credit these assertions are entitled to.

[1] 'Cette invention n'est point originaire d'Angleterre, elle appartient toute entiere a la France; je declare que j'en suis le seul inventeur, et que l'idèe ne m'en a eté fournie par personne.' *Journal des Mines*, vol. xiii, No. 73.

It would appear from some experiments of Montgolfier, that the effect of the water-ram is equal to between $\frac{1}{2}$ and $\frac{3}{4}$ of the power expended, which renders it superior to most hydraulic machines.[2]

---

[2] Those who wish for more information on this subject, may consult the Journal des Mines, vol. xiii, No. 73, where Montgolfier has given a very unphilosophical account of the ram.—Sonini's Journal, Feb. 1806, p. 334, and Nicholson's Journal, No. 56, vol. xiv, p. 98.

OPTICS.

ON ACHROMATIC TELESCOPES.

On Achromatic Object Glasses.

Achromatic object glasses.

NOTWITHSTANDING the claims of foreigners to the invention of the achromatic telescope, we have the most unquestionable evidence that this instrument was first invented and constructed about the year 1758, by our countryman Mr. John Dollond. As telescopes of this description are not affected with the prismatic colours, the late Dr. Bevis proposed to distinguish them by the name of *Achromatic*, an appellation which they have hitherto retained, though some have erroneously stated that it was first given them by the astronomer Lalande.

During the 17th century, when every branch of science was cultivated with unwearied assiduity, the attention of philosophers was particularly directed to the improvement of the *refracting* telescope. But as the different refrangibility of the rays of light was then unknown, men of science employed themselves chiefly in trying to remove the spherical aberration, or the error which arises from the spherical figure of the ob-

Imperfections of telescopes.

ject glass. For this purpose they ground their object lenses of a parabolic or hyperbolic figure, or of a spherical form, with the radius of the surface next the object six times greater than that of the surface next the eye, in which case Huygens had shewn that the aberration is less than when the radii of curvature have any other proportion. After all these trials, however, the refracting telescope still retained its former imperfections, and the opticians of those days, completely despairing of bringing it to perfection, turned the whole of their attention to the construction of the *reflecting* telescope.

Discovery of Dollond.

It was reserved for Sir Isaac Newton to discover the cause of these imperfections, and for Dollond to point out their cure. From Newton's Theory of Colours, it plainly appeared that the imperfections of the dioptric telescope arose from the different refrangibility of the rays of light, and that, compared with this, the spherical aberration was extremely trifling. But though Newton, by thus pointing out the cause of the indistinctness of refracting telescopes, contributed indirectly to their improvement, he may certainly be said to have checked the progress of this branch of science, when he stated,[1] 'that 'all refracting substances diverged the prismatic 'colours in a constant proportion to their mean 'refractions,—that refraction could not be pro-'duced without colour, and, consequently, that 'no improvement could be expected in the re-'fracting telescope.' In this conclusion philosophers had acquiesced for above half a century, till Mr. Dollond having examined the premises

[1] Newton's Optics, p. 112.

from which it was drawn, obtained a result very different from that of Sir Isaac Newton. He found that substances which had the same refractive power had different dispersive powers, or, in his own words,[a] 'that there is a difference in 'the dispersion of the colours of light, when 'the mean rays are equally refracted by different 'mediums;' and thence concluded that the object glasses of refracting telescopes were capable of being made, without being affected by the different refrangibility of the rays of light.

That our readers may understand this illustrious discovery, and the method of its application to the construction of achromatic object glasses, let *A B C* be a prism, *O* a beam of white light proceeding in the direction *O N*, but refracted from its rectilineal course by the interposition of the prism, and forming the prismatic spectrum *R M V*. The line *n M* being the direction of the mean refracted light, the angle *N n M* is called the *angle of deviation*, and *R n V* the *angle of dissipation*, or *dispersion*. In the same medium, the angle of dispersion is always proportional to the angle of deviation, or to the mean angle of refraction, and Newton imagined that this was universally the case in different media, *i. e.* that the angle *N n M* is always proportional to the angle *R n V*, whether the prism be of crown, or flint, or any other kind of glass. Dollond, however, found that these angles were not proportional to each other in different media, but that in some the angle of deviation is larger when the angle of dispersion is smaller, and that in others the angle of deviation is smaller when

PLATE IX, Fig. 5. App.

[a] See the Philosophical Transactions, vol. 50, p. 748.

the angle of dispersion is larger. Thus, if the prism *A B C* be made of crown glass, the angle of deviation will be *N n M*, and that of dispersion *R n V*, but if a flint-glass prism with a less refracting angle be substituted in its room, the angle of deviation may be *N n M*, while that of dispersion becomes *r n v*.

Application to achromatic telescopes.

The application of these principles to the improvement of the refracting telescope will be easily comprehended, if we consider that light is refracted and dispersed by lenses in the same manner as by prisms. Thus, in Fig. 6, let *A B* be a convex lens, *O* a beam of light incident at *m*, emerging at *m*, and proceeding in the direction *m N*; then if we suppose *a b c* to be a prism, whose sides *a b*, *a c*, are tangents to the surfaces of the lens in the points *n*, *m*, the beam of light *O*, incident at *n*, will emerge at *m*, and proceed in the same direction *m N* as formerly; and if the lens be concave, as *C D*, it will refract and disperse the rays in the same way as a prism *a c d*, placed in a contrary direction with its base *a d* uppermost. Now, if we apply to the prism *a b c* another prism *a c d*, having a similar refracting angle, and the same refractive and dispersive power, or if to the convex lens *A B* we apply the concave one *C D*, having the same curvature and the same refractive and dispersive power, then the ray of white light *O*, incident at *n*, will emerge colourless at *p*, and proceed in the direction *p N*, parallel to *O n*, because the change which is produced on the incident ray by the first prism or convex lens, is counteracted by an equal and opposite change produced by the second prism or concave lens. But if the second prism or lens has a different refractive and dispersive power from the first, and if the refract-

PLATE IX, Fig. 6.

ing angle of both is the same, the ray $p\,N$ will be coloured after refraction, because the second prism more than counteracts the effects of the first, and it will be bent to or from the axis of the lenses according as the refracting power of the second prism or lens is greater or less than that of the first.

From these observations, the attentive reader will easily understand the construction of the double achromatic object glass, in which $A\,B$ is the convex lens of *crown glass*, and $C\,D$ the concave one of *flint glass*. As the refractive and dispersive powers of the lens $C\,D$ is greater than those of the lens $A\,B$, the curvatures of the lenses, or the refracting angles of the corresponding prisms, being equal, the ray $p\,N$ will be bent from the axis of the lenses, and it will be coloured by the excess of the dispersive power of the flint above that of the crown glass. In this case, therefore, the combined lenses will not have a positive focus. But, since, in the same medium, the angle of dispersion increases or diminishes with the angle of deviation, we can diminish the refraction and dispersion of the concave lens by diminishing its concavity, or the refracting angle of the corresponding prism. Now, let the concavity of the lens $C\,D$ be diminished till its dispersion be equal to the dispersion of the lens $A\,B$, its refraction or power of bending the incident rays will also be diminished; then since the dispersion of the concave lens is equal to the dispersion of the convex one, and its curvature less, the ray $p\,N$ will emerge perfectly colourless, and it will be bent *towards* the axis of the lenses, as the convergency of the incident ray occasioned by the convex lens is not wholly counteracted by the divergency produced by the

Double achromatic object glass. Fig. 6.

concave one. In the same manner every other ray falling upon the surface of AB will be refracted colourless into a positive focus, and an image will be formed perfectly achromatic.

Triple achromatic object glass.

From what has been said concerning the double achromatic object glass, it will be easy to comprehend how a colourless image is formed by a combination of three lenses, which is now universally adopted for the purpose of diminishing the spherical aberration. In Fig. 7, let AB, CD, EF, be the three lenses which compose the triple object glass,[1] AB, and EF, being convex, and of crown glass, and CD concave, and made of flint glass; and let ab, cd, ef, be corresponding prisms, which, if substituted instead of the lenses, would refract and disperse, in a similar manner, any ray of light which falls upon the points q, m, r, t, g, p, where the sides of the prisms are supposed to touch the surfaces of the lenses. Suppose, also, which is generally the case, that the two convex lenses have equal focal lengths, and that the focal distance of either lens is greater, or their curvature less, than that of the concave one, whose dispersion exceeds that of the lens AB; then a ray, O, of white light incident at q, will, after refraction by the lens AB, be separated into its component parts, and proceed in the direction mrR, nsV; mrR being the extreme red ray, and nsV the extreme violet. But as these rays are intercepted by the lens CD, at the points r, s, they will undergo another refraction in a contrary direction, and will proceed according to

Plate IX, Fig. 7.

[1] The lenses are placed at a distance from each other in the figure, that the progress of the incident ray may be more easily perceived.

the dotted lines *t r*, *o v*. These rays will diverge after refraction, and be bent *from* the axis of the lenses, since the refraction, as well as the refracting angle of the prism *c d*, or lens *c D*, exceeds the refraction, and refracting angle of the prism *a b*, or lens *A B*; for though the violet ray *q n s* is bent from the red ray *q m r*, by the refraction of the lens *A B*, it is again bent towards it by the superior refraction of the concave lens, and they will therefore converge to one another in the direction *t r*, *o v*. In this case, the excess of dispersive power in the concave lens tends only to delay the mutual convergency of the red and violet rays, or to remove the point where they would meet farther from the lens *e D*. Now it is evident that two rays of different refrangibility falling upon a prism or lens with different angles of incidence, may emerge with the same angle of refraction, or may be united at their emersion from the prism or lens; for in this case their difference of refrangibility counteracts the difference between their angles of incidence. The red and violet rays *o r*, *t v*, therefore, which fall upon the lens *E F*, with different angles of incidence, will, after refraction by the third lens, proceed perfectly colourless in the direction *p N*. In the same manner, all the rays which proceed from any object, emerging colourless from the triple object-glass, will unite in one point, and form an image completely achromatic.

Having thus discovered that light could be refracted without colour, the next object of philosophers was to ascertain the curvature which must be given to lenses, in order to produce this effect, and likewise to correct the spherical aberration. This subject has been treated with the greatest ability by several foreign mathematicians,

but particularly by Euler,[1] D'Alembert,[2] Clairaut,[3] Boscovich,[4] and Klugel.[5] The writings of these philosophers furnish us with the most complete and accurate information upon this point; and art has in this case received from science all the assistance which she can possibly bestow. It shall be our object at present to reduce the results of their investigations either into tables or into such a form as may be easily comprehended by the practical optician, and thus to furnish the artist with a popular view of this interesting subject. For this purpose, the celebrated Euler has given, in his Dioptrics,[6] two formulæ, from which we have calculated the two following tables, containing the radii of curvature for the lenses of a triple object-glass.—The first column contains the focal distance of the lenses when combined; and the six following columns contain the radii of their curvature in inches and decimals, beginning with the surface next the object.

---

[1] Comment. Nov. Acad. Petropol. Tom. 18, p. 407.

[2] Mem. de l'Acad. Paris, 1764, 8vo, p. 139; 1765, 8vo, p. 81, and 1767, 4to, p. 43.

[3] Mem. de l'Acad. Paris 1756, 8vo, p. 612; 1757, 8vo, p. 853, and 1762.

[4] R. J. Boscovichii Opera pertinentia ad Opticam et Astronomiam, Bassani. 1785, Tom. 1. Opusc. 2, p. 169.

[5] Comment. Reg. Soc. Gotting. 1795 to 1798, Tom. 13, p. 28.

[6] The mean refraction of the crown glass is supposed to be 1.53, and that of the flint glass 1.58, and their dispersive powers as 2 to 3.

TABLE I.

Table of the Radii of Curvature of the Lenses of a Triple Achromatic Object Glass, according to Euler's first Formula.

Tables for triple object glasses.

Focal length.	Convex lens of Crown Glass.		Concave lens of Flint Glass.		Convex lens of Crown Glass.		SemiAperture.
Inch.	Inches.	Inches.	Inches.	Inches.	Inches.	Inches.	Inches.
6	3.00	22.00	3.10	2.91	3.13	2.85	0.71
9	4.50	33.00	4.65	4.36	4.70	4.28	1.07
12	6.00	44.00	6.20	5.82	6.26	5.70	1.43
18	9.00	66.00	9.30	8.72	9.40	8.56	2.14
24	12.00	88.00	12.40	11.64	12.52	11.40	2.86
30	15.01	109.99	15.50	14.53	15.65	14.27	3.56
36	18.01	131.99	18.60	17.44	18.80	17.12	4.28
42	21.01	153.99	21.70	20.37	21.91	19.97	4.99
48	24.02	175.99	24.80	23.28	25.04	22.80	5.72
54	27.02	197.99	27.90	26.16	28.18	25.69	6.42
60	30.02	219.99	31.00	29.06	31.31	28.54	7.13

TABLE II.

Table of the Radii of Curvature of the Lenses of a Triple Achromatic Object Glass, according to Euler's second Formula.

Focal length.	Convex lens of Crown Glass.		Concave lens of Flint Glass.		Convex lens of Crown Glass.		SemiAperture.
Inch.	Inches.	Inches.	Inches.	Inches.	Inches.	Inches.	Inches.
6	1.70	12.44	12.88	1.77	3.56	15.00	0.42
9	2.55	18.66	19.31	2.66	5.34	22.51	0.64
12	3.40	24.87	25.75	3.55	7.13	30.01	0.85
18	5.09	37.31	38.63	5.32	10.69	45.01	1.27
24	6.80	49.74	51.50	7.10	14.25	60.02	1.70
30	8.49	62.19	64.38	8.86	17.81	75.02	2.12
36	10.19	74.63	77.26	10.63	21.37	90.02	2.54
42	11.89	87.07	90.14	12.40	24.93	105.03	2.96
48	13.60	99.48	103.02	14.17	28.49	120.03	3.39
54	15.27	111.93	116.87	15.96	32.07	135.04	3.82
60	16.97	124.37	128.75	17.73	35.63	150.04	4.24

The only person in our country who has written upon the theory of achromatic object glasses, is the late learned Dr. Robison of Edinburgh, who, following the steps of Clairaut and Boscovich, has given an interesting dissertation upon this subject.[7] From the formulæ contained in that dissertation, the following table is computed.

TABLE III.[8]

Table of the Radii of Curvature of the Lenses of a Triple Object Glass.

Focal length.	Convex lens of Crown glass.		Convex lens of Flint glass.		Convex lens of Crown glass.	
Inches.	Inches.	Inches.	Inches.	Inches.	Inches.	Inches.
6	4.54	3.03	3.03	6.36	6.36	0.64
9	6.83	4.56	4.56	9.54	9.54	0.92
12	9.25	6.17	6.17	12.75	12.75	1.28
18	13.67	9.12	9.12	19.08	19.08	1.92
24	18.33	12.25	12.25	25.50	25.50	2.56
30	22.71	15.16	15.16	31.79	31.79	3.20
36	27.33	18.25	18.25	38.17	38.17	3.84
42	31.87	21.28	21.28	44.53	44.53	4.48
48	36.42	24.33	24.33	50.92	50.92	5.12
54	40.96	27.36	27.36	57.28	57.28	5.76
60	45.42	30.33	30.33	63.58	63.58	6. 4

The reader will observe, that only three pair of grinding tools are necessary for constructing a telescope according to the preceding table; but the work may be performed by only two grinding tools, if we employ the radii of curvature,

[7] Article *Telescope*, Encyclopædia Britannica, vol. xviii, p. 338.

[8] A telescope 30 inches in focal length, constructed according to this table, bore an aperture of $3\frac{1}{7}$ inches.

which are contained in the following table, computed from the formulæ of Boscovich.

TABLE IV.

Focal length.	Radii of the four surfaces of the two lenses of Crown glass.	Radius of the two surfaces of the concave lens of Flint glass.
Inches.	Inches.	Inches.
6	3.84	3.17
9	5.76	4.75
12	7.68	6.34
18	11.52	9.50
24	15.36	12.68
30	19.20	15.84
36	23.04	19.00
42	26.88	23.17
48	30.72	25.36
54	34.66	28.51
60	38.40	31.68

TABLE V.

The Radii of Curvature employed by the London Opticians are pretty nearly represented in the following Table, which is calculated from Dr. Robison's Measurements.

Focal length.	Convex lens of Crown glass.		Radius of both the surfaces of the concave lens of Flint glass.	Convex lens of Crown glass.	
Inches.	Inches.	Inches.	Inches.	Inches.	Inches.
6	3.77	4.49	3.47	3.77	4.49
9	5.65	6.74	5.21	5.65	6.74
12	7.54	8.99	6.95	7.54	8.99
18	11.30	13.48	10.42	11.30	13.48
24	15.08	17.98	13.90	15.08	17.98
30	18.34	22.47	17.37	18.34	22.47
36	22.61	26.96	20.84	22.61	26.96
42	26.38	31.45	24.31	26.38	31.45
48	30.16	35.96	27.80	30.16	35.96
54	33.91	40.45	31.27	33.91	40.45
60	37.68	44.94	34.74	37.68	44.94

Radii of curvature in Dollond's telescopes.

Two of Dollond's best achromatic telescopes being examined, were found to have their lenses of the following curvatures, reckoning from the surface next the object. Crown glass lens, 28 inches and 40. Concave lens 20.9 inches, and 28. Crown glass lens 28.4, and 28.4. The focal length of the compound object-glass was 46 inches. In the other telescope, whose focal length was 46.3 inches, the curvature of the 1st lens was 28 and 35.5 inches; the 2d lens 21.1 and 25.75; and the 3d 28 and 28. Both these telescopes magnified from 100 to 200 times, according to the powers applied.

The duc de Chaulnes having in his possession one of Dollond's best telescopes, whose focal length was 3 feet 5 inches 4.25 lines, made a variety of accurate experiments in order to determine the curvature, thickness, and distance, of its lenses, and found them to be of the following dimensions.[5] Radius of the 1st surface, or the surface next the object, 25 inches 11.5 lines. Radius of the 2d surface 32 inches 8 lines. Radius of the 3d surface 17 inches 10 lines. Radius of the 4th surface 24$\frac{1}{4}$ inches. Radius of the 5th 24$\frac{1}{4}$ inches; and the radius of the 6th 26 inches and 10.6 lines. Thickness of the first lens at its axis 2.11 lines; thickness of the 2d 1.59 lines; thickness of the 3d 2.18; and the thickness of the whole lens 5.91 lines.[6]

A very excellent telescope, with a double achromatic object glass, was constructed by M. Antheaulme in 1763, from the formulæ of Clair-

---

[5] These experiments are detailed at great length in the Mem. de l'Acad. Paris, 1767, 4to, p. 423.

[6] For the dimensions of the eye piece of this telescope, see the article on *Achromatic Eye pieces*, p. 458.

aut. The lens of flint glass was placed next the object, and was a meniscus with its convex side outwards. The radius of its concavity was $17\frac{1}{4}$ inches, and the radius of its convex side was 7 feet $6\frac{1}{3}$ inches. The interior surface of the lens of crown glass had a radius of 18 inches, while its exterior surface, or that next the eye, was 7 feet 6 inches. These lenses were separated by a piece of card, and formed a compound object glass, with a focal length of 7 feet, and an aperture of 3 inches and 4 lines. Its eye-piece consisted of two lenses. That next the object was a double convex lens with 18 lines of focal length, and 9 lines of aperture. Its first surface, or that next the object glass, had a radius of $11\frac{1}{2}$ lines, and its second surface a radius of 7 inches 2 lines. The second eye-glass, which was a meniscus, had 5 lines of focus and 2 lines of aperture. The radius of its convex surface was $2\frac{1}{4}$ lines, and that of its concave surface, which was next the eye, was 8 lines. The distance between the two eye-glasses was 9 lines.

Tables for Double Achromatic Object Glasses.

Tables for double object glasses

The following table, calculated from the formulæ of Boscovich, contains the radii of curvature for the lenses of a *double achromatic object glass.*

TABLE VI.

Focal length.	Convex Lens of Crown Glass		Concave Lens of Flint Glass.	
Inches	Inches.	Inches.	Inches.	Inches
6	1.94	1.91	1.91	9.49
9	2.91	2.86	2.86	14.24
12	3.88	3.82	3.82	18.99
18	5.82	5.73	5.73	28.48
24	7.76	7.63	7.63	36.99
30	9.70	9.54	9.54	47.47
36	11.64	11.45	11.45	56.97
42	13.58	13.36	13.36	66.46
48	15.51	15.27	15.27	75.98
54	17.45	17.17	17.17	85.47
60	19.39	19.08	19.08	94.95
70	22.62	22.26	22.26	110.77
80	25.86	25.44	25.44	126.60
90	29.09	28.62	28.62	142.42
100	32.32	31.80	31.80	158.25

In the following table, calculated from Dr. Robison's measurements, the reader will find the radii of curvature which are employed by the London artists in the construction of the double achromatic object glass.

TABLE VII.[4]

Focal length.	Convex Lens of Crown Glass,		Concave Lens of Flint Glass.	
Inches.	Inches.	Inches.	Inches.	Inches.
6	1.76	2.12	2.07	6.88
9	2.64	3.17	3.10	10.33
12	3.53	4.23	4.13	13.77
18	5.29	6.35	6.20	20.65
24	7.05	8.46	8.26	27.54
30	8.81	10.58	10.33	34.42
36	10.58	12.69	12.39	41.30
42	12 34	14.81	14.46	48.18
48	14.11	16.92	16.52	55.07
54	15.87	19.04	18.59	61.96
60	17.63	21.16	20.66	68.84
70	20.57	24 68	24.10	80.32
80	23.50	28.21	27.54	91.79
90	26.44	31.73	30.99	103.27
100	29.38	35.26	34.43	114.74

Table for quadruple object glasses.

Although it has been the practice in this country to construct only double and triple achromatic object glasses, yet they may be composed even of four or five lenses, the convex ones of crown glass, and the concave ones of flint glass being placed in an alternate order. By augmenting the number of media, indeed, a quantity of light must be lost, and the labour of the artist greatly increased; but M. Jeaurat informs

[4] In this and the six preceding tables, the sine of incidence is supposed to be to the sine of refraction as 1.526 to 1 in the crown glass, and as 1.604 to 1 in the flint glass; and the ratio of the differences of the sines of the extreme rays in the crown and flint glass 0.0 54.

us, that he constructed a compound object glass 5 inches and 10 lines in focal length, which bore an aperture of $1\frac{1}{2}$ inches, while the best achromatic telescopes of 6 inches focus, constructed in England, had an aperture only of an inch and a quarter. To such, therefore, as wish to construct object glasses of this description, the following table, containing their radii of curvature, may probably be acceptable.

TABLE VIII.[5]

Focal length of the compound object glass.		Radius of the six interior surfaces.			Radius of the two exterior surfaces.			Aperture of the object glass.
Feet.	Inches	Feet.	Inch	Dec.	Feet.	Inch	Dec	Inch. Dec.
0	4	0	3.08		0	3.58		1.25
0	6	0	4.50		0	5.33		1.50
0	8	0	5.92		0	7.08		1.83
0	10	0	7.33		0	8.83		2.17
1	0	0	8.83		0	10.58		2.25
2	0	1	5.33		1	9.17		2.58
3	0	2	1.83		2	7.67		2.92
4	0	2	4.42		3	6.25		3.25
5	0	3	6.92		4	4.75		3.58
6	0	4	3.50		5	3.33		3.92
7	0	5	0.00		6	1.83		4.17
8	0	5	8.58		7	0.42		4.50
9	0	6	5.08		7	11.00		4.83
10	0	7	1.58		8	9.50		5.17

Difficulties in the construction of achromatic telescopes.

Though it is demonstrable that a telescope constructed according to the preceding tables,

[5] This table supposes that the mean refraction of the crown glass is to that of the flint glass as 1000 to 1045, and their dispersive powers as 200 to 353.

and formed of glass, whose refractive and dispersive power is similar to that which was employed in the formulæ upon which these tables are founded, will form an image perfectly distinct and colourless; yet it is so difficult to procure flint glass of the same refractive and dispersive power, that it is almost impossible for a private individual to succeed, even after several trials. The London opticians have always at hand a number of lenses of various curvatures, and different powers of refraction and dispersion, and by selecting such as answer best upon trial, they are enabled, without much trouble, to construct an object glass in which the spherical and chromatic aberrations are almost wholly corrected. Those, therefore, who are not furnished with a sufficient number of lenses, must necessarily meet with frequent disappointments in their attempts to construct achromatic telescopes; and the only way of preventing these disappointments, and rendering success more certain, is to have a variety of tables, which being founded on different conditions, give different curvatures to the lenses. If the artist should be unsuccessful, either from the nature of the refracting media which he employs, or from giving the lenses a greater or lesser curvature than the table requires, he may, with very little trouble, sometimes with altering the radius of a single surface, adapt the lenses to the conditions of some other table, and in all probability obtain a more favourable result. With the view of facilitating these attempts, we have computed the eight preceding tables, and for the same purpose we shall subjoin the following different forms of achromatic object glasses from Boscovich and Klugel.

In these forms a represents the first surface of the compound lens, or that which is next the object, b the second surface, a' the third, b' the fourth, a'' the fifth, and b'' the sixth; a, b, a'', b'' representing the radii of curvature for the convex lenses of crown glass, and a', b' the curvature of the concave lens of flint glass. The focal distance of the first lens, or that whose surfaces are marked a, b, is represented by x, that of the second by y, and that of the third by z, while the focal length of the compound lens is distinguished by the letter F.

FORMS FOR TRIPLE OBJECT GLASSES.

I.

Forms for triple object glasses.

$a=b=a''=b''=0.6412$	$x=0.6096$
$a'=0.5227$	$y=0.4384$
$b'=0.5367$	$z=0.6096$
$F=1$	

In this form the two lenses of crown glass are isosceles,[6] and have the same curvature and focal distance. The middle lens of flint glass is nearly isosceles, and may be made so in practice, so that only two grinding tools are necessary for this form.

II. *The two first Lenses Isosceles.*

$a=b=a'=b'=0.530$	$x=0.5038$
$a''=1.215$	$y=0.4388$
$b''=0.3046$	$z=0.7727$
$F=1$	

[6] A lens is called *isosceles* when both its surfaces have the same curvature.

III. *The first and third Lenses Isosceles.*

$a=b=a''=b''=0.616$
$a'=0.6356$ $F=1$
$b'=0.3790$[7]

IV. *The two first Lenses Isosceles.*

$a=b=a'=b'=0.4748$
$a''=0.3514$ $F=1$
$b''=0.4383$

V. *The second and third Lenses Isosceles.*

$a=0.5721$
$b=1.8744$
$a'=b'=a''=b''=0.4748$

VI. *All the three Lenses Isosceles.*

$a=b=0.7963$
$a'=b'=0.4748$
$a''=b''=0.5023$

VII. *Second Lens Isosceles, the first and third of equal focal Length, but placed in an inverse Order.*

$a=b''=0.7306$
$a'=b'=0.4748$
$a''=b=0.5325$

VIII. *Second Lens Isosceles, the first and third of equal focal Length, and placed in a direct Order.*

$a=a''=0.7048$
$b=b''=0.5471$
$a'=b'=0.4748.$[8]

---

[7] In these two forms the refractive and dispersive power of the glass is supposed the same as in the note on p. 437.

[8] In the preceding forms, which are calculated from the formulæ of Boscovich, the sine of incidence is to the sine of refraction as 1.527 to 1 in the crown glass, and as 1.575 to 1 in the flint glass, and the ratio of the differences of the sines of the extreme rays 0.6486.

FORMS FOR DOUBLE OBJECT GLASSES.

I. *First Lens Isosceles.*

Forms for double object glasses.

$a=b=0.3206$	$x=0.3408$
$a'=0.3201$	$y=0.4384$
$b'=1.533$	$F=1.$

II.

$a=$ 6943	Dist. between	
$b=$22712	the lenses	$=$ 100
$a'=$14750	Aperture	$=$ 3000
$b'=$18383	Thickness of the	
$x=$10000	convex lens	$=$ 250
$y=$14080	Thickness of the	
$F=$32024	concave lens	$=$ 100

III.[1]

$a=$ 2168	Dist. between	
$b=$ 7092	the lenses	$=$ 31
$a'=$ 4606	Aperture	$=$ 937
$b'=$ 5740	Thickness of the	
$x=$ 3123	convex lens	$=$ 79
$y=$ 4397	Thickness of the	
$F=$10000	concave lens	$=$ 31

Method of using these forms.

In making use of the preceding forms, we have only to fix on the focal length which we intend to give to the object glass, and multiply the different numbers by this focal length, expressed in feet or inches, and the result will be the proper radii of curvature in feet or inches. Thus, let it be required to construct a double achromatic object glass according to the first of these forms, whose focal length shall be 20 inches, we shall have

[1] This and the preceding form are calculated from Klugel, and suited to glass, with nearly the same refractive and dispersive powers as that mentioned in the preceding note.

$a=b=20\times0.3206=6$ inches and $\frac{4}{10}$ nearly;
$a'=20\times0.3201=6$ inches and $\frac{4}{10}$ nearly;
$b'=20\times1.553=30$ inches and $\frac{7}{10}$ nearly;
$x=20\times0.3408=6$ inches and $\frac{8}{10}$ nearly;
$y=20\times0.4384=8$ inches and $\frac{8}{10}$ nearly;
and $F=20\times1=20$ inches.

Method of improving achromatic object glasses.

Achromatic object glasses may be much improved by interposing pure turpentine varnish between the concave and convex lenses. By this means the reflection from the internal surfaces is removed, and that loss of light prevented which arises from an imperfect polish of the surfaces. M. Putois, an optical instrument maker in Paris, is said to have discovered that the best medium for this purpose is mastich,[a] a transparent resinous substance, which is exuded from the lentiscus tree in the island of Chio, and brought to this country in grains or tears.

Achromatic telescopes with fluid object glasses.

Achromatic telescopes have also been constructed, by substituting transparent fluids instead of the concave lens of flint glass. For this discovery we are indebted to the ingenious Dr. Robert Blair, who has given an account of his experiments in the 3d volume of the Transactions of the Royal Society of Edinburgh, to which we must refer the reader, after giving a description of one of these fluid object glasses.

If pure spirit of turpentine be interposed between two convex lenses of crown glass, having the radii of their surfaces as 6 to 1 with the most convex sides turned inwards, the image formed by this combination will be perfectly achromatic. The spirit of turpentine has the form of a double

[a] Traite Elementaire de Physique par Brisson, tom. ii, § 1657, p. 428.

concave lens, and as its refractive and dispersive powers differ from those of crown glass, it will act in every respect like a lens of flint glass. A few years ago I constructed an object glass of this kind, having 36 inches of focal length, but found it troublesome to keep it in order.

On Achromatic Eye Pieces.

Achromatic eye-pieces.

Although a brief account of the achromatic telescope has been given by those who have written upon optics, since the invention of that instrument, yet these authors have unaccountably overlooked the construction of achromatic eye pieces. Dr. Robison, indeed, has treated this subject at considerable length, after Boscovich, but has furnished almost no information to the practical optician. On this account, with the Italian philosopher as our guide, we shall dwell a little longer upon this point, than what might otherwise be thought necessary in a work like ours. In order to correct the error arising from the inequal refrangibility of light in the eye pieces of telescopes, we are not under the necessity of using compound lenses of crown and flint glass, as this species of aberration can be completely removed by a particular arrangement of the eye glasses which are employed for erecting the object.

Method of correcting the chromatic aberration by single lenses. PLATE XIV, Fig. 7.

This will appear from Fig. 7 of Plate XIV, where AB is an achromatic object glass, and DE an eye-piece of the kind mentioned in p. 451. Let CDE be the axis of the telescope, and ST a ray passing through the object glass AB. As the object glass is achromatic, this ray will fall upon the eye-glass D, without being decomposed into the prismatic colours, through

whatever part of the lens it is transmitted. The eye-glass D, however, will separate the ray ST into its component colours, and the red part of the ray will be bent into the direction TR, and the violet part into the direction TV. But when the second lens is interposed, it will intercept the red ray at the point m, and the violet ray at the point n of its anterior surface. Now as the red ray Tm enters the lens E at a point m, farther from the axis than the violet ray, and as the refracting angle of the lens is greater at m than at n, this increase of the refracting angle for the red ray will make up for its inferior refrangibility, and the rays Tm, Tn, will emerge parallel from the lens E in the direction mr, nv. The chromatic aberration, therefore, which is always proportional to the angle formed by the resulting rays mr, nv, will be destroyed.—In small pocket telescopes, as opera glasses, &c. where it would be very inconvenient to apply a long eye piece, compound lenses of crown and flint glass should be adopted, and may consist either of two or three glasses, with the following curvatures.

FORMS FOR A DOUBLE EYE GLASS.

Forms for compound eye-glasses of crown and flint glass.

I. *Both Lenses Isosceles.*[a]

$a=$ $=0.320$	$x=0.304$
$a'=b'=0.529$	$y=0.438$

II. *First Lens Isosceles.*

$a=a'=b=0.320$	$x=0.304$
$b'=1.517$	$y=0.438$

[a] The letters a, b, x, y, &c. represent the same quantities as in page 440.

FORMS FOR A TRIPLE EYE GLASS.

I. *All the three Lenses Isosceles.*

$a=b=a''=b''=0.640$ $\quad z=x=0.608$
$a'=b'=0.529$ $\quad y=0.438$

II. *First Lens Isosceles.*

$a=b''=0.810$ $\quad z=x=0.608$
$b=a'=b'=a''=0.529$ $\quad y=0.438$

If it is required to erect the object as in the Galilean telescope, the middle lens of flint glass must be made convex, and the other lenses concave, but with the same radii of curvature, so that the concavity of the compound lens may predominate.

On Eye Pieces with three Lenses, which remove the Chromatic Aberration.

Eye-pieces with three lenses.

The three lenses must be made of the same kind of glass, and may be of any focal length. The distance between the first and second, or the two next the object, must be equal to the sum of their focal distances, and the distance between the second and third must exceed the sum of their focal distances, by a quantity which is a third proportional to the distance between the first and second, and the focal length of the second lens; or, in other words, the distance between the second and third lenses must be equal to the sum of their focal distances, added to the quotient arising from the square of the focal distance of the second lens, divided by the sum of the focal distances of the first and second. These, and other circumstances, which should be attended to in the construction of achromatic eye pieces,

will be better understood by expressing them algebraically.

Thus, let F be the focal length of the object glass, and x, y, z, the focal distances of these eye glasses, reckoning from that which is nearest the object. Then we shall have

Formulæ for achromatic eye-pieces.

1, The distance between the first and second lenses - - $x+y$

2, The distance between the second and third - - $y+z+\frac{y^2}{x+y}$

3, Distance of the first lens from the focus of the object glass - $\frac{xy}{x+y}$

4, Magnifying power of the eye-piece $\frac{Fy}{xz}$

5, Focal distance of a single lens with the same magnifying power - $\frac{xz}{y}$

6, Distance of the eye from the third lens - - - z

7, Length of the whole eye-piece $x+3y+2z$

8, Length of the whole telescope $F+x+3y+2z$

9, Aperture of the lenses[1] $a, a', a''...a^{n}=a'', a=\frac{na}{y}$

10, The aperture of the diaphragm, or field bar, or m, should be a little less than - - - a
And should be placed in the focus of the object glass.

11, The field of view is nearly - $\frac{3438m}{F}$

---

[1] The apertures of the lenses may be made equal to one another, but should never be greater than half the focal distance of the third lens.

Although the aberration of colour will be completely removed by making the lenses of any focal length, and placing them at the distances indicated by the preceding formulæ, yet it is preferable to make the first and second lenses of the same focal length, and to give the third a less focal distance, and make its distance from the second equal to its own focal length, added to $1\frac{1}{2}$ the focal distance of one of the other lenses; for, in this case, where x and y are equal, the expression $\frac{y^2}{x+y}$, which, when added to $y+z$, expresses the distance between the second and third lenses, becomes $\frac{1}{2}y$.[2] Beside the simplicity of this combination, it has another advantage, for the magnifying power of the eye-piece is always equal to the magnifying power of the third lens. This is evident from the fifth formula $\frac{xz}{y}$, which becomes $=z$ when x and y have the same value. So that in this construction, when we wish to give a certain magnifying power to a telescope, we have only to take such a focal length for the third lens as will produce this magnifying power, and make the focal length of the other two a little greater than that of the third. By increasing the focal lengths of the two first lenses, the image is not injured by any particles of dust which may be lying on their surface, and the spherical aberration is also diminished. By augmenting the curvature of the third lens, however, we contract the field of view, which ought, if possible,

---

[2] Since $x=y$ in this case, $\frac{y^2}{x+y}$ is $=\frac{y^2}{2y}=\frac{y}{2}$ or $\frac{1}{2}y$ for $\frac{1}{y} \times 2y=y^2$.

to be avoided. This may be avoided, indeed, as Boscovich has shewn, by making the third lens consist of two convex ones of the same glass, their surfaces being in contact, and their focal lengths equal. From long experience, he found that eye pieces of this construction are superior to all others, and that the error arising from the spherical figure of the glass is greatly diminished, by making all the lenses plano-convex, and turning the plain sides to the eye, excepting the second lens, whose plane surface should be turned to the object. All the lenses may be made of the same focal length, and then the distance between the first and second, and the second and third, will be equal to the sum of their focal distances. In this case the third and fourth lenses, which are joined together, are considered as a single lens, whose focal length is equal to one half the focal length of either of the two. The apertures, too, may be all equal, and the field bar must be a little less than any of the apertures.

In all kinds of achromatic eye-pieces which are composed of single lenses, flint-glass should be employed, because it has the greatest refractive power, and therefore requires a less curvature to have the same focal distance. The spherical aberration, consequently, which always increases with the curvature of the lenses, will be less in a flint-glass eye-piece, than in one of crown-glass. Flint-glass, indeed, produces a greater separation of colours, but the error arising from this cause is completely removed by the proper arrangement of the lenses.

On Eye-Pieces with Four Lenses, which remove the Chromatic Aberration.

Eye-pieces with four lenses.

A good achromatic eye-piece may be made of four lenses, if their focal lengths, reckoning from that next the object, be as the numbers 14, 21, 27, 32, their distances 23, 44, 40, their apertures 5.6; 3.4; 13.5; 2.6; and the aperture of the diaphragm placed in the anterior focus of the 4th eye-glass, 7.

In one of Ramsden's small telescopes, whose object glass was $8\frac{1}{2}$ inches in focal length, and its magnifying power 15.4, the focal lengths of the eye-glasses were 0.77 of an inch; 1.025; 1.01; 0.79, and their respective distances, reckoning from that next the object, were 1.18; 1.83; 1.10.

In the excellent telescope of Dollond's construction, which belonged to the duc de Chaulnes,[3] the focal length of the eye-glasses, beginning with that next the object, were $14\frac{1}{4}$ lines, 19, $22\frac{1}{4}$, 14, their distances 22.48 lines; 46.17; 21.45; and their thickness at the centre 1.23 lines; 1.25; 1.47. The fourth lens was plano-convex, with the plane side to the eye, and the rest were double convex lenses.

On Achromatic Eye-Pieces for Astronomical Telescopes.

Achromatic eye-pieces for astronomical telescopes.

In eye-pieces of this kind which invert the object, the focal length of the first lens should

[3] See page 434.

be triple that of the second, and their distance double the focal length of the second, or $\frac{2}{3}$ of the focal length of the first. The lenses should be plano-convex, the plane surfaces turned to the eye, in order that the aberration of sphericity may be diminished as much as possible.[4]

The telescope of Dollond's, belonging to the duc de Chaulnes, had two astronomical eye-pieces, one of which was furnished with a micrometer. In the eye-piece which carried the micrometer, the first lens was $12\frac{1}{4}$ lines in focal length, and 1.62 lines thick; the second was 5.45 lines in focal length, and 1.25 thick, the distance between their interior surfaces 4.20 lines, and the distance of the first lens from the focus of the object glass $13\frac{1}{4}$ lines. In the other eye-piece the focal length of the first lens was 8.30 lines, and its thickness 1.60; and the focal length of the second was 3.53, and its thickness 0.97 lines. In both these eye-pieces the lenses were plano-convex, with the plane surfaces turned to the eye.

---

[4] See page 444.

OPTICS.

ON THE CONSTRUCTION OF OPTICAL INSTRUMENTS, WITH TABLES OF THEIR APERTURES AND MAGNIFYING POWERS, AND THE METHOD OF GRINDING THE LENSES AND SPECULA OF WHICH THEY ARE COMPOSED.

On the Method of grinding and polishing Lenses.

On grinding lenses.

HAVING fixed upon the proper aperture and focal distance of the lens, take a piece of sheet copper, and strike a fine arch upon its surface, with a radius equal to the focal distance of the lens, if it is to be equally convex on both sides; or with a radius equal to half that distance, if it is to be plano-convex, and let the length of this arch be a little greater than the given aperture. Remove with a file that part of the copper which is without the circular arch, and a *convex gage* will be formed. Strike another arch with the same radius, and having removed that part of the copper which is within it, a *concave gage* will be obtained. Prepare two circular plates of brass, about $\frac{1}{10}$ of an inch thick, and half an inch greater in diameter than the breadth of the lens, and solder them upon a cylinder of lead of the same diameter, and about an inch high. These tools

Formation of the gages.

Formation of the tools.

are then to be fixed upon a turning lathe, and one of them turned into a portion of a concave sphere, so as to suit the convex gage; and the other into a portion of a convex sphere, so as to answer the concave gage. After the surfaces of the brass plates are turned as accurately as possible, they must be ground upon one another alternately, with flour emery; and when the two surfaces exactly coincide, the grinding tools will be ready for use.

Formation of the glass.

Procure a piece of glass whose dispersive power is as small as possible, if the lens is not for achromatic instruments, and whose surfaces are parallel; and by means of a pair of large scissars or pincers, cut it into a circular shape, so that its diameter may be a little greater than the required aperture of the lens. When the roughness is removed from its edges by a common grind-stone,[1] it is to be fixed with black pitch to a wooden handle of a smaller diameter than the glass, and about an inch high, so that the centre of the handle may exactly coincide with the centre of the glass.

Mode of grinding.

The glass being thus prepared, it is then to be ground with the fine emery upon the concave tool, if it is to be convex, and upon the convex tool, if it is to be concave. To avoid circumlocution, we shall suppose that the lens is to be convex. The concave tool, therefore, which is to be used, must be firmly fixed to a

[1] When the focal distance of the lens is to be short, the surface of the piece of glass should be ground upon a common grindstone, so as to suit the gage as nearly as possible; and the plates of brass, before they are soldered on the lead, should be hammered as truly as they can be done into their proper form. By this means much labour will be saved both in turning and grinding.

table or bench, and the glass wrought upon it with circular strokes, so that its centre may never go beyond the edges of the tool. For every 6 circular strokes, the glass should receive 2 or 3 cross ones along the diameter of the tool, and in different directions. When the glass has received its proper shape, and touches the tool in every point of its surface, which may be easily known by inspection, the emery is to be washed away, and finer kinds[a] successively substituted in its room, till by the same alternation of circular and transverse strokes, all the scratches and asperities are removed from its surface. After the finest emery has been used, the roughness which remains may be taken away, and a slight polish superinduced by grinding the glass with pounded pumice-stone, in the same manner as before. While the operation of grinding is going on, the convex tool should, at the end of every five minutes, be wrought upon the concave one for a few seconds, in order to preserve the same curvature to the tools and the glass. When one side is finished off with the pumice-stone, the lens must be separated from its handle by inserting the point of a knife between it and the pitch, and giving it a gentle stroke. The pitch which remains upon the glass may be re-

[a] Emery of different degrees of fineness may be made in the following manner.—Take five or six clean vessels, and having filled one of them with water, put into it a considerable quantity of flour emery. Stir it well with a piece of wood, and after standing for 5 seconds, pour the water into the second vessel. After it has stood about 12 seconds, pour it out of this into a third vessel, and so on with the rest; and at the bottom of each vessel will be found emery of different degrees of fineness, the coarsest being in the first vessel, and the finest in the last.

moved by rubbing it with a little oil, or spirits of wine; and after the ground side of the glass is fixed upon the handle, the other surface is to be wrought and finished in the ground and manner.

When the glass is thus brought into its proper form, the next and the most difficult part of the operation is to give it a fine polish. The best, though not the simplest, way, of doing this, is to cover the concave tool with a layer of pitch, hardened by the addition of a little rosin, to the thickness of $\frac{1}{15}$ of an inch. Then having taken a piece of thin writing paper, press it upon the surface of the pitch with the convex tool, and pull the paper quickly from the pitch before it has adhered to it; and if the surface of the pitch is marked everywhere with the lines of the paper, it will be truly spherical, having coincided exactly with the surface of the convex tool. If any paper remains on the surface of the pitch, it may be removed by soap and water; and if the marks of the paper should not appear on every part of it, the operation must be repeated till the polisher, or bed of pitch, is accurately spherical. The glass is then to be wrought on the polisher by circular and cross strokes, with the oxide of tin, called the flowers of putty in the shops, or with the red oxide of iron, otherwise called colcothar of vitriol, till it has received on both sides a complete polish.[3] The polishing will advance

Mode of polishing

By means of pitch.

[3] As colcothar of vitriol is obtained by the decomposition of martial vitriol, it sometimes retains a portion of this salt. When this portion of martial vitriol is decomposed by dissolution in water, the yellow ochre which results penetrates the glass, forms an incrustation upon its surface, and gives it a dull and yellowish tinge, which is communicated to the image which it forms.

slowly at first, but will proceed rapidly when the polisher becomes warm with friction. When it is nearly finished, no more putty or water should be put upon the polisher, which should be kept warm by breathing upon it; and if the glass moves with difficulty, from its adhesion to the tool, it should be quickly removed, lest it spoil the surface of the pitch. When any particles of dust or pitch insinuate themselves between the glass and the polisher, which may be easily known from the very unpleasant manner of working, they should be carefully removed, by washing both the polisher and the glass, otherwise the lens will be scratched, and the bed of pitch materially injured.

By means of cloth.

The operation of polishing may also be performed by covering the layer of pitch with a piece of cloth, and giving it a spherical form by pressing it with the convex tool when the pitch is warm. The glass is wrought as formerly, upon the surface of the cloth, with putty or colcothar of vitriol, till a sufficient polish is induced. By this mode the operation is slower, and the polish less perfect; though it is best fitted for those who have but little experience, and would therefore be apt to injure the figure of the lens by polishing it on a bed of pitch.

In this manner the small lenses of simple and compound microscopes, the eye glasses, and the object glasses, of telescopes, are to be ground. In grinding concave lenses, Mr. Imison[4] employs leaden wheels with the same radius as the curvature of the lens, and with their circumferences of the same convexity as the lens is to be concave. These spherical zones are fixed upon

[4] School of Arts, part ii, p. 145.

a turning lathe, and the lens, which is held steadily in the hand, is ground upon them with emery, while they are revolving on the spindle of the lathe. In the same way convex lenses may be ground and polished, by fixing the concave tool upon the lathe; but these methods, however simple and expeditious they may be, should never be adopted for forming the lenses of optical instruments, where an accurate spherical figure is indispensable. It is by the hand alone that we can perform with accuracy those circular and transverse strokes, the proper union of which is essential to the production of a spherical surface.

Impropriety of grinding on a lathe.

On the Method of Casting, Grinding, and Polishing the Specula of Reflecting Telescopes.

The metals of reflecting telescopes are generally composed of 32 parts of copper, and 15 of grain tin, with the addition of two parts of arsenic, to render the composition more white and compact. The reverend Mr. Edwards found, from a variety of experiments, that if one part of brass, and one of silver, be added to the preceding composition, and only one part of arsenic used, a most excellent metal will be obtained, which is the whitest, hardest, and most reflective, that he ever met with. The superiority of this composition, indeed, has been completely evinced by the excellence of Mr. Edwards' telescopes, which excel other reflectors in brightness and distinctness, and shew objects in their natural colours. But as metals of this composition are extremely difficult to cast, as well as to grind and polish, it will be better for those who

Composition of the metal.

are inexperienced in the art, to employ the composition first mentioned.

Method of casting the metal.

After the flasks of sand[5] are prepared, and a mould made for the metal by means of a wooden or metallic pattern, so that its face may be downwards, and a few small holes left in the sand at its back, for the free egress of the included air;—melt the copper in a crucible by itself, and when it is reduced to a fluid state, fuse the tin in a separate crucible, and mix it with the melted copper, by stirring them together with a wooden spatula. The proper quantity of powdered arsenic, wrapt up in a piece of paper, is then to be added, the operator retaining his breath till its noxious fumes are completely dissipated; and when the scoria is removed from the fluid mass, it is to be poured out as quickly as possible into the flasks. As soon as the metal is become solid, remove it from the sand into some hot ashes or coals, for the purpose of annealing it, and let it remain among them till they are completely cold. The ingate is then to be taken from the metal by means of a file, and the surface of the speculum must be ground upon a common grindstone, till all the imperfections and asperities are taken away. When Mr. Edwards' composition is employed, the copper and tin should be melted according to the preceding directions, and, when mixed together, should be poured into cold water, which will separate the mass into a number of small particles. These small pieces of metal are then to be collected and put into the crucible,

[5] The finest sand which I have met with in this country, is to be found at Roxburgh castle, in the neighbourhood of Kelso.

along with the silver and brass; after they have been melted together in a separate crucible, the proper quantity of arsenic is to be added, and a little powdered rosin thrown into the fluid metal before it is poured into the flasks.

When the metal is cast, and prepared by the common grindstone for receiving its proper figure, the gages and grinding tools are to be formed in the same manner as for convex lenses, with this difference only, that the radius of the gages must always be double the focal length of the speculum. In addition to the convex and concave brass tools, which should be only a little broader than the metal itself, a convex elliptical tool of lead and tin should also be formed with the same radius, so that its transverse may be to its conjugate diameter as 10 to 9, the latter being exactly equal to the diameter of the metal. On this tool the speculum is to be ground with flour emery, in the same manner as lenses, with circular and cross strokes alternately, till its surface is freed from every imperfection, and ground to a spherical figure. It is then to be wrought with great circumspection, on the convex brass tool, with emery of different degrees of fineness, the concave tool being sometimes ground upon the convex one, to keep them all of the same radius, and when every scratch and appearance of roughness is removed from its surface, it will be fit for receiving the final polish. Before the speculum is brought to the polisher, it has been the practice to smooth it on a bed of hones, or a convex tool made of common blue hones. This additional tool, indeed, is absolutely necessary, when silver and brass enter into the composition of the metal, in order to remove that roughness which will always remain after the finest emery

Method of froming the grinding tools, &c.

Bed of hones.

has been used; but when these metals are not ingredients in the speculum, there is no occasion for the bed of hones. Without the intervention of this tool I have finished several specula, and given them as exquisite a lustre as they could possibly have received. Mr. Edwards does not use any brass tools in his process, but transfers the metal from the elliptical leaden tool to the bed of hones. By this means the operation is simplified, but we doubt much if it is, in the least degree improved. As a bed of hones is more apt to change its form than a tool of brass, it is certainly of great consequence that the speculum should have as true a figure as possible before it is brought to the hones; and we are persuaded, from experience, that this figure may be better communicated on a brass tool, which can always be kept at the same curvature by its corresponding tool, than on an elliptical block of lead. We are certain however, that when the speculum is required to be of a determinate focal length, this length will be obtained more precisely with the brass tools than without them. But Mr. Edwards has observed, that these tools are not only unnecessary, but 'really detrimental.' That Mr. Edwards found them unnecessary, we cannot doubt, from the excellence of the specula, which he formed without their assistance; but it seems inconceivable how the brass tools can be in the least degree detrimental. If the mirror is ground upon 20 different tools before it is brought to the bed of hones, it will receive from the last of these tools a certain figure, which it would have received even if it had not been ground on any of the rest; and it cannot be questioned, that a metal wrought upon a pair of brass tools, is equally, if not more, fit for the

bed of hones, than if it had been ground merely on a tool of lead.

When the metal is ready for polishing, the elliptical leaden tools is to be covered with black pitch,[6] about $\frac{1}{20}$ of an inch thick, and the polisher formed in the same way as in the case of lenses, either with the concave brass tool, or with the metal itself. The colcothar of vitriol should then be triturated between two surfaces of glass, and a considerable quantity of it applied at first to the surface of the polisher. The speculum is then to be wrought in the usual way upon the polishing tool, till it has received a brilliant lustre, taking care to use no more of the colcothar, if it can be avoided, and only a small quantity of it, if it should be found necessary. When the metal moves stiffly on the polisher, and the colcothar assumes a dark muddy hue, the polish advances with great rapidity. The tool will then grow warm, and would probably stick to the speculum, if its motion were discontinued for a moment. At this stage of the process, therefore, we must proceed with great caution, breathing continually on the polisher, till the friction is so great as to retard the motion of the speculum. When this happens, the metal is to be slipped off the tool at one side, cleaned with soft leather, and placed in a tube for the purpose of trying its performance; and if the polishing has been conducted with care, it will be found to have a true *parabolic* figure.

Method of polishing the metal.

[6] In summer, or when the pitch is soft, it should be hardened by the addition of a little rosin; and should always be strained through a piece of linen, in order to free it from impurities, and rough particles.

ON MICROSCOPES.

On the Single Microscope.

Single microscope.

In the first volume, we have described the method of forming small glass globules for the magnifiers of single microscopes;[7] and have also explained the manner in which the enlarged picture is formed upon the retina. When the lenses are made, either by fusion, or, which is by far the more accurate way, by grinding them on spherical tools, they are then to be fitted up for the purpose of examining minute objects. The method which Mr. Wilson has adopted in his pocket microscope, is very ingenious, though rather devoid of simplicity, as it obliges us to screw and unscrew the magnifiers, when we wish to view the object with a larger or a smaller power. The simplest and the most convenient method of mounting single microscopes, is to fix the lenses

Plate XI, Fig. 3.

a, b, c, d, in a flat circular piece of brass, $C D$, which can be moved round I as a centre, by the action of the endless screw $A B$, upon the toothed circumference of the circular plate. After the object has been viewed by some of the magnifiers, it may be examined successively with all the rest, by a few turns merely of the endless screw.

Its magnifying power.

In the first volume, Mr. Ferguson has already shewn how to find the magnifying power of single microscopes; but in order to save the trouble of calculation, we have computed the following new table of the magnifying power of

[7] See vol. i, p. 260, note 8.

convex lenses, from 1 inch to $\frac{1}{100}$ of an inch in focal length, upon the supposition that the nearest distance at which we see distinctly is *seven* inches. The first column contains the focal length of the convex lens in 100^{ths} of an inch. The second contains the number of times which such a lens will magnify the diameters of objects. The third contains the number of times that the surface is magnified; and the fourth the number of times that the cube of the object is magnified. —A table of a similar kind, though upon a much smaller scale, has already been published by Mr. Barker; but he supposes the nearest distance at which the eye can see distinctly, to be *eight* inches, which, I am confident from experience, is too large an estimate for the generality of eyes.

When we consider, however, that the eye examines very minute objects at a less distance than it does objects of greater magnitude; we will find that the magnifying power of lenses ought to be deduced from the *distance at which the eye examines objects really microscopic.* This circumstance has been overlooked by every writer on optics, and merits our attentive consideration. I have now before me two specimens of engraving. The one is so large that I can easily read it at the distance of 10 inches. The other, which is a watch paper, beautifully engraven by Kirkwood and Sons, contains the Lord's prayer in a circular space $\frac{1}{4}$ of an inch in diameter, and is so exceedingly minute, that I cannot read it at a distance exceeding 5 inches. Now I maintain, that if these two kinds of engraving are seen through the *same microscope*, the one will be *twice* as much magnified as the other. This indeed is obvious, for as the magnifying power of a lens is equal to the distance at which the object is ex-

amined by the naked eye, divided by the focal distance of the lens, we shall have $\frac{5}{x}$ for the number of times that the watch paper is magnified, and $\frac{10}{x}$ for the number of times that the large engraving is magnified, x being the focal length of the lens. It follows, therefore, that the number of times that any lens magnifies objects really microscopic, should be determined by making the distance at which they are examined by the naked eye 5 inches.

Upon this principle I have computed Table II, which contains the magnifying power of convex lenses, when employed to examine microscopic objects.

TABLE I.

New Tables of the Magnifying Power of small Convex Lenses, or Single Microscopes, the distance at which the eye sees distinctly being 7 inches.

A new table for single microscopes.

Focal distance of the lens or microscope.	Number of times that the *diameter* of an object is magnified.	Number of times that the *surface* of an object is magnified.	Number of times that the *cube* of an object is magnified.
100ths of an inch.	Times. Dec. of a Time.	Times.	Times.
1 100	7.00	49	343
$\frac{3}{4}$ 75	9.33	87	810
$\frac{1}{2}$ 50	14.00	196	2744
$\frac{2}{5}$ 40	17.50	306	5360
$\frac{3}{10}$ 30	23.33	544	12698
$\frac{2}{10}$ 20	35.00	1225	42875
19	36.84	1354	49836
18	38.89	1513	58864
17	41.18	1697	69935
16	43.75	1910	83453
15	46.66	2181	101848
14	50.00	2500	125000
13	53.85	2894	155721
12	58.33	3399	198156
11	63.67	4045	257259
$\frac{1}{10}$ 10	70.00	4900	343000
9	77.78	6053	470911
8	87.50	7656	669922
7	100.00	10000	1000000
6	116.66	13689	1601613
$\frac{1}{20}$ 5	140.00	19600	2744000
$\frac{1}{25}$ 4	175.00	30625	5359375
3	233.33	54289	12649337
$\frac{1}{50}$ 2	350.00	122500	42875000
1	700.00	490000	343000000

TABLE II.

A New Table of the Magnifying Power of Small Convex Lenses, or Single Microscopes, the distance at which the eye sees distinctly being 5 inches.

Focal distance of the lens or microscope.		Number of times that the *diameter* of an object is magnified.		Number of times that the *surface* of an object is magnified.	Number of times that the *cube* of an object is magnified.
100ths of an inch.		Times.	Dec. of a Time.	Times.	Times.
1	100	5.00		25	125
$\frac{3}{4}$	75	6.67		44	297
$\frac{1}{2}$	50	10.00		100	1000
$\frac{2}{5}$	40	12.50		156	1953
$\frac{3}{10}$	30	16.67		278	4632
$\frac{2}{10}$	20	25.00		625	15625
	19	26.32		693	18233
	18	27.78		772	21439
	17	29.41		865	25438
	16	31.25		977	30518
	15	33.33		1111	37026
	14	35.71		1275	45538
	13	38.48		1481	56978
	12	41.67		1736	72355
	11	45.55		2075	94507
$\frac{1}{10}$	10	50.00		2500	125000
	9	55.55		3086	171416
	8	62.50		3906	244141
	7	71.43		5102	364453
	6	83.33		6944	578634
$\frac{1}{20}$	5	100.00		10000	1000000
$\frac{1}{25}$	4	125.00		15625	1953125
	3	166.67		27779	4629907
$\frac{1}{50}$	2	250.00		62500	15625000
	1	500.00		250000	125000000

On the Double Microscope.

The double microscope is composed of two convex lenses placed at any distance not less than the sum of their focal lengths; and a lens with a large aperture and focal distance is generally fixed a little beyond the anterior focus of the eye-glass, for the purpose of enlarging the field of view. As the focal length of the lenses, as well as their distances, are altogether arbitrary, different opinions have been entertained respecting the most suitable values of these quantities. I have found, however, from experience, that a good compound microscope may be formed by making the object glass $\frac{4}{10}$ of an inch in focal length, and the eye-glass 1 inch, their distance being about 8 inches. The amplifying lens or second eye-glass should generally be $1\frac{1}{4}$ inches in diameter, with $2\frac{1}{2}$ inches of focal length, and placed at $1\frac{1}{4}$ inches before the eye-glass; and the aperture of the object glass should not exceed *one tenth* of an inch. If, however, we increase the magnifying power of the microscope by augmenting the distance between the glass next the object and that next the eye, we must likewise enlarge the aperture of the object glass; but if we increase the magnifying power by augmenting the curvature, or diminishing the focal length of the object glass, the aperture must be proportionally diminished. The distance of the eye from the eye-glass should be equal to the focal distance of the latter; and the hole through which the rays are finally transmitted should not exceed *one seventh* of an inch. Double microscopes.

The method of finding the magnifying power of double microscopes when only two lenses are Its magnifying power.

employed, has been shewn in the first volume. But as an amplifying lens, or second eye-glass, is always used, we shall shew how to determine the magnifying power of these instruments when three lenses are employed. The following rule we believe is new. Divide the difference between the distance of the two first lenses, or those next the object, and the focal distance of the second or amplifying glass, by the focal distance of the second glass, and the quotient will be a first number. Square the distance between the two first lenses, and divide it by the difference between that distance and the focal distance of the second glass, and divide this quotient by the focal distance of the third glass, or that next the eye, and a second number will be had. Multiply together the first and second numbers, and the magnifying power of the object glass, and the product will be the magnifying power of the compound microscope.

Rule for finding it.

ON TELESCOPES.

On the Refracting Telescope.

Refracting telescope.

Having already described the nature and operation of refracting telescopes, we have now only to lay before the reader a new table of the apertures and magnifying powers of these instruments, more accurate we trust than any which has yet been published. It is a remarkable circumstance, that the only table of this kind which has appeared, was copied by succeeding writers from Dr. Smith's optics, as the production of the celebrated Huygens, while it was calculated only by the editors of his dioptrics. An excellent

Reasons for computing a new table.

telescope of Huygens, indeed, was the standard upon which the table was constructed; but this philosopher informs us in his *Astroscopia Compendiaria*, that he had a refracting telescope with an object glass 34 feet in focal length, which, in astronomical observations, bore an eye-glass of $2\frac{1}{2}$ inches focal distance, and therefore magnified 163 times, which is considerably greater, in proportion, than the magnifying power of the standard telescope upon which the old table was founded. Since the lenses of these instruments therefore may now be wrought with the same accuracy as in the time of Huygens, we have computed the following table according to this new standard, the apertures, magnifying powers, and the focal length of the eye-glass being severally as the square roots of their focal lengths. As the dimensions of the standard telescope of Huygens were taken in rhinland measure, the following table is suited to the same measure; but the second and third columns may be converted into English measure, by dividing them by 7, the focal lengths of the object glasses being supposed English feet.

Method of removing the spherical aberration.

In order to render the common refracting telescope as perfect as possible, without making it achromatic, the exterior surface of the object glass should be ground to a radius equal to *five ninths* of its focal length, and the radius of the interior surface, or that next the eye, should be *five* times its focal length. In eye-glasses, the radius of the surface next the object, should be *nine* times its focal distance, and that of the surface next the eye, *three fifths* of the same distance. By this means, the aberration arising from the spherical figure of the lenses will be nothing for objects placed in the direction of

their axis, and the least possible for objects removed from the axis. According to Huygens, the spherical aberration was the least possible when the radii of the surfaces were as 6 to 1: But though this be true for objects placed in the axis of the lenses, yet a considerable aberration remains when the objects are placed on one side of the axis.

A New Table of the Apertures, Focal lengths, and Magnifying Power of Refracting Telescopes.

A new table for refracting telescopes.

Focal length of the object glass.	Linear aperture of the object glass.	Focal distance of the eye-glass.	Magnifying power.
Feet.	Inch. Dec.	Inch. Dec.	Times.
1	0.65	0.50	28
2	1.03	0.62	39
3	1.30	0.75	48
4	1.45	0.87	55
5	1.61	1.00	60
6	1.79	1.07	67
7	1.96	1.15	73
8	2.14	1.21	77
9	2.20	1.30	83
10	2.32	1.38	87
13	2.63	1.58	99
15	2.81	1.70	106
20	3.31	1.95	123
25	3.73	2.15	139
30	4.01	2.40	150
35	4.34	2.58	163
40	4.64	2.76	174
45	4.92	2.93	184
50	5.20	3.08	195
55	5.48	3.22	205
60	5.71	3.36	214
70	6.16	3.64	231
80	6.58	3.90	246
90	7.02	4.12	262
100	7.39	4.35	276
200	10.41	6.17	389
300	12.89	7.52	479
400	14.72	8.71	551
500	16.52	9.71	618

On the Gregorian Telescope.

Gregorian telescope.

To the observations already made upon this instrument, we have only to add a few practical remarks. In order to remove the tremors from reflecting telescopes, the springs and screws should be taken away from the back of the speculum, and three small screws employed, which pass through the tube perpendicular to its axis, and touch the back of the mirror merely with their sides. As the speculum is apt to bend when it is supported wholly upon its lower extremity, it should be made to rest upon two points 45 degrees distant from its lowest part, and on each side of it; and if the metal is wedged in at these points with bits of card, it will be prevented from falling backward or resting upon its lowest point. Some reflecting telescopes may be much improved, as Dr. Maskelyne has shewn, by inclining the great speculum about $2\frac{1}{2}$ degrees[1] to the axis of the tube, so that the pencils of rays may fall obliquely on its aurface.[2]

The diameter of the small eye hole may be found by dividing the aperture of the telescope in inches by its magnifying power; but it is generally about $\frac{1}{50}$ of an inch.

The following table, founded upon the computations of Dr. Smith, contains all the dimensions of Gregorian telescopes, and is more comprehensive and accurate than that which Mr. Edwards published.

---

[1] This degree of inclination greatly improved the 6 feet Newtonian reflector in the Observatory of Greenwich; but different specula will require different degrees of obliquity, and some may rather be injured by such an inclination.

[2] These observations are also applicable to the metals of Cassegrainian and Newtonian telescopes.

Table of the Dimensions, Focal lengths, and Apertures, of Gregorian Telescopes, as constructed by Mr. Short, according to the computations of Dr. Smith. See Plate XVIII, Fig. 7.

Focal length of the great speculum.	Breadth of the great speculum.	Breadth of the small speculum, and of the hole in the large one.	Focal length of the small speculum.	Distance between the two specula.	Distance between the large speculum and the plane surface of the first eye-glass.	Focal distance of the first eye-glass, or that next the metals.	Focal distance of the second eye-glass, or that next the eye.	Distance between the plane sides of the two lenses	Distance between the second eye-glass and the small eye-hole.	Diameter of the diaphragm placed in the anterior focus of the lens *S*.	Magnifying power.
P m.	*D F.*	*U V=b g.*	*L n.*	*P L.*	*P R.*	*R.*	*S.*	*R S.*	*S e.*	*a b.*	
Inch. Dec.	Inch. Dec.	Inch. Dec.	Inch. Dec.	In. Dec.	Inch. Dec	Inch. Dec.	Inch. Dec.	Inch. Dec.	Inch. Dec.	Inch. Dec.	Times.
5.65	1.55	0.31	1.11	6.78	1.76	2.45	0.81	1.63	0.41	0.27	40
9.60	2.30	0.40	1.50	11.25	3.36	3.13	1.04	2.09	0.52	0.35	60
15.50	3.30	0.50	2.15	17.84	3.95	5.97	1.31	2.63	0.66	0.44	86
36.00	6.26	0.65	3.43	39.72	1.44	5.12	1.71	3.41	0.85	0.57	165
60.00	9.21	0.83	5.01	65.39	2.78	6.43	2.14	4.29	1.07	0.72	243
1	2	3	4	5	6	7	8	9	10	11	12

On the Cassegrainian Telescope.

Cassegrainian telescope.

From the following table of the dimensions of Cassegrainian telescopes, founded on Dr. Smith's calculations, it appears, that though they are shorter by twice the focal distance of the small speculum than those of the Gregorian form with the same focal length, yet they have a greater magnifying power. A Cassegrainian telescope $15\frac{1}{2}$ inches in focal length, will magnify, according to the table, 93 times; while a Gregorian one, with a similar speculum, magnifies only 86 times. This great difference between the performance of these instruments, does not exist merely in theory; for Mr. Short constructed a telescope of the Cassegrainian form, of 24 inches focus, which, with an aperture of 6 inches, magnified 355 times. With this power, indeed, it was rather indistinct; but it bore a power of 231 times with sufficient distinctness. In the Observatory at Greenwich, there is a Gregorian telescope of Short's construction, which magnifies 250 times when the smallest mirror is employed, which is considerably less than the power of the Cassegrainian one of the same size.

Reflecting telescopes are generally furnished with two or three small specula of different focal lengths, that the magnifying power may be varied without changing the eye-piece.

Table of the Dimensions, Focal lengths, and Apertures, of Cassegrainian Telescopes. See Plate XVIII, Fig. 7. in which the Small Convex Speculum is supposed to be placed at GH.

Focal length of the great speculum.	Breadth of the great speculum.	Breadth of the small speculum, and of the hole in the large one.	Focal length of the small speculum.	Distance between the two specula.	Distance between the large speculum and the plane surface of the first eye glass.	Focal distance of the first eye-glass or that next the metals.	Focal distance of the second eye-glass or that next the eye.	Distance between the plane sides of the two lenses.	Distance between the second eye-glass and the small eye-hole.	Diameter of the diaphragm, placed in the anterior focus of the lens *S*.	Magnifying power.
P m.	*D F.*	*U V.*			*P R.*	*R.*	*S.*	*R S.*	*S c.*	*a b.*	
Inch.Dec.	Inch.Dec.	Inch.Dec.	Inch.Dec.	In.Dec.	Inch.Dec.	Inch.Dec.	Inch.Dec.	Inch.Dec.	Inch.Dec.	Inch.Dec.	Times.
15.50	3.52	0.40	1.97	13.51	1.41	3.17	1.06	2.11	0.53	0.18	93
36.00	6.57	0.59	3.57	32.75	1.65	4.69	1.56	3.03	0.78	0.26	173
60.00	9.61	0.77	3.17	55.21	2.97	6.06	2.02	4.04	1.01	0.34	253
1	2	3	4	5	6	7	8	9	10	11	12

On the Newtonian Telescope.

Newtonian telescope.

As the Newtonian telescope was powerfully recommended to the world by the simplicity of its construction, as well as by the name of its illustrious inventor, it is a matter of surprise that its merits should have been so long overlooked. During the last century Gregorian telescopes seem to have been universally preferred to those of the Newtonian form, till the celebrated Dr. Herschel introduced the latter into notice, by the splendour and extent of the discoveries which they enabled him to make. This philosopher, equally distinguished by his virtues and his talents, has constructed Newtonian telescopes from 7 to 40 feet[1] in focal length, by which he has greatly enlarged our knowledge of the solar system, and disclosed many new and important facts respecting the structure of the heavens.

PLATE XVIII, Fig. 7.

In the Newtonian telescope, the large parabolic speculum is not perforated with a hole UV. A small elliptical plane mirror, inclined 45 degrees to the axis of the tube, is placed at GH, about as much nearer the speculum than its focus, as the centre of the small mirror is distant from the tube; that is, the distance Gm of the small speculum from the focus of the great one, should be nearly equal to PT, half the diameter of the tube. The rays which form the image IK of the object AB instead of proceeding to form it at m, are intercepted by the plane spe-

[1] A description of this noble instrument may be seen in the Phil. Trans. 1795, pt. 2. The diameter of the speculum is 4 feet, its thickness about $3\frac{1}{2}$ inches, and its greatest magnifying power 6000.

culum at GH, and refracted upwards through an aperture in the side of the tube TT, where the image is formed and magnified by a double convex lens of a short focal distance.

As the small plane mirror has an oblique position to the eye, it must be of an elliptical form. In order to find its conjugate or shortest diameter, say as the focal length of the great speculum is to its aperture, so is the distance of the small speculum from the focus of the great one to the conjugate diameter of the small mirror; that is, the conjugate diameter of the small mirror is $= \frac{Gm \times DF}{Pm}$. Its transverse or longest diameter will be $= \frac{Gm \times DF}{Pm} \times 1.4142$; that is, equal to the conjugate diameter multiplied by 1.4142; or, which is the same thing, its transverse will be to its conjugate diameter as 7 to 5,[1] which is nearly the ratio of the diagonal of a square to one of its sides.—If a rectangular prism be substituted in place of the small mirror, having its sides perpendicular to the incident and emergent rays, the image will be erected, and a less quantity of light will be lost, than when the reflection is made from a mirror of the common kind. Form of the plane mirror.

In most of Dr. Herschel's telescopes the plane mirror is thrown away, and the focal image IK is viewed directly with a small eye glass, placed at TE, the lower side of the tube. When the aperture of the speculum is very large, the loss of light occasioned by the interposition of part of Dr. Herschel's improvements.

[1] Mr. Adams in his *Introduction to Natural Philosophy*, v. ii, p. 534, erroneously observes, that the length of the small speculum should be to its breadth as 2 to 1.

the observer's head is trivial; but when the aperture is small, the speculum must be inclined a little to the incident rays. I have frequently taken a Newtonian speculum, $3\frac{4}{10}$ inches in diameter, and 30 inches in focal length out of its tube, and viewed the moon in this manner with great satisfaction. The superior performance of Newtonian telescopes, without the plane mirror, can be conceived only by those who have made the experiment.

A new finder for Newtonian telescopes.

As it is more difficult to find any of the heavenly bodies with a Newtonian than with a Gregorian telescope, it has been customary to fix a small astronomical telescope on the tube of the former, so that the axis of the two instruments may be parallel. The aperture of its object glass is large, and cross hairs are fixed in the focus of the eye glass. The object is then found by this small telescope, which is called the *finder*; and if the axis of the instruments are rightly adjusted, it will be seen also in the field of the large telescope. When the Newtonian telescope, however, is large, and placed upon its lower end to view bodies in great altitudes, the finder can be of no use, from the difficulty of getting the eye to the eye piece. On this account I would propose to bend the tube of the finder to a right angle, and place a plane mirror at the angular point, so as to throw the image to one side, or rather above the upper part of the tube, that the eye piece of the finder may be as near as possible to the eye piece of the telescope. If the latter of these plans be adopted, the angular point, where the plain mirror is fixed, should be placed as near as possible to the focal image, in order that only a small part of the finder may stand above the tube; for in this way the eye can be trans-

ferred with the greatest facility from the one eye piece to the other. The advantages of this construction will be understood from Figure 7, where TT is part of a Newtonian telescope, D the eye-piece, and ABC the finder. The image formed by the object glass A is reflected upwards by the plain mirror B, placed at an angle of 45 degrees with the axis of the tube, and the image is viewed by the eye glass at C. Those who have been in the habit of using the Newtonian telescope with the common finder, will be sensible of the convenience resulting from this contrivance. PLATE XIII, Fig. 7. App.

Reasons for computing a new table for Newtonian telescopes.

The only table, containing the apertures, magnifying power, &c. of Newtonian telescopes, which has hitherto been published, was calculated by Dr. Smith,[4] from the middle aperture and power of Hadley's excellent Newtonian telescope, as a standard, the focal length of the great speculum being 5 feet $2\frac{1}{2}$ inches, its aperture 5 inches, and power 208. A speculum, however, 3 feet and 3 inches in focal length, was wrought, by Mr. Hauksbee, to so great perfection, as to magnify 226 times.[5] It shewed the minute parts of the new moon very distinctly, as well as the belts of Jupiter, and the black list or division of Saturn's ring. For these objects, it bore an aperture of $3\frac{1}{2}$ or 4 inches; but in cloudy weather it shewed land objects most distinct, when the whole surface of the metal was exposed, which was $4\frac{1}{2}$ inches in diameter. Since the method of grinding specula, and giving them a true parabolic figure, is much better un-

[4] Optics, vol. i, p. 148. Dr. Smith's table was continued from 17 to 24 feet, by Mr. Edwards.

[5] Smith's Optics, vol. ii. *Remarks*, p. 79, col. 2.

derstood at present than it was in the time of Mr. Hauksbee, Newtonian telescopes may be made as perfect as this instrument of his construction. Upon it, as a standard, therefore, we have computed the following new table, on the supposition, that reflecting telescopes, of different lengths, shew objects equally bright and distinct, when their linear apertures, and their linear amplifications, or magnifying powers, are as the *square square roots*, or *biquadratic roots*, of the cubes of their focal lengths; and consequently, when the focal distances of their eye glasses are as the square square roots of their lengths.

Explanation of the table.

The first column contains the focal length of the great speculum in feet, and the second its linear aperture in inches, and 100^{ths} of an inch. The third and fourth columns contain Sir Isaac Newton's numbers, by means of which the apertures of any kind of reflecting telescope may be readily computed.[6] The fifth column exhibits the focal length of the eye glasses in 1000^{ths} of an inch; and the sixth contains the magnifying power of the instrument.

---

[6] See Gregory's Optics, Appendix, p. 229, and the Philosophical Transactions, No. 81, p. 4004.

A New TABLE of the Apertures and Magnifying Power of Newtonian Telescopes.

Focal length of the concave speculum.	Aperture of the concave speculum.	Sir Isaac Newton's numbers.		Focal length of the eye-glass.	Magnifying power.
Feet.	Inch.Dec.	Aperture of the speculum.	Focal length of the eye-glass.	Inch.Dec.	Times.
$\frac{1}{2}$	1.34	100	100	0.107	56
1	2.23	168	119	0.129	93
2	3.79	283	141	0.152	158
3	5.14	383	157	0.168	214
4	6.36	476	168	0.181	265
5	7.51	562	178	0.192	313
6	8.64	645	186	0.200	360
7	9.67			0.209	403
8	10.44	800	200	0.218	445
9	11.69			0.222	487
10	12.65	946	212	0.228	527
11	13.58			0.233	566
12	14.50	1084	221	0.238	604
13	15.41			0.243	642
14	16.25			0.248	677
15	17.11			0.252	713
16	17.98	1345	238	0.256	749
17	18.82			0.260	784
18	19.63			0.264	818
19	20.45			0.268	852
20	21.24	1591	251	0.271	885
21	22.06			0.274	919
22	22.85			0.277	952
23	23.62			0.280	984
24	24.41	1824	263	0.283	1017

A new table for Newtonian telescopes.

Dr. Herschel's telescopes.

The telescope which Dr. Herschel generally uses, and with which he has made many of his best discoveries, is a Newtonian reflector, with a speculum 7 feet in focal length, having an aperture of $6\frac{1}{4}$ inches, and powers of 227 and 460, though he sometimes employs a power of 6450 for the fixed stars. Dr. Herschel informs me, that he obtains such high powers, merely by using small double convex lenses for eye-glasses, and that he has some in his possession less than *one fiftieth of an inch* in focal length.

In one of Dr. Herschel's 7 feet telescopes which I have seen in the possession of Mr. Sligo, an ingenious gentleman in Edinburgh, an achromatic eye-piece was employed for the smallest magnifying power. The large speculum is well finished, and the image which it formed remarkably distinct. The contrivances by which the vertical and horizontal movements were effected, are particularly simple and ingenious, and do great credit to their inventor.

OPTICS.

DESCRIPTION OF A NEW FLUID MICROSCOPE INVENTED BY THE EDITOR.

FOR the first idea of fluid microscopes we are indebted to the ingenious Mr. Stephen Grey, who published an account of his discovery in the Transactions of the Royal Society.[1] They consisted merely of a drop of water, taken up on the point of a pin, and placed in a small hole at D, $\frac{1}{30}$ of an inch in diameter, in the piece of brass $D\,E$, about $\frac{1}{10}$ of an inch thick. The hole D is in the middle of a spherical cavity, about $\frac{1}{8}$ of an inch in diameter, and a little deeper than half the thickness of the brass. On the opposite side of the brass is another spherical cavity, half as broad as the former, and so deep as to reduce the circumference of the small hole to a sharp edge. The water being placed in these cavities, will form a double convex lens, with unequal convexities. The object, if it is solid, is fixed upon the point C of the supporter $A\,B$, and placed at its proper distance from the water lens, by the screw $F\,G$. When the object is fluid, it is placed in the hole A, but in such a manner as

Fluid microscopes first invented by Mr. Gray.

PLATE XII, Fig. 1.

Description of his water microscope.

[1] Phil. Trans. No. 221, 223. See also Smith's Optics, vol. ii, p. 394.

not to be spherical; and this hole is brought opposite the fluid lens, by moving the extremity *G* of the screw into the slit *G H*.

Description of the new fluid microscope. PLATE XI, Fig. 2, 3, 4.

From this microscope of Mr. Grey's, the one which we are now to describe is totally different. It is represented, as fitted up, in Plate XI, Fig. 2, and some of its parts, on a larger scale, in Fig. 3 and 4. A drop of very pure and viscid turpentine varnish is taken up by the point of a piece of wood, and dropped at *a*, upon the piece of thin and well polished glass *abcdI*; and different quantities being taken up, and dropped, in a similar manner, at *b*, *c*, *d*, will form four or more plano-convex lenses of turpentine varnish, which may be made of any focal length, by taking up a greater or a less quantity of the fluid. The lower surface of the glass *abcdI*, having been first smoked with a candle, the black pigment, immediately below the lenses *a*, *b*, *c*, *d*, is then to be removed, so that no light may pass by their circumferences. The piece of glass, *aIc*, is next to be perforated at *I*, and surrounded with a toothed wheel *CD*, which can be moved round *I* as a centre, by the endless screw *AB*. The apparatus *CDBA* is placed in a circular case, which is represented by *BH* in Fig. 2, and part of it, on a larger scale, by *CD* in Fig. 4, and to its sides the screw *AB* is fastened, by means of the two arms *m*, *n*. This circular case is fixed to the horizontal arm *R*, by means of a brass pin, which passes through its upper and under surfaces, and through the hole *I*, (Fig. 3), which does not embrace the pin very tightly, in order that *CD* may revolve with facility. On the upper surface of *BH* is an aperture *K*, directly above the line described by the centres of the fluid lenses, when moving

round *I*; and in this aperture is inserted a small cap, with a little hole at its top, to which the eye is applied. *EMN* is the moveable stage, that carries the slider *OP*, on which microscopic objects are laid; and is brought nearer, or removed from, the lenses by the vertical screw *DE*. *RS* is the perpendicular arm to which the microscope is attached. *FG* is the pedestal; and *C* is a plain mirror, which has both a vertical and horizontal motion, in order to illuminate the objects on the slider.

When the microscope is thus constructed, the object to be viewed is placed upon *OP*, and the screw *AB* is turned, till one of the lenses be directly below the aperture *K*. The slider is then raised or depressed, by the screw *DE*, till the object be brought into the focus of the lens. In this manner, by turning the screw *AB*, and bringing all the lenses, one after another, directly below *K*, the object may be successively examined with a variety of magnifying powers. Method of adjusting it.

The focal lengths of these fluid lenses will increase a little after they are formed; but if they are preserved from dust, they will last for a long time. The turpentine varnish should be as pure and viscid as possible; the glass on which it is dropped should be very thin; and the microscope should stand on a horizontal surface.

I have even employed these fluid lenses as the object glasses of compound microscopes; and I once constructed a compound microscope, in which both the object-glass and eye-glass were made of turpentine varnish. It performed much better than I expected, but rather gave a yellowish tinge to the objects which were presented to it. Compound fluid microscopes.

OPTICS.

ACCOUNT OF AN IMPROVEMENT ON THE CAMERA OBSCURA, AND OF A NEW PORTABLE ONE UPON A LARGE SCALE.

THE camera obscura, which is one of the simplest and most amusing of our optical instruments, has already been described in the first volume.[1] The improvements which have been made upon it since its first invention, regard chiefly its external form, and no attempts have been made to increase the brilliancy and perfection of the image. When we compare the picture of external objects, which is formed in a dark chamber by the object-glass of a common refracting telescope, with that which is formed by an achromatic object-glass, we will find the difference between their distinctness much less than we would have at first expected. Although the achromatic lens forms an image of the minutest parts of the landscape, yet when this image is received on paper, these minute parts are obliterated by the small hairs and asperities on its surface, and the effect of the picture is very much impaired. In the Royal Observatory at Greenwich, the image is received upon a large concave piece of stucco, but from the testimony of those who have witnessed its effects, this sub-

Causes of indistinctness in the camera obscura.

[1] See vol i, pp. 285, 286.

stance does not seem to be more favourable for the reception of images than a paper ground. In order to obviate these inconveniencies, I tried a number of white substances of different degrees of smoothness, and several metallic surfaces with different degrees of polish, but did not succeed in finding any surface superior to paper. I happened, however, to receive the image on the silvered back of a looking glass, and was surprised at the brilliancy and distinctness with which external objects were represented. The little spherical protuberances, however, which arise from the roughness of the tin-foil, have a tendency to detract from the precision of the image, and certainly injure it considerably when examined narrowly with the eye. In order to remove these small eminences, I ground the surface carefully with a bed of hones, which I had used for working the plane specula of Newtonian telescopes. By this operation, which is exceedingly delicate, and may be performed without injuring the other side of the mirror, I obtained a surface finely adapted for the reception of images. The minute parts of the landscape are formed with so much precision, and the brilliancy of colouring is so uncommonly fine, as to equal, if not exceed the images which are formed in the air by means of concave specula. Notwithstanding the blueish colour of the metallic ground, white objects are represented in their true colour, and the verdure of the foliage appears so rich and vivid, that the image seems to surpass in beauty even the object itself. On account of the metallic lustre of the surface, the distinctness of the image will always be greatest when the eye of the observer is placed in the direction of the reflected rays.

Method of removing these and rendering the image more brilliant and distinct.

Description of a new portable camera obscura.

The common portable camera obscura, which has already been described,[1] is necessarily on a small scale, and is very far from being convenient. These inconveniencies are completely remedied in the camera obscura invented by my friend the Rev. Mr. Thomson of Duddingston, which is represented in Figures 5. and 6 of Plate XIV. In Fig. 5, A is a metallic or wooden ring, in which the four wooden bars AF, AI, AG, AH, move by means of joints at A; and are kept asunder by the cross pieces B,C, D,E, which move round B and D as centres, and fold up along BA, and DA, when the instrument is not used. The surface $FIGH$, on which the image is received, consists of a piece of silk covered with paper. It is made to roll up at IH, which moves in a joint at I, so that the whole surface $FIHG$, when winded upon IH, can be folded upon the bar IA. By this means, the instrument which is covered with green silk, lined with a black substance, may be put together and carried as an umbrella. It is shewn more fully in Fig. 6, where A is the aperture for placing the lens, and BC a semi-circular opening for viewing the image. A black veil may be fixed to the circumference of BC, and thrown over the head of the observer to prevent the admission of any extraneous light.

PLATE XIV, Fig. 5.

Fig. 6.

[1] See vol. i, p, 286.

DIALING.

DESCRIPTION OF AN ANALEMMATIC DIAL, WHICH SETS ITSELF.

THE analemmatic dial is represented by CD in Fig. 2 of Plate XII, and is generally described upon the same surface with a horizontal dial AB, for the purpose of ascertaining its proper position, without the assistance of a meridian line or compass. It is always of an elliptical form, approaching to that of a circle, as the place for which it is made recedes from the equator. Its stile is perpendicular, and has different positions in the line ♋ ♑, changing with the declination of the sun, and indicated by the names of the months marked upon its surface. From the obliquity of the stile of the one dial, and the rectangular position of the other, the motion of their shadows is so different, that the dial may be reckoned properly placed when the shadows of both stiles indicate the same hour. Analemmatic dial. PLATE XII, Fig. 2.

In order to understand the theory and construction of this dial, let BE be its length perpendicular to the direction of the meridian. Having bisected BE in A, make AO equal to the sine of the latitude of the place; and with the cosine of the latitude as radius, set off AD and AC equal to the tangent of 23° 28′, the Theory of the dial. Fig. 4.

sun's greatest declination. The points *D* and *C* are the places of the stile in the time of the solstices, on the 21st of June and December; and if the tangent of the sun's declination for the first day of every month is set off in a similar manner between *A* and *D*, and *A* and *C*, the points thus found will be the place of the stile on those days, and the radius *B C* drawn from all these points to *B* will be the hour line of six at these different times.

Fig. 5. In order to prove this, let *Z Æ N H* (Fig. 5), be the meridian, *P p* the six o'clock hour circle, and *P H* the height of the pole, then *A Z S* is the azimuth of the sun, and *P Z S* its complement, *A S* the sun's declination, and *P S* its complement. Now, in the spherical triangle *P Z S* right angled at *P*, we have by spherical trigonometry (Playfair's Euclid, prop. XVIII.) Radius: Sin. *P Z*=Tang. *P Z S*: Tang. *P S*, that is, Radius: Sin. *P Z*=Co Tang. Azimuth: Co Tang. declination, for *P Z S* is the complement of the azimuth, and *P S* the codeclination; but as radius is a mean proportional between the tangent and cotangent (Def. IX, Cor. 1, plane trigonom.), the tangents will be in the reciprocal ratio of the cotangents, and consequently cotang. azimuth: cotang. declin.=Tang. declin.: Tang. azimuth. Therefore, Rad. : Sin *P Z*=Tang. declin. : Tang. : azimuth; and the sine of *P Z* the colatitude, is the same as the cosine of the latitude.

Now, if *A C* represents the six o'clock hour line when the sun is in the equator, and *A C* the tangent of the sun's declination, for a radius equal to the cosine of the latitude, or *A C*=Tang. declin. × cosin. latitude, the angle *A B C* will be equal to the sun's azimuth, for from the last

analogy, Tang. declin. × cos. latitude=Rad. × Tang. azimuth, therefore AC=Rad. × Tang. azimuth; that is, AC is equal to the tangent of the sun's azimuth when AB is radius; and consequently ABC is the sun's azimuth since AC is its tangent. If the sun were in the equator and the stile at A, his azimuth from the south would be OAB, whereas when the stile is at C, his azimuth is OCB, which is equal to $OAB - ABC$; therefore ABC is the sun's azimuth from the east or west at six o'clock, and BC the six o'clock hour line. In the same way it might be shewn, when the stile is placed in any point between C and D, that a line drawn from it to the point B will be the six o'clock hour line for that declination, and that the angle at B, comprehended between this line and AB, will be equal to the azimuth of the sun.

In order to determine the horary points and the circumference of the dial, we must consider, that if the equator be projected upon the horizon of any place, it will form an ellipse whose conjugate or shortest diameter is equal to the sine of the latitude of that place. Let BMF therefore, be the equator projected on the horizon of a given place, so that AM half the conjugate axis is to AB, half the transverse axis, as the sine of the latitude of that place is to radius. Then having described the semicircle $BXIIF$, divide the quadrants $BXII$, and $XIIF$, into six equal parts for the hours, into 12 for the half hours, and into 24 for the quarters, each hour being 15 degrees in the daily motion of the sun, each half hour 7° 30′, and each quarter 3° 45′, and from these points, from the point III, for example, draw $IIICE$ parallel to $AXII$, or perpendicular to AB, the point

Fig. 6.

C where this line cuts the ellipse will be the horary point, and $D\,C$ will be the three o'clock hour line when the stile is at D.

As there is some difficulty, however, in describing an ellipse with accuracy, we shall shew how to find the horary points without describ-
Fig. 5. ing this conic section. Take $B\,C$ equal to the breadth of the dial, and having bisected it in A, draw A 12 perpendicular to $B\,C$, and equal to the sine of the latitude, $A\,C$ being radius. Then upon the centre A, with the distance A 12, describe the semicircle D 12 F, and with the distance $A\,B$ the semicircle $C\,H\,B$. Divide the quadrant $H\,B$ into six equal parts for hours in the points m, n, o, p, q, and the quadrant 12 E into the same number of equal parts in the points a, b, c, d, e; and through a, b, c, &c. draw a 11, b 10, c 9, &c. parallel to $C\,B$; and through m, n, o, &c. draw m 1, n 2, o 3, parallel to $H\,A$; —the points of intersection 1, 2, 3, 4, 5, will be the horary points, and will be in the circumference of an ellipse. The horary points being thus known, it is not necessary to trace the ellipse, otherwise it might be easily done with the hand. If the divisions $H\,m$, $m\,n$, &c. are subdivided into half hours and quarters, or even lower, the corresponding points in the ellipse 12 B may be determined in a similar manner.

In order to demonstrate that C is the horary point of three o'clock, and $D\,C$ the hour line when the sun is at his greatest north declination, we must find from the construction the angle $C\,D\,M$, or the sun's azimuth, reckoned from the south, and see if the triangle $P\,Z\,S$ (Fig. 7) furnishes us with a similar expression of the
Fig 6. angle Z, or sun's azimuth. In Fig. 6, $C\,H$, or its equal $A\,E$, is evidently the sine of the horary

angle, AB being radius; and since CE or AH is the cosine of the horary angle, in a circle whose radius is AM, or the sine of the latitude, we will have CE or AH=Cos. horary angle × Sin. lat. But according to the first part of the construction AD=Tan. declin. × Cos. lat.; therefore DH, the difference between AD and AH will be = Cos. hor. angle × Sin. lat—Tang. declin. × Cos. lat.; and the tangent of the angle CDH or $\frac{CH}{DH}$ will then be equal to

$$\frac{Sin.\ Hor.\ Angle}{Cos.\ Hor.\ Angle \times Sin.\ Latit. - Tang.\ Decl. \times Cos.\ Lat.}$$

Now, in order to find a similar expression for the angle PZS, (Fig. 7) let SO be a perpendicular upon PZ; and the Sines of the segments PO, ZO, will be reciprocally proportional to the angles at the base P and Z, (Playfair's Spher. Trig. Prop. XXVII); that is, Sin. ZO: Sin. PO=Tang. P : Tang. Z; and therefore, Tang. $Z = \frac{Sin.\ PO \times Tang.\ P}{Sin.\ ZO}$. But, Sin. ZO = Sin. $\overline{PZ - PO}$*=Sin. PO × Cos. PZ—Sin. PZ ×Cos. PO.—Now, since Rad. : Tang. = Sin. : Cosine, and since Cos. : Sin. = Rad. : Tang. we have, by the rule of proportion, Sin. PO= Cos. PO × Tang. PO; and Tang. $PO = \frac{Sin.\ PO}{Cos.\ PO}$

Therefore, $\frac{Sin.\ PO}{Sin.\ ZO} = \frac{Cos.\ PO \times Tang.\ PO}{Sin.\ PO \times Cos.\ PZ - Sin.\ PZ \times Cos.\ PO}$

Dividing by Cos. PO we have.

$\frac{Sin.\ PO}{Sin.\ ZO} = \frac{Tang.\ PO}{\frac{Sin.\ PO \times Cos.\ PZ - Sin.\ PZ}{Cos.\ PO}}$; and since

Fig. 7.

* See Trail's Algebra, Appendix, No. VI, *on the arithmetic of Sines*, Theorem II.

Tang. $PO = \frac{Sin.\ PO}{Cos.\ PO}$, we shall have, by substitution,

$$\frac{Sin.\ PO}{Sin.\ ZO} = \frac{Tang.\ PO}{Tang.\ PO \times Cos.\ PZ - Sin.\ PZ}$$

Again, by Playfair's Spher. Trigon. Prop. XXI, Cos. P : Rad. = Tang. PO : Tang, PS, consequently Tang. PO = Tang. $PS \times$ Cos. P. Substituting, therefore, this new value of Tang. PO in its room, in the last equation, multiplying the whole by Tang. P, and dividing by Tang. PS,* we shall have,

$$\frac{Tang.\ P \times Sin.\ PO}{Sin.\ ZO} = \frac{Cos.\ P \times Tang.\ P}{Cos.\ PZ \times Cos.\ P - Sin.\ PZ \times Cos.\ PS}$$

But since Tang. : Rad. = Cos. : Sin.; Sin. P = Cos. $P \times$ Tang. P. By substituting Sin P in place of its value we shall have Tang. Z, or its equal,

$$\frac{Tang.\ P \times Sin.\ PO}{Sin.\ ZO} = \frac{Sin.\ P}{Cos.\ P \times Cos.\ PZ - Sin.\ PZ \times Cos.\ PS}$$

that is, by substituting the names of the symbols

$$Tang.Z = \frac{Sin.\ Hor.\ Angle}{Cos.Hor.Ang. \times Sin.Lat. - Tang.Dec. \times Cos.Lat.}$$

which is the same expression of the tangent of the sun's azimuth, or angle Z, as was deduced from the former construction.

Its construction.

The analemmatic dial being thus demonstrated, its construction will be better understood by taking an example. Let it be required, therefore, to construct one of these dials for latitude 56 degrees north, which nearly answers to Edinburgh. Let AC (Fig. 3) be taken for half the breadth or radius of the dial, and let it be divided into 1000 parts, then A 12, which must be equal to the sine of the latitude, or 56 degrees, will be 829, which are the three first figures of the

Fig. 3.

* Since the tangents are in the inverse ratio of the cotangents, multiplying any number by the cotangent, is the same as dividing it by the tangent.

natural sine of 56 degrees in a table of sines. In order to find the points *D*, *C*, (Fig. 4) where the stile is to be placed at the solstices on the 21" of June and December, take the tangent of 23° 28′, the sun's declination at that time, and it will be 434, if the radius were *AC* or 1000; but as the radius is the cosine of the latitude, which is 559, we must say as 1000 : 559=434 : 243, the length of *AD* and *AC*. On the 21" of February, April, August, and October, the sun's declination is nearly 11° 19′, the tangent of which for a radius of 1000 is 200; but for a radius of 559, the cosine of the latitude, it will be 112, which is the distance of the stile from *A* on both sides on the 21" of the months already mentioned. On the 21" of January, May, July, and November, the sun's declination is nearly 20° 8′ the tangent of which, for the radius 1000, is 367; but for the radius 559 it will be 205, which is the distance of the stile from *A*, on both sides, on the 21" of these months, the names of the months being inserted beside the points, as in Fig. 2. The horary points are now to be determined in the manner already mentioned,[1] and the dial will be finished. In order to place the dial, we have only to turn it round till the stile of the analemmatic dial indicates the same hour with that of the horizontal one, and it will then be properly placed. Fig. 4.

[1] See p. 491.

DIALING.

DESCRIPTION OF A NEW DIAL IN WHICH THE HOURS ARE AT EQUAL DISTANCES IN THE CIRCUMFERENCE OF A CIRCLE.[x]

Lambert's dial. PLATE XII, Fig. 6.

WITH any radius describe the circle *FXIIB*: draw *AXII* for the meridian, and divide the quadrants *FXII*, *BXII*, each into six equal parts for hours. To the latitude of the place add the half of its complement, or the height of the equator, and the sum will be the inclination of the stile, or the angle *DAC*. Thus, at Edinburgh, the latitude is 55° 58′, the complement of which, or the altitude of the equator, is 34° 2′; the half of which is 17° 1′, being added to 55° 58′, gives 72° 59′ for the inclination of the stile or the angle *DAC*. The position of the stile, in the figure is that which it must have on the 21st of March and September, when the sun crosses the equator; but when the sun has north declination, the point *A* must move towards *D*, and when he is south of the equator, it must move in the opposite direction. In or-

[x] This dial was invented by M. Lambert, and is described and demonstrated in the Ephemerides of Berlin, 1777, p. 200, written in German.

der to find the position of the point *A* for any declination of the sun, multiply together the radius of the dial, the tangent of half the height of the equator at the place for which the dial is constructed, and the tangent of the sun's declination, and the product of these three quantities divided by the square of the radius of the tables, will give the distance of the moveable point *A* from the centre of the circle *FXIIB*.

Let it be required, for example, to find the position of the point *A* on the 21st of December and June, when the declination of the sun is a maximum, or 23° 28′, the radius *AB* of the dial being divided into 100 equal parts.

Log. 100=2.0000000
Log. Tang. 17° 1′=9.4857907
Log. Tang. 23° 28′=9.6376106

Sum 21.1234013=Log. of product.

From this logarithm subtract 20, the logarithm of the square of the radius, and the remainder will be 1.1234013=Log. 13.29.

Take $13\frac{1}{4}$ parts, therefore, in your compasses, and having set them both ways from *A*, the limits of the moveable stile will be marked out.

For any other declination, the position of the point *A* may be found in a similar manner. It will be sufficient in general to determine it for the declination of the sun when he enters each sign, and place these positions on the dial, as represented in Fig. 2. Fig. 2.

The length of the stile *AC*, or its perpendicular height *HC*, must always be of such a size that its shadow may reach the hours in the circle *FXIIB*. For any declination of the sun, its length *AC* may be determined by plain trigonometry. *AXII* is always given, the inclin-

ation of the stile DAC is also known, the angle $AXIIC$ is equal to the sun's meridian altitude, and therefore the whole triangle may be easily found in the common way, or by the following trigonometrical formula:—AC the length of the stile $= \frac{AXII \times \text{Sin. Merid. Alt.}}{\text{Sin. } (180° - \text{Angle of Stile} + \text{Merid. Alt.})}$

Improvement upon it by La Grange.

Notwithstanding the simplicity in the construction of this dial, the motion of the stile is troublesome, and should if possible be avoided. For this purpose the idea first suggested by the celebrated La Grange will be of essential utility. He allows the stile to be fixed in the centre A, and describes with the radius AB, circles upon the different points where the stile is to be placed between A and D, and on the other side of A, which is not marked in the figure. All these circles must be divided equally into hours like the circle $FXIIB$, and when the sun is in the summer solstice, the divisions on the circle nearest the stile are to be used; when he is in the winter solstice, the circle farthest from A must be employed, and the intermediate circles must be used when the sun is in the intermediate points. This advice of La Grange may be adopted also in analemmatic dials.

ASTRONOMY.

ON THE CAUSE OF THE TIDES ON THE SIDE OF THE EARTH OPPOSITE TO THE MOON.

On the cause of the tides opposite the moon.

It has always been reckoned difficult for those unacquainted with physical astronomy, to understand why the sea ebbs and flows on the side of the globe opposite to the moon. This fact, indeed, has frequently been regarded, and sometimes adduced, by the ignorant, as an unsurmountable objection to the Newtonian theory of the tides, in which the rise of the waters is referred to the attraction of the sun and moon. From an anxiety to give a popular explanation of this subject, Mr. Ferguson has been led into an error of considerable importance, in so far as he ascribes the tides on the side of the earth opposite the moon, to the excess of the centrifugal force above the earth's attraction.[1] It cannot be questioned, indeed, that the earth revolves round the common centre of gravity of the earth and moon, at the distance of nearly 6000 miles from that centre; and that the side of the earth opposite the moon has a greater velocity, and con-

[1] See vol. i, p. 48, 49.

sequently a greater centrifugal force than the side next the moon; but as the side of the earth farthest from the moon, is only 10,000 miles from the centre of gravity, it will describe an orbit of 31,415 miles in the space of 27 days 8 hours, or 656 hours, which gives only a velocity of 47 miles an hour, which is too small to create a centrifugal force, capable of raising the waters of the ocean.

PLATE V, Fig. 4. The true cause of the rise of the sea may be understood from Plate V, Fig. 4, where *A B C* is the earth, *O* the common centre of gravity of the earth and moon, round which the earth will revolve in the same manner as if it were acted upon by another body placed in that centre. Let *A M*, *B N*, *C P*, be the directions in which the points *A*, *B*, *C*, would move, if not acted upon by the central body; and let *B b n* be the orbit into which the centre *B* of the earth is deflected from its tangential direction *B N*. Then since the waters at *A* are acted upon by a force, as much less than that which influences the centre of the earth, as the square *O B* is less than the square of *O A*, they cannot possibly be deflected as much from their tangential direction *A M*, as the centre *B* of the earth; that is, instead of describing the orbit *A m*, they will describe the orbit *e a*. In the same manner the waters at *c* being acted upon by a force as much greater than that which influences the centre *B* of the earth, as the square of *O B* exceeds the square of *O C*, will be deflected farther from their tangential direction than the centre of the earth, and instead of describing the orbit *c p*, will describe the orbit *h c i*.

As the earth, therefore, when revolving round the centre of gravity *O*, will be acted upon by

the moon, in the same way as by another body placed in that centre, it will assume an oblate spheroidal form *a b c*; so that the waters at *c* will rise towards the moon, and the waters at *a* will be *left behind*, or will be *less deflected* than the other parts of the earth, by the lunar attraction, from that rectilineal direction in which all revolving bodies, if influenced only by a projectile force, would naturally move.

INDEX TO VOLUME SECOND

A

Absolute fall of water, *app.* - Page 144
Achromatic telescope, *app.* - - 423
——— object glass, double, *app.* - 428
——— tables of their radii, *app.* 436
triple, - - 428
——— tables of their radii, *app.* 431
——— telescopes with four lenses, - 438
——— formulæ for, *app.* - 440
——— eye pieces, - - 444
formulæ for, *app.* 445, 447
Altitude of the sun, to find it by trigonometry, 54
Amontons on friction, *app.* - - 335
Analemmatic dial, *app.* - - - 488
Anemometer, Leslie's, *app.* - - 278
Archimedes's screw engine, - - 113
mode of its operation, *note*, - 114
Azimuth of the sun, to find it by trigonometry, 54, 59

B

Balance, improvement upon it, *app.* - 385
Barker's water mill, without wheel or trundle, 97
——— various improvements upon it, *app.* - 205
——— rules for constructing it, *app.* - 208
Besant's undershot wheel, *app.* - - 203
Bevelled wheels, on the formation of their teeth, *app.* 230
Blakey's hydraulic engine, - - 109
Blowing machine, *app.* - - 415
Breast mills, *app.* - - - 188
Bulfinger on friction, *app.* - - 335

C

Camera obscura, improvement upon it, *app.* 486
——— new portable, *app.* - 487
Capstane, description of a simple and powerful one, *app.* 381
Carriage wheels, *app.* - - 295
——— conical rims disadvantageous in, *app.* 309

Carriage wheels, inclination of spokes disadvantageous, *app.* - - - Page 302
Cassegrainian telescope, *app.* - - 474
——————— table for, *app.* - 475
Centre of gravity, mechanical method of finding it, *app.* 387
Clocks and watches, how to regulate them, - 66
Coulomb on wind mills, *app.* - - 264
——— on friction, *app.* - - - 339
Course of discharge, *app.* - - - 142
——— of impulsion, *app.* - - - ib.
Crane, description of a new and safe one, invented by the author, - - - - 89
Crown wheels, *app.* - - - - 233
Cylindrical sun-dial for shewing the time of the day, the sun's place, and altitude, - - 122
——————— method of using it, - 125

D

Declining dials, - - - - 4
Dial, horizontal, - - - 3, 6, 16
—— vertical, - - - - 4, 6, 9
—— inclining, - - - - 4
—— reclining, - - - ib.
—— declining, - - - ib.
—— erect, direct, south, - - 6, 9
—— erect declining, - - - 10
—— on a card, - - - 19
—— Pardie's universal, - - 22
—— double horizontal, - - - 61
—— Babylonian, - - - ib.
—— Italian, - - - - ib.
—— Analemmatic, *app.* - - 488
—— Lambert's, description of, *app.* - 495
Dials, method of placing them, - - 66
—— to make three on three different planes with one gnomon, - - - - 126
—— universal, on a plain cross, - - 127
——————— by a terrestrial globe, and the shadows of several gnomons at the same time, 130
Dialing-lines, how constructed, - - 17
——— by trigonometry, - - - 42
——— principles and art of, - - 1
——— by the terrestrial globe, - - 5
——— cylinder, universal, - - 118
Dollond's Achromatic eye piece, *app.* - 450
Double microscopes, *app.* - - - 467
——— mills, *app.* - - - 184

E

Eclipses, - - - Page 77, 79
——— limits of, - - - 82
——— period of, - - - ib.
Engine, steam, *app.* - - - 389
Epicycloids, exterior, method of forming them mechanically, *app.* - - - 234
——— ——— geometrically, *app.* 236
interior, *app.* - - - 234
Equation of time, - - - 35
Erect, direct, south dial, - - 6, 9
declining dial, - - 10
Euler on wind mills, *app.* - - 272
——— on friction, *app.* - - 336

F

Finder, a new one for Newtonian telescopes, *app.* 478
Float-boards, number of, *app.* - - 147
——— size of, *app.* - - - ib.
——— position of, *app.* - - 153
Flour mills, improvement upon, *app.* - 203
Fluid microscopes, *app.* - - 483
Grey's, *app.* - - ib.
single, invented by the editor, *app.* 484
——— double, ——— 485
Fluid object glass, Dr. Blair's, *app.* - 443
Fly wheels on the nature and operation of, *app.* 353
——— how they become regulators of machinery, *app.* - - - ib.
——— how they become accumulators of power, *app.* - - - 357
Friction, how to find the *momentum* of, in wind mills, *app.* - - - - 276
——— nature and effects of, *app.* - 334
——— Amonton's observations upon, *app.* - 335
——— Bulfinger's ——— *app.* - ib.
——— Parent's ——— *app.* - 336
——— Euler's *app.* - ib.
——— Ferguson's *app.* - 337
——— Vince's *app.* - 338
——— Coulomb's *app.* - 339
——— Leslie's ——— *app.* - 345
——— method of diminishing the effects of, *app.* 347
——— wheels, *app.* - - - 348

G

Glass griading, *app.* - - - Page 452
Gregorian telescopes, *app.* - - 472
——————— table for, *app.* - 473
Grey's water microscopes, *app.* - - 483
Grinding lenses, method of, *app.* - - 452
——— specula, ——— *app.* - - 457
Gudgeon's, form and size of, *app.* - - 162

H

Halley's, Dr. period of eclipses, *note*, - 82
Herschel's telescopes, *app.* - - 477, 482
Horizontal dial, how to construct it, - 6, 16
——————— description of, - - 3
——— mills, *app.* - - - 179
Horses, way in which they draw, *app.* - 314
——— power of, *app.* - - - 401
Hour of the day, to find it by trigonometry, - 56
Hydraulic ram, - - 420
Hydraulic engine, Blakey's, - - ib.
Hydrostatical paradox, - - - 100

I

Inclining dials, - - - - 4

L

Lambert's dial, description of, *app.* - 495
Latitude of a place, rules for finding it, - 37
Laywell spring, *note*, - - - 106
Lenses, method of grinding and polishing them, 452
Leslie's anemometer, *app.* - - 271
——— on friction, *app.* - - 345, 378
——— on the construction and effect of machines, *app.* 361
Limits of eclipses, - - - 82
Lunations, table of mean, - - 84

M

Machine, water-blowing, *app.* - - 415
Machines, on the construction and effect of, *app* 361

Machine, thrashing, *app.* - - Page 321
Machine, in place of the common hydrostatical bellows, 104
Man, estimate of his force, *app. note*, - 281
Meridian line, how to draw one, - 68
Microscope, fluid, Grey's, *app.* - 483
——— —— single, invented by the editor, - 484
——— —— double, *app.* - - 485
Microscopes, single, *app.* - - 462
——— ——— tables for, *app.* - 465, 466
——— double, *app.* - - 467
Mill course, on the construction of it, *app.* - 140
Mills, on the performance of undershot, *app.* 163, 194
—— horizontal, *app.* - - 179
—— double, *app.* - - - 184
—— breast, *app.* - - - 188
—— overshot, *app.* - - 192
—— improvement on flour, *app.* - - 203
Millstone, on the formation, size, and velocity, of it, *app.* - - - - - 158
Millwright's tables, description of two on new principles, *app.* - - - - 174, 175
Montgolfier's hydraulic ram, *app.* - - 429

N

New and full moons, how to calculate the mean time of, - - - - 71
Newtonian telescope, *app.* - - 476
———'s, table for their apertures, &c. *app.* 481
——— a new finder for, *app.* - 478
Nonius, *See* Vernier.

O

Overshot wheels, formation of their buckets, *app.* 196
——— velocity of, *app.* - ib.
——— table for, *app.* - - 201
——— Borda's observations upon, *app.* 202
Overshot mills, *app.* - - - 192
——— power of, *app.* - - ib.
——— performance of, *app.* - - 194

P

Paradox, hydrostatical, - - 100
Parent on windmills, *app.* - 267
Parent on friction, *app.* - - - 336

Period of eclipses, - - Page 82
Pivots, form and size of, *app.* - - 162
Precepts for calculating the mean time of new and full moons, - - - - 71
Pump mill, quadruple, - - - 115
Pyrometer, description of an accurate one, - 94

Q

Quadruple pump mill, - - 115

R

Rackwork, method of forming its teeth, *app.* - 241
Rain wind, cause of it, *app.* - - 417
Ram, hydraulic, *app.* - - - 420
Ramsden's achromatic eye piece, *app.* - 450
Reciprocating springs, - - 106
Reclining dials, - - - 4
Reflecting telescopes, *app.* - - 472
——— table for, - 473, 475, 481
Refracting telescopes, *app.* - - 468
——— table for, - - 471
Relative fall of water, *app.* - - - 144

S

Saw mill, *note*, - - - 135
Screw engine, Archimedes's, - - 113
Single microscopes, *app.* - - 462
Smeaton's maxims on undershot mills, *app.* - 286
Smeaton on windmills, *app.* - - 284
Specula, method of casting, grinding, and polishing, *app.* - - - - - 457
Springs, reciprocating, - - - 106
——— Laywell, *note*, - - - ib.
Spur wheel, formation of, *app.* - - 154
Steam engine, *app.* - - - - 389
——— Watt's *app.* - - 391
——— Woolff's improvements on, *app.* 407
——— on the power of, and the method of computing it, *app.* - - - 411

T

Tables of the sun's place and declination - 26
——— for calculating new and full moons and eclipses, 85

Tables of the equation of time, - - Page 32
Table of mean lunations, - - - 84
—— of the number of floatboards in undershot water wheels, according to Pitot, *app.* - 149
—— for millwrights, constructed on new principles, *app*, - - - 174, 175
—— for breast mills, *app.* - - - 190
—— for overshot mills, *app.* - - 201
—— of the velocity of thrashing machines, *app.* 326, 329
—— of the power of thrashing machines, *app* - 333
Tables for achromatic telescopes, *app.* - 436
—— for single microscopes, *app.* - - 465
—— for refracting telescopes, *app.* - - 471
—— for Gregorian telescopes, *app.* - - 473
—— for Cassegrainian telescopes, *app.* - 475
—— for Newtonian telescopes, *app.* - 481
Teeth of wheels, method of forming them, *app.* - 210
———— method of disposing them, *app.* - 234
Teeth of rackwork, method of forming them, *app.* 241
Telescope achromatic, *app.* - - 423
———— refracting, *app.* - - - 468
———— ———— table for, *app.* - 471
———— Gregorian, *app* - - - 472
———— ———— table for, *app.* - - 473
———— Cassegrainian, *app.* - - - 474
———— ———— table for, *app.* - - 475
———— Newtonian, *app.* - - - 476
———— table for, *app.* - 481
———— Herschel's, *app.* - - 477, 482
———— Dollond's, *app.* - - - 434
———— with fluid object glasses, *app.* - 443
Thales's eclipse, - - - - 79
Thrashing machines, *app.* - - - 321
driven by water, *app.* - 323
driven by horses, *app.* - 327
on the power of, *app.* - 332
Tides, on the cause of, *app.* - - - 497
Traction, on the line of, *app.* - - 313
Trundle, formation of, *app.* - - - 154
Turpentine varnish microscope, *app.* - - 484

U

Universal dialing cylinder, - - 118
Undershot water wheels, construction of, *app.* - 139
———— table of the number of floatboards in, according to Pitot, *app.* - - 149
Undershot mills, on the performance of them, *app.* 163, 194

V

Vernier scale, *note*, - - - Page 52
Verrier's windmill, description of, *app.* - 258
Vertical dials, - - - - - 4
Vince on friction, *app.* - - - 338

W

Water, how to measure its velocity, *app.* - 177
Water blowing machine, *app.* - - 415
Water microscopes, *app.* - - - 483
Water wheel, size of, *app.* - - - 147
——— number of floatboards in, *app.* - ib.
——— position of floatboards, *app.* - ib.
Wheels, bevelled, on the formation of their teeth, *app.* 230
Wheels, on the teeth of, *app.* - - 210
Wheels, friction, *app.* - - - 348
——— fly, *app.* - - - - 353
Wheels of carriages, on the advantages of large ones, *app.* - - - 298
——— on the position of, *app.* - 312
Wheel carriages, *app.* - - - 295
——— on the formation of, *app.* - 296
——— how to place the centre of gravity, *app.* - - - - - 317
Whitehurst's machine for raising water, *app.* - 419
Wind, method of finding its velocity, *app.* - 276
——— by Coulomb, *app.* 279
Windmill, description of Verrier's, *app.* - 258
——— those in Holland, *app.* - 265
——— sails, on the formation and position of, *app.* 266
——— angle of their inclination, according to Parent, *app.* - - - 267
——— Euler's theorem concerning, *app.* - 268
——— Euler's observations upon, *app.* - 272
Windmills, table of their power, &c. *app.* - 274
——— horizontal, *app.* - - - 288
——— comparison between vertical and horizontal ones, *app.* - - - - - 289
——— Smeaton's observations on, *app.* - 284
——— Coulomb's ——— *app.* - 265
Wipers of stampers, &c. mode of forming them, *app.* 241

Printed by Mundell, Doig, and Stevenson, Edinburgh.

Just Published, by

Mundell, Doig, & Stevenson, Edinburgh,

and

Longman, Hurst, Rees, & Orme; and T. Ostell, London.

I.

AN INQUIRY into the NATURE and CAUSES of the WEALTH of NATIONS, by ADAM SMITH, F.R.S. LL.D. with a LIFE of the Author, 3 vols 8vo, One Guinea in boards.

ADVERTISEMENT

TO THE PRESENT EDITION OF THIS WORK.

For this Edition an Account of the Life of the Author has been drawn up; and although it cannot be said that any Facts relating to that truly great Man are given, in addition to those which have already appeared, yet a more satisfactory Account, it is presumed, will now be found of his Studies and Doctrines, than has been prefixed to any other Edition of the Inquiry into the nature and causes of the Wealth of Nations.

There are likewise prefixed, a Comparative View of the Doctrines of Smith and the French Economists, and a Method of facilitating the Study of Mr. Smith's Inquiry, by German Garnier, of the National Institute, Translator of this Work into the French language.

The Advantage of some Directions to the Readers of this immortal Work, as it has justly been called, particularly to those who have not previously made the Science of Political Economy their Study, has been generally acknowledged. The following Observations are extracted from a Review which appeared of M. Garnier's Translation.—

'Mr Garnier, in order to facilitate the understanding of his author, has 'laid down the heads of his work in the order in which he conceives they 'ought to have been treated; and no doubt, had the course now sketched 'been followed by Dr. Smith, his book would have been read with more 'pleasure and interest, and his doctrines would have been more easily ap- 'prehended. We are of opinion, therefore, that the arrangement here 'given, or something on the same plan, might be advantageously prefixed 'to a future edition of the original.'—*App. to Monthly Review*, 1802.

II.

The FABLE of the BEES; or, PRIVATE VICES, PUBLIC BENEFITS. With an ESSAY on CHARITY and CHARITY SCHOOLS, and a Search into the NATURE of SOCIETY. Also a Vindication of the Book from the Aspersions contained in a Presentment of the Grand Jury of Middlesex, and an abusive Letter to Lord C—.

" It was Dr. Mandeville who seems to have been at the bottom of all that has been written on this subject, (National Economy) either by Dr. Smith or the French Economists:—That national wealth consists in industry, excited by necessity, natural or luxurious; that the value and perfection of all the subjects of industry depend chiefly on the division of labour; that certain labours or employments are productive, and others unproductive; that it is mechanics or ploughmen that are demanded for national wealth, not men addicted to books, who often tend to make the poorer classes idle, vain, and discontented; that the value of articles depends on their scarcity and plenty. These are the leading principles in Dr. Mandeville's Fable of the Bees. Let any man of candour and common understanding peruse the Fable of the Bees, and the innumerable publications of the Economists, and then say, whether it be not almost certain, that the way was prepared for the inquiries and conclusions of the latter by those of the former. The introduction of the Fable of the Bees into France coincides with the time when the Economists received the impressions of education. As the just mode of investigation in natural philosophy was invented by Englishmen, so also the just mode of investigation in political economy, how to make a people powerful and happy, the most important of all the subjects of reasoning, was also first pointed out by an Englishman. Bacon and Newton were the fathers of legitimate inquiry in natural, and Mandeville in political philosophy. It is not a little astonishing, that the honour due, on this score, to Mandeville, has not been reclaimed before by his countrymen.—*Antijacobin Review, &c.* 1805.